



(43) International Publication Date
6 December 2001 (06.12.2001)

PCT

(10) International Publication Number
WO 01/92342 A2

(51) International Patent Classification⁷: **C08F 4/00**

(21) International Application Number: **PCT/US01/17627**

(22) International Filing Date: **31 May 2001 (31.05.2001)**

(25) Filing Language: **English**

(26) Publication Language: **English**

(30) Priority Data:

60/208,087	31 May 2000 (31.05.2000)	US
60/211,601	15 June 2000 (15.06.2000)	US
60/214,036	23 June 2000 (23.06.2000)	US
60/264,537	25 January 2001 (25.01.2001)	US

(71) Applicant (*for all designated States except US*): **E.I. DU PONT DE NEMOURS AND COMPANY** [US/US]; 1007 Market Street, Wilmington, DE 19898 (US).

(72) Inventors; and

(75) Inventors/Applicants (*for US only*): **WANG, Lin** [US/US]; 112 Brook Run, Hockessin, DE 19707 (US).

HAUPTMAN, Elisabeth [FR/US]; 26 Holly Way, Wilmington, DE 19809 (US). **JOHNSON, Lynda, K.** [US/US]; 707 Burnley Road, Wilmington, DE 19803 (US). **MC-CORD, Elizabeth, F.** [US/US]; 514 Hemlock Drive, Hockessin, DE 19707 (US). **WANG, Ying** [CN/US]; 1347 Wooded Knoll, West Chester, PA 19382 (US). **ITTEL, Steven, D.** [US/US]; 7 Barley Mill Drive, Wilmington, DE 19807 (US).


(74) Agent: **LERMAN, Bart, E.**; E.I. Du Pont De Nemours And Company, Legal Patent Records Center, 1007 Market Street, Wilmington, DE 19898 (US).

(81) Designated States (*national*): AE, AG, AL, AM, AT, AU, AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU, CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM, HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK, LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX, MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL, TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(84) Designated States (*regional*): ARIPO patent (GH, GM, KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European

[Continued on next page]

(54) Title: **CATALYSTS FOR OLEFIN POLYMERIZATION**



(57) Abstract: Transition metal complexes of selected monoanionic phosphine ligands, which also contain a selected Group 15 or 16 (IUPAC) element and which are coordinated to a Group 3 to 11 (IUPAC) transition metal or a lanthanide metal, are po-lymerization catalysts for the (co)polymerization of olefins such as ethylene and α -olefins, and the copolymerization of such olefins with polar group-containing olefins. These and other nickel complexes of neutral and monoanionic bidentate ligands copolymerize ethylene and polar comonomers, especially acrylates, at relatively high ethylene pressures and surprisingly high temperatures, and give good incorporation of the polar comonomers and good polymer productivity. These copolymers are often unique structures, which are described.

WO 01/92342 A2



patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE, IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF, CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

For two-letter codes and other abbreviations, refer to the "Guidance Notes on Codes and Abbreviations" appearing at the beginning of each regular issue of the PCT Gazette.

Published:

- *without international search report and to be republished upon receipt of that report*

TITLE

CATALYSTS FOR OLEFIN POLYMERIZATION

FIELD OF THE INVENTION

Transition metal complexes of selected monoanionic phosphine ligands, which also contain a selected Group 15 or 16 (IUPAC) element and which are coordinated to a Group 3 to 11 (IUPAC) transition metal or a lanthanide metal, are polymerization catalysts for the (co)polymerization of olefins such as ethylene and α -olefins, and the copolymerization of such olefins with polar group-containing olefins. In general, nickel complexes of neutral and monoanionic bidentate ligands copolymerize ethylene and polar comonomers at relatively high ethylene pressures and surprisingly high temperatures.

TECHNICAL BACKGROUND

Polyolefins are very important items of commerce, large quantities of various grades of these polymers being produced annually for a large number of uses, such as packaging films, elastomers and moldings. There are many different methods for making such polymers, including many used commercially, such as free radical polymerization, and many so-called coordination catalysts such as Ziegler-Natta-type and metallocene-type catalysts. Each of these catalyst systems has its advantages and disadvantages, including cost of the polymerization and the particular monomers (co)polymerized, and structure of the polyolefin produced. Due to the importance of polyolefins, new catalyst systems which are economical and/or produce new types of polyolefins are constantly being sought.

U. Klabunde, et al., J. Mol. Cat., vol. 41, p. 123-134 (1987) describes the polymerization of ethylene with nickel complex catalysts having certain phosphorous-oxygen ligands.

The catalysts and processes of this reference are different than those of the present invention.

U. Muller, et al., Angew. Chem. Int. Ed. Eng., vol. 28, p. 1011-1013 report on the interaction of $\text{Ni}(\text{COD})_2$ (COD is cyclooctadiene), ethylene and a phosphorous-oxygen compound which may be a ligand. There is no evidence for polymerization.

K. A. Ostoja Starzewski, et al., Angew. Chem., Intl. Ed. Engl., vol. 26, p. 63 (1987) report on the polymerization of ethylene using certain phosphorous-oxygen ylides and $\text{Ni}(\text{COD})_2$. Ylides are not used herein.

W. Keim, Angew. Chem. Int. Ed. Engl., vol. 22, p. 503 (1983) reports the use of nickel complexes of certain arsenic-oxygen compounds to oligomerize ethylene. Higher molecular weight polymers are not reported.

P. Braunstein, et al., J. Chem. Soc., Dalton Trans., 1996, p. 3571-3574 report that nickel complexes of certain phosphorous-nitrogen compounds oligomerize ethylene to low molecular weight olefins. Higher molecular weight polymers are not reported.

US5714556, US6060569, US6174975 and S. D. Ittel, et al., Chem. Rev., vol. 100, p. 1169-1203 (2000) (and references therein), report the use of transition metal complexes of various phosphorous-containing ligands as catalysts for olefin polymerizations. The catalysts and processes of these references are different than those of the present invention.

One of the advantages of some late transition metal catalysts is that they can incorporate polar comonomers, for example olefinic esters, in copolymerizations with hydrocarbon olefins, especially ethylene. Palladium complexes are particularly noted for this ability, while nickel complexes

often do not copolymerize polar comonomers or do so only very poorly, see for example US5866663.

It has also been discovered that using relatively high temperatures and high hydrocarbon olefin (ethylene) pressures often improves the incorporation of the polar comonomer in the polymer formed as well as increasing the productivity of the polymerization catalyst. This is surprising in view of the observations in the literature that increasing temperatures usually decrease the productivity of many nickel polymerization catalysts, see for instance US6127497 and WO00/50470.

JP-A-11292918 reports the copolymerization of methyl acrylate and ethylene using certain nickel complexes as polymerization catalysts. These polymerization are carried out at low temperatures and pressures, and mostly the incorporation of methyl acrylate is reported to be very low, and the polymers have low branching levels.

A. Michalak, et al., Organometallics, vol. 20, p. 1521-1532 (2001) conclude that, using computational methods, nickel complexes having neutral bidentate ligands such as α -dimines should not copolymerize ethylene and polar comonomers such as methyl acrylate.


Other references of interest concerning transition metal complexes and/or their use as polymerization catalysts are Keim, Organometallics, vol. 2, p. 594 (1983); I. Hirose, et al., J. Mol. Cat., vol. 73, p. 271 (1992); and R. Soula, et al., Macromolecules, vol. 34, p. 2438-2442. None of the complexes or processes with them are claimed herein.

Other references of interest concerning polar copolymers include US3481908, US3278495 and M. M. Marques, et al., Poly. Int., 50, 579-587 (2001).


All of the above publications are incorporated by reference herein for all purposes as if fully set forth.

SUMMARY OF THE INVENTION


This invention concerns a "first" process for the polymerization of olefins, comprising the step of contacting, at a temperature of about -100°C to about +200°C, at least one polymerizable olefin with an active polymerization catalyst comprising a Group 3 through 11 (IUPAC) transition metal or a lanthanide metal complex of a ligand of the formula (I), (II) or (XII)



(I)



(II)



(XII)

wherein:

R^1 and R^2 are each independently hydrocarbyl, substituted hydrocarbyl or a functional group;

Y is $CR^{11}R^{12}$, $S(T)$, $S(T)_2$, $P(T)Q$, NR^{36} or $NR^{36}NR^{36}$;

X is O , CR^5R^6 or NR^5 ;

A is O , S , Se , N , P or As ;

Z is O , Se , N , P or As ;

each Q is independently hydrocarbyl or substituted hydrocarbyl;

R^3 , R^4 , R^5 , R^6 , R^{11} and R^{12} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R^7 is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group, provided that when Z is O or Se , R^7 is not present;

R⁸ and R⁹ are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R¹⁰ is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

5 each T is independently =O or =NR³⁰;

R³⁰ is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R³¹ and R³² are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

10 R³³ and R³⁴ are each independently hydrocarbyl or substituted hydrocarbyl, provided that each is independently an aryl substituted in at least one position vicinal to the free bond of the aryl group, or each independently has an E_s of -1.0 or less;

15 R³⁵ is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group, provided that when A is O, S or Se, R³⁵ is not present;

each R³⁶ is independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

20 m is 0 or 1;

s is 0 or 1;

n is 0 or 1; and

q is 0 or 1;

and provided that:




25 any two of R³, R⁴, R⁵, R⁶, R⁸, R⁹, R¹¹ and R¹² bonded to the same carbon atom taken together may form a functional group;

30 any two of R¹, R², R³, R⁴, R⁵, R⁶, R⁷, R⁸, R⁹, R¹¹, R¹², R³¹, R³², R³³, R³⁴, R³⁵ and R³⁶ bonded to the same atom or vicinal to one another taken together may form a ring; and

when said ligand is (I), Y is C(O), Z is O, and R¹ and R² are each independently hydrocarbyl, then R¹ and R² are each independently an aryl substituted in one position vici-

nal to the free bond of the aryl group, or R^1 and R^2 each independently have an E_s of -1.0 or less.

Also described herein is a "second" process for the polymerization of olefins, comprising the step of contacting,
 5 at a temperature of about -100°C to about $+200^\circ\text{C}$, at least one polymerizable olefin with a compound of the formula (IV), (V) or (XIII)



wherein R^1 , R^2 , R^3 , R^4 , R^5 , R^6 , R^7 , R^8 , R^9 , R^{10} , R^{11} , R^{12} , R^{30} , R^{31} , R^{32} , R^{33} , R^{34} , R^{35} , R^{36} , Y , X , A , Z , Q , T , m , s , n and q are as defined above;

15 M is a Group 3 through Group 11 transition metal or a lanthanide metal; and

L^1 is a monodentate monoanionic ligand into which an ethylene molecule may insert between L^1 and M , and L^2 is a monodentate neutral ligand which may be displaced by ethylene or an empty coordination site, or L^1 and L^2 taken together are a monoanionic bidentate ligand into which ethylene may insert between said monoanionic bidentate ligand and said nickel atom, and each L^3 is independently a monoanionic ligand and z is the oxidation state of M minus 2;

25 and provided that;

any two of R^3 , R^4 , R^5 , R^6 , R^8 , R^9 , R^{11} and R^{12} bonded to the same carbon atom taken together may form a functional group;

any two of R^1 , R^2 , R^3 , R^4 , R^5 , R^6 , R^7 , R^8 , R^9 , R^{11} , R^{12} ,
5 R^{31} , R^{32} , R^{33} , R^{34} , R^{35} and R^{36} bonded to the same atom or vicinal to one another taken together may form a ring; and

when said compound is (IV), Y is C(O), Z is O, and R^1 and R^2 are each independently hydrocarbyl, then R^1 and R^2 are each independently an aryl substituted in one position vicinal to the free bond of the aryl group, or R^1 and R^2 each independently have an E_s of -1.0 or less.

In the above-mentioned processes, (IV), (V) and (XIII) and/or the transition metal complexes of (I), (II) or (XII) may in and of themselves be active catalysts, or may be "activated" by contact with a cocatalyst/activator as further
15 described below.

The present invention also concerns the ligands of the formulas (I), (II) and (XII) above, transition metal complexes thereof, and polymerization catalyst components comprising these transition metal complexes.

Also disclosed herein is a "third" process for forming an ethylene/polar monomer copolymer, comprising the step of contacting, under polymerizing conditions, a nickel complex of a bidentate neutral ligand or a bidentate monoanionic ligand, with a monomer component comprising one or more hydrocarbon olefins and one or more polar comonomers (and other optional components such as, for example, one or more cocatalysts and/or other additives), at a temperature of about 60°C to about 170°C, provided that when CO is present, at
25
30 least one other polar monomer is present.

This third process also relates to an improved process for forming an ethylene/polar monomer copolymer, said process comprising the step of contacting, under polymerizing

conditions, a transition metal complex of a bidentate neutral ligand or a bidentate monoanionic ligand, with a monomer component comprising one or more hydrocarbon olefins and one or more polar comonomers (and other optional components such as, for example, one or more cocatalysts and/or other additives), wherein the improvement comprises that the transition metal is nickel, and that the monomer component and complex are contacted at a temperature of about 60°C to about 170°C, provided that when CO is present, at least one other polar monomer is present.

This invention further concerns a "first" polymer, consisting essentially of repeat units derived from ethylene, and one or more polar olefins of the formula $H_2C=CHC(O)R^{32}$, wherein R^{32} is $-OR^{34}$ or any group readily derivable from it, and R^{34} is hydrocarbyl or substituted hydrocarbyl, wherein:

said polymer contains "first branches" of the formula $-(CH_2)_nCH_3$ and "second branches" of the formula $-(CH_2)_mC(O)R^{32}$, wherein m and n are independently zero or an integer of 1 or more; and

said polymer has the following structural characteristics:

(a) one or both of:

(1) the ratio of first branches wherein n is 0 to first branches wherein n is 1 is about 3.0 or more; and

(2) the ratio of first branches wherein n is 0 to first branches wherein n is 3 is 1.0 or more; and

(b) one or both of:

(1) the total number of first branches in which n is 0, 1, 2 and 3 in said polymer is about 10 or more per 1000 CH_2 groups; and

(2) the incorporation of repeat units derived from $H_2C=CHC(O)R^{32}$ is 0.3 mole percent or more based on

the total repeat units derived from the hydrocarbonolefin and $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$.

This invention also concerns a "second" polymer, consisting essentially of repeat units derived from:

5 one or more hydrocarbon olefins, such as ethylene, and one or more polar olefins of the formula $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$, wherein R^{32} is $-\text{OR}^{34}$, or any group readily derivable from it, and R^{34} is hydrocarbyl or substituted hydrocarbyl;

10 wherein in said polymer incorporation of repeat units derived from $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$ is 0.3 mole percent or more based on the total repeat units; and

wherein said polymer has one or both of the following structural characteristics:

15 at least 5 mole percent of said repeat units derived from $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$ are present in said polymer as end groups; and

said end groups are at least 0.001 mole percent of the total repeat units in said polymer;

and provided that said end groups have the formula

20 ----- $\text{HC}=\text{CH}-\text{C}(\text{O})-\text{R}^{32}$

wherein ----- is the remainder of the polymer chain of said end group.

This invention still further concerns a "third" polymer, consisting essentially of:

25 repeat units derived from ethylene;

repeat units derived from one or more monomers of the formula $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$, wherein each R^{32} is independently $-\text{OR}^{34}$ or any group readily derivable from it, and each R^{34} is independently hydrocarbyl or substituted hydrocarbyl, and

30 repeat units derived from one or more alpha-olefins of formulas $\text{H}_2\text{C}=\text{CH}-(\text{CH}_2)_t-\text{H}$ and/or $\text{H}_2\text{C}=\text{CH}-\text{R}^{75}-\text{G}$, wherein t is an integer of 1 to 20, R^{75} is alkylene or substituted alkylene, and G is an inert functional group.

These and other features and advantages of the present invention will be more readily understood by those of ordinary skill in the art from a reading of the following detailed description. It is to be appreciated that certain features of the invention which are, for clarity, described below in the context of separate embodiments, may also be provided in combination in a single embodiment. Conversely, various features of the invention which are, for brevity, described in the context of a single embodiment, may also be provided separately or in any subcombination.

BRIEF DESCRIPTION OF THE DRAWINGS

Figure 1 shows the ^{13}C NMR of a copolymer of ethylene and 2-phenoxyethyl acrylate (EGPEA) which also contains some homopolymer of EGPEA, and which shows assignments of various NMR peaks.

Figure 2 shows the ^{13}C NMR of a copolymer of ethylene and hexyl acrylate (HA) which also contains some homopolymer of HA, and which shows assignments of various NMR peaks.

Figure 3 shows the ^{13}C NMR of a copolymer of ethylene and methyl acrylate (MA) which also contains some homopolymer of MA, and which shows assignments of various NMR peaks. Also shown are formulas for calculations of the amount of homopolymer present and the amount of MA incorporated in the copolymer.

DETAILED DESCRIPTION OF THE PREFERRED EMBODIMENTS

Herein, certain terms are used. Some of them are:

A "hydrocarbyl group" is a univalent group containing only carbon and hydrogen. As examples of hydrocarbyls may be mentioned unsubstituted alkyls, cycloalkyls and aryls.

If not otherwise stated, it is preferred that hydrocarbyl groups (and alkyl groups) herein contain 1 to about 30 carbon atoms.

By "substituted hydrocarbyl" herein is meant a hydrocarbyl group that contains one or more substituent groups which are inert under the process conditions to which the compound containing these groups is subjected (e.g., an inert functional group, see below). The substituent groups also do not substantially detrimentally interfere with the polymerization process or operation of the polymerization catalyst system. If not otherwise stated, it is preferred that substituted hydrocarbyl groups herein contain 1 to about 30 carbon atoms. Included in the meaning of "substituted" are chains or rings containing one or more heteroatoms, such as nitrogen, oxygen and/or sulfur, and the free valence of the substituted hydrocarbyl may be to the heteroatom. In a substituted hydrocarbyl, all of the hydrogens may be substituted, as in trifluoromethyl.

By "(inert) functional group" herein is meant a group other than hydrocarbyl or substituted hydrocarbyl that is inert under the process conditions to which the compound containing the group is subjected. The functional groups also do not substantially interfere with any process described herein that the compound in which they are present may take part in. Examples of functional groups include halo (fluoro, chloro, bromo and iodo), and ether such as $-OR^{22}$ wherein R^{22} is hydrocarbyl or substituted hydrocarbyl. In cases in which the functional group may be near a transition metal atom the functional group should not coordinate to the metal atom more strongly than the groups in those compounds are shown as coordinating to the metal atom, that is they should not displace the desired coordinating group.

By a "cocatalyst" or a "catalyst activator" is meant a compound that reacts with a transition metal compound to form an activated catalyst species. One such catalyst activator is an "alkyl aluminum compound" which, herein, is

meant a compound in which at least one alkyl group is bound to an aluminum atom. Other groups such as, for example, alkoxide, hydride and halogen may also be bound to aluminum atoms in the compound.


5 By "neutral Lewis base" is meant a compound, which is not an ion, that can act as a Lewis base. Examples of such compounds include ethers, amines, sulfides and organic nitriles.

10 By "neutral Lewis acid" is meant a compound, which is not an ion, that can act as a Lewis acid. Examples of such compounds include boranes, alkylaluminum compounds, aluminum halides and antimony [V] halides.

15 By "cationic Lewis acid" is meant a cation that can act as a Lewis acid. Examples of such cations are lithium, sodium and silver cations.

20 By an "empty coordination site" is meant a potential coordination site on a transition metal atom that does not have a ligand bound to it. Thus if an olefin molecule (such as an ethylene molecule) is in the proximity of the empty coordination site, the olefin molecule may coordinate to the metal atom.

25 By a "ligand into which an olefin molecule may insert between the ligand and a metal atom", or a "ligand that may add to an olefin", is meant a ligand coordinated to a metal atom which forms a bond (L-M) into which an olefin molecule (or a coordinated olefin molecule) may insert to start or continue a polymerization. For instance, with ethylene this may take the form of the reaction (wherein L is a ligand):



30 By a "ligand which may be displaced by an olefin" is meant a ligand coordinated to a transition metal which, when

exposed to the olefin (such as ethylene), is displaced as the ligand by the olefin.

By a "monoanionic ligand" is meant a ligand with one negative charge.

5 By a "neutral ligand" is meant a ligand that is not charged.


By "aryl" is meant a monovalent aromatic group in which the free valence is to the carbon atom of an aromatic ring. An aryl may have one or more aromatic rings which may be
10 fused, connected by single bonds or other groups.

By "substituted aryl" is meant a monovalent aromatic group substituted as set forth in the above definition of "substituted hydrocarbyl". Similar to an aryl, a substituted aryl may have one or more aromatic rings which may be
15 fused, connected by single bonds or other groups; however, when the substituted aryl has a heteroaromatic ring, the free valence in the substituted aryl group can be to a heteroatom (such as nitrogen) of the heteroaromatic ring instead of a carbon.

20 By "aryl substituted in at least one position vicinal to the free bond of the aryl group," is meant the bond to one of the carbon atoms next to the free valence of the aryl group is something other than hydrogen. For example for a phenyl group, it would mean the 2 position of the phenyl
25 group would have something other than hydrogen attached to it. A 1-naphthyl group already has something other than hydrogen attached to one of the vicinal carbon atoms at the fused ring junction, while a 2-naphthyl group would have to be substituted in either the 1 or 3 positions to meet this
30 limitation. A preferred aryl substituted in at least one position vicinal to the free bond of the aryl group is a phenyl group substituted in the 2 and 6 positions, and optionally in the other positions.


"Alkyl group" and "substituted alkyl group" have their usual meaning (see above for substituted under substituted hydrocarbyl). Unless otherwise stated, alkyl groups and substituted alkyl groups preferably have 1 to about 30 carbon atoms.

By a "styrene" herein is meant a compound of the formula




wherein R^{43} , R^{44} , R^{45} , R^{46} and R^{47} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group, all of which are inert in the polymerization process. It is preferred that all of R^{43} , R^{44} , R^{45} , R^{46} and R^{47} are hydrogen. Styrene (itself) is a preferred styrene.

By a "norbornene" is meant a compound of the formula



wherein R^{40} is hydrogen or hydrocarbyl containing 1 to 20 carbon atoms. It is preferred that R^{40} is hydrogen or alkyl, more preferably hydrogen or n-alkyl, and especially preferably hydrogen. The norbornene may be substituted by one or more hydrocarbyl, substituted hydrocarbyl or functional groups in the R^{40} or other positions, with the exception of the vinylic hydrogens, which remain. Norbornene (itself), dimethyl endo-norbornene-2,3-dicarboxylate and t-butyl 5-norbornene-2-carboxylate are preferred norbornenes, with norbornene (itself) being especially preferred.

By a " π -allyl group" is meant a monoanionic ligand comprised of 1 sp^3 and two sp^2 carbon atoms bound to a metal center in a delocalized η^3 fashion indicated by



5 The three carbon atoms may be substituted with other hydrocarbyl groups or functional groups.

"Vinyl group" has its usual meaning.

By a "hydrocarbon olefin" is meant an olefin containing only carbon and hydrogen.

10 By a "polar (co)monomer" or "polar olefin" is meant an olefin which contains elements other than carbon and hydrogen. In a "vinyl polar comonomer," the polar group is attached directly to a vinylic carbon atom, as in acrylic monomers. When copolymerized into a polymer the polymer is
15 termed a "polar copolymer". Useful polar comonomers are found in US5866663, WO9905189, WO9909078 and WO9837110, and S. D. Ittel, et al., Chem. Rev., vol. 100, p. 1169-1203(2000), all of which are incorporated by reference herein for all purposes as if fully set forth. Also
20 included as a polar comonomer is CO (carbon monoxide).

By a "bidentate" ligand is meant a ligand which occupies two coordination sites of the same transition metal atom in a complex.

By "under polymerization conditions" is meant the conditions
25 for a polymerization that are usually used for the particular polymerization catalyst system being used. These conditions include things such as pressure, temperature, catalyst and cocatalyst (if present) concentrations, the type of process such as batch, semibatch, continuous, gas
30 phase, solution or liquid slurry etc., except as modified by conditions specified or suggested herein. Conditions normally done or used with the particular polymerization cata-

lyst system, such as the use of hydrogen for polymer molecular weight control, are also considered "under polymerization conditions". Other polymerization conditions such as presence of hydrogen for molecular weight control, other polymerization catalysts, etc., are applicable with this polymerization process and may be found in the references cited herein.

By "E_s" is meant a parameter to quantify steric effects of various groupings, see R. W. Taft, Jr., J. Am. Chem. Soc., vol. 74, p. 3120-3128 (1952), and M.S. Newman, Steric Effects in Organic Chemistry, John Wiley & Sons, New York, 1956, p. 598-603, which are both hereby included by reference. For the purposes herein, the E_s values are those described for o-substituted benzoates in these publications. If the value of E_s for a particular group is not known, it can be determined by methods described in these references.

The transition metals preferred herein in the first and second processes are in Groups 3 through 11 of the periodic table (IUPAC) and the lanthanides, especially those in the 4th, 5th, 6th and 10th periods. Suitable transition metals include Ni, Pd, Cu, Pt, Fe, Co, Ti, Zr, V, Hf, Cr, Ru, Rh and Re, with Ni, Ti, Zr, Cu and Pd being more preferred, and Ni, Ti and Zr being especially preferred. Preferred oxidation states for some of the transition metals are Ni[II], Ti[IV], Zr[IV], and Pd[II].

For ligand (I), Table 1 gives preferred structures. For ligand (II), Table 2 gives preferred structures. In both tables, H is hydrogen, HC is hydrocarbyl, SHC is substituted hydrocarbyl and FG is functional group.

Table 1

m	n	X	Z	R ³	R ⁴	R ⁵	R ⁶	R ⁷	R ¹¹	R ¹²
Zero	Zero		N					HC, SHC	HC, SHC	H, HC, SHC
Zero	Zero		O						HC, SHC	HC, SHC, FG
Zero	1		O	H	H				HC, SHC, FG	HC, SHC, FG
Zero	1		N	H	H			HC, SHC	H, HC, SHC, FG	H, HC, SHC, FG
Zero	1		S	H	H				HC, SHC, FG	HC, SHC, FG
1	Zero	O	O			H, HC, SHC	H, HC, SHC		H, HC, SHC	H, HC, SHC
1	1	CR ⁵ R ⁶	O	H, HC, SHC	H, HC, SHC	H	H		H, HC, SHC	H, HC, SHC
1	1	CR ⁵ R ⁶	N	H, HC, SHC	H, HC, SHC	H	H	HC, SHC	H, HC, SHC	H, HC, SHC

Table 2

q	R ⁸	R ⁹	R ¹⁰
Zero			HC, SHC
1	H, HC	H, HC	HC, SHC

5 In all preferred (I) and (II) (and by reference corresponding structures (IV) and (V), respectively), R¹ and R² are t-butyl, aryl or substituted aryl, more preferably t-butyl, and 2,6-disubstituted phenyl, especially 2,6-dimethoxyphenyl. It is believed that in most of the ligands
10 it is preferred that R¹ and R² be relatively sterically bulky groups, for example t-butyl. Thus, for instance, 2,6-dimethylphenyl would often be favored over phenyl for R¹ and R². Thus R¹ and R² may, for example, be isopropyl, phenyl, substituted phenyl, aryl, substituted aryl, cyclohexyl, t-
15 butyl or 2-octyl. In another preferred form, R¹ and R² are independently aryl substituted in one position vicinal to the free bond of the aryl group, or R¹ and R² each independently have an E_s of -1.0 or less, or both. By both means they may be aryl substituted in one position vicinal to the

free bond of the aryl group, and also have an E_s of -1.0 or less.

Any two of R^3 , R^4 , R^5 , R^6 , R^8 , R^9 , R^{11} and R^{12} bonded to the same carbon atom taken together may form a functional group. By this is meant, for instance, two of these bonds may form part of an oxo (keto) group, $=O$, or an imino $=N-R$, wherein R is hydrocarbyl group. Preferred types of functional groups (single or double bonded) include oxo, $-C(O)R^{13}$ and $-CO_2R^{13}$, wherein R^{13} is hydrocarbyl or substituted hydrocarbyl.

In (I) or (IV) the following structures are preferred:

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

the transition metal is Ti, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

the transition metal is Zr, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} is hydrogen, R^{12} is hydrocarbyl or substituted hydrocarbyl, and Z is N; or

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is O; or

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is N; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =N-silyl, Z is N and R⁷ is silyl; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O, Z is N, and R⁷ is hydrocarbyl or substituted hydrocarbyl; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are a ring and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are N-hydrocarbyl- or N-substituted hydrocarbylimino, Z is N and R⁷ is hydrocarbyl or substituted hydrocarbyl; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are sulfo, Z is N and R⁷ is hydrocarbyl or substituted hydrocarbyl.

In (II) or (V), it is preferred that the transition metal is Ni, q is 0 or 1, R⁸ and R⁹ are hydrogen and R¹⁰ is hydrocarbyl or substituted hydrocarbyl.


In (XII) (and by reference corresponding structure (XIII)), R³³ and R³⁴ are preferably t-butyl, aryl (other than phenyl) or substituted aryl, more preferably t-butyl and 2,6-disubstituted phenyl, especially 2,6-dimethoxyphenyl. It is believed that in most of the ligands it is preferred that R³³ and R³⁴ be relatively sterically bulky groups, for example t-butyl. Thus, for instance, 2,6-dimethylphenyl would often be favored over 2-methylphenyl for R³³ and R³⁴. Thus R³³ and R³⁴ may, for example, be isopropyl, aryl (other


than phenyl), substituted aryl, cyclohexyl, t-butyl or 2-octyl. In another preferred form R^{33} and R^{34} are independently aryl substituted in one position vicinal to the free bond of the aryl group, or R^{33} and R^{34} each independently have an E_s of -1.0 or less, or both. By both means they may be aryl substituted in one position vicinal to the free bond of the aryl group, and also have an E_s of -1.0 or less.

As examples of useful groups R^{31} and R^{32} may be mentioned hydrogen, aryl, substituted aryl, oxygen and nitrogen based functional groups and SO_3Na , as well as when R^{31} and R^{32} taken together form a ring, for example, an aromatic or non-aromatic ring, which may include one or more heteroatoms.


Other preferences include when A is O and s is 0.

In (IV), (V) and (XIII), useful groups L^1 include hydrocarbyl and substituted hydrocarbyl (especially phenyl and alkyl, and particularly phenyl, methyl, hydride and acyl). Useful groups for L^2 include phosphine such as triphenylphosphine, nitrile such as acetonitrile, ethers such as ethyl ether, pyridine, and tertiary alkylamines such as triethylamine and TMEDA (N,N,N',N'-tetramethyl-1,2-ethylenediamine). Alternatively L^1 and L^2 taken together may be a π -allyl or π -benzyl group such as





and



wherein R is hydrocarbyl, and π -allyl and π -benzyl groups are preferred.

5 In (IV), (V) and (XIII), when an olefin (such as ethylene) may insert between L^1 and the transition metal atom, and L^2 is an empty coordination site or is a ligand which may be displaced by an olefin (such as ethylene), or L^1 and L^2 taken together are a bidentate monoanionic ligand into which an
10 olefin (such as ethylene) may be inserted between that ligand and the transition metal atom, (IV), (V) and (XIII) may by themselves catalyze the polymerization of an olefin.

Examples of L^1 which form a bond with the metal into which ethylene may insert between it and the transition
15 metal atom are hydrocarbyl and substituted hydrocarbyl, especially phenyl and alkyl, and particularly methyl, hydride and acyl. Ligands L^2 which ethylene may displace include phosphine such as triphenylphosphine, nitrile such as acetonitrile, ether such as ethyl ether, pyridine, tertiary al-
20 kylamines such as TMEDA, and other olefins. Ligands in which L^1 and L^2 taken together are a bidentate monoanionic ligand into which ethylene may insert between that ligand


and the transition metal atom include π -allyl- or π -benzyl-type ligands (in this instance, sometimes it may be necessary to add a neutral Lewis acid cocatalyst such as triphenylborane or tris(pentafluoro-phenyl)borane of a cationic Lewis acid such as Li^+ to initiate the polymerization, see for instance previously incorporated US6174975). For a summary of which ligands ethylene may insert into (between the ligand and transition metal atom) see for instance J. P. Collman, et al., Principles and Applications of Organotransition Metal Chemistry, University Science Books, Mill Valley, CA, 1987, included herein by reference.

If for instance the ligand in the location of L^1 is not a ligand into which ethylene may insert between it and the transition metal atom, it may be possible to add a cocatalyst which may convert it into L^1 a ligand which will undergo such an insertion. Thus if the ligand in the location of L^1 is halo such as chloride or bromide, a carboxylate, acetylacetonate or an alkoxide, it may be converted to hydrocarbyl such as alkyl by use of a suitable alkylating agent such as an alkylaluminum compound, a Grignard reagent or an alkyllithium compound. It may be converted to hydride by use of a compound such as sodium borohydride.

As indicated above, when L^1 and L^2 taken together are a monoanionic bidentate ligand, a cocatalyst (sometimes also called an activator) which is an alkylating or hydriding agent is also typically present in the olefin polymerization. A preferred cocatalyst is an alkylaluminum compound, and useful alkylaluminum compounds include trialkylaluminum compounds such as triethylaluminum, trimethylaluminum and tri-*i*-butylaluminum, alkyl aluminum halides such as diethylaluminum chloride and ethylaluminum dichloride, and aluminoxanes such as methylaluminoxane. More than one such cocatalyst may be used in combination.


Preferred for L^3 are ligands of the type above described for L^1 .

The ligands (I), (II) and (XIII) may be synthesized by a variety of methods, depending on the particular ligand desired. The synthesis of many specific ligands is illustrated in the Examples. Many of these syntheses are accomplished through the use of R_2PLi or R_2PCH_2Li . More generally speaking, the synthesis of various types of ligands is illustrated in the schemes shown below. In these schemes, each R independently represents hydrocarbyl or substituted hydrocarbyl, and each R' independently represent hydrogen, hydrocarbyl or substituted hydrocarbyl.




Scheme 1

In Scheme 1 one may substitute an imine for the ketone R'_2CO and obtain a final product in which Z is nitrogen rather than oxygen. In another variation of Scheme 1 one can react R_2PH with an acrylonitrile, followed by reaction with $R'MgX$ (addition across the nitrile bond) and then $((allyl)NiCl)_2$ to form the 6-membered metallocycle in which Z is nitrogen. To obtain compounds in which Z is not nitrogen or oxygen, one can use analogous compounds containing the appropriate element for Z. As shown in Scheme 2, (II) can exist in isomeric forms, and the formula for any of the forms represents all of the isomeric forms.




Scheme 2

Scheme 2 shows the synthesis of (II). Appropriate substitution (as in all these synthesis schemes) in these compounds may be obtained by using appropriately substituted starting materials.




Scheme 3

Scheme 3 shows the synthesis of 4-membered (or isomeric) metallocycles. Herein by isomeric is meant (and included in the definition of) that 4-membered heterocycles such as those shown in Scheme 3 may also be in the form of bridged dimers and/or oligomers. Z may be changed by using the appropriate starting material.



Scheme 4

Scheme 4 illustrates the synthesis of a 6-membered metallocycle. The corresponding nitrogen compound may be made by using an aziridine as a starting material.



Scheme 5

Scheme 5 illustrates a method for making (I) in which X is -O-. Herein TMEDA is tetramethylethylenediamine.

In Schemes 1-5 above Ni complexes are prepared, and for making late transition metal complexes other than Ni, similar reactions of metal compounds with an appropriate anion may be used to prepare the complex. Useful types of Ni compounds are listed below.

(Ph_3P)₂Ni(Ph)(Cl) which gives as ligands (in addition to (I), (II) or (XIII)) Ph and Ph_3P .

(TMEDA)₂Ni(Ph)(Cl) in the presence of a "trapping ligand" L^2 such as pyridine, which gives as ligands (in addition to (I), (II) or (XIII)) Ph and pyridine.

(Ph_3P)₂NiCl₂ which gives as ligands (in addition to (I), (II) or (XIII)) Cl and Ph_3P .

$((\text{allyl})\text{Ni}(\text{X}))_2$ which gives as a ligand (in addition to (I), (II) or (XII)) π -allyl.

Other useful Ni precursors and methods of synthesis of these types of nickel complexes may also be found in previously incorporated US6060569, US6174975 and S. D. Ittel, et al., Chem. Rev., vol. 100, p. 1169-1203(2000), as well as WO98/42664, and R. H. Grubbs., et al., Organometallics, vol. 17, p. 3149 (1988), which are also incorporated herein by reference for all purposes as if fully set forth.

In preparing early transition metal complexes such as Zr and Ti complexes, the anion may be reacted with a simple metal compound such as a halide, for example ZrCl_4 or TiCl_4 .

Useful monomers (olefins) include hydrocarbon olefins such as ethylene and α -olefins of the formula $\text{H}_2\text{C}=\text{CH}(\text{CH}_2)_t\text{H}$ (III) wherein t is an integer of 1 to 20, a styrene, a norbornene and cyclopentene; and polar comonomers such as CO and polar olefins. Useful polar olefins include those of the formula $\text{H}_2\text{C}=\text{CHR}^{13}\text{E}$, wherein R^{13} is alkylene, alkylidene or a covalent bond, especially $-(\text{CH}_2)_x-$ wherein x is 0 or an integer of 1 to 20 and E is a polar group. Useful polar groups E include $-\text{CO}_2\text{R}^{14}$, $-\text{OC}(\text{O})\text{R}^{14}$, $-\text{CO}_2\text{H}$, $-\text{C}(\text{O})\text{NR}^{14}_2$ and $-\text{OR}^{14}$, and $-\text{CO}_2\text{R}^{14}$ and $-\text{OR}^{14}$ are more preferred, wherein each R^{14} is hydrogen, hydrocarbyl or substituted hydrocarbyl, preferably alkyl or substituted alkyl. For any olefin other than a norbornene, cyclopentene and a styrene, it is preferred that it be copolymerized with ethylene. An especially preferred olefin is ethylene (alone). Typically CO and polar comonomers will be used with a hydrocarbon olefin such as ethylene to form a copolymer, and often when CO is used at least one other polar monomer will also be present.

It will be understood that not every combination of every ligand with every transition metal will polymerize every (type of) olefin or combination of olefins described

herein. For instance, late transition metals are believed to be more efficacious for polymerization of polar olefins than are early transition metals. The structure of the polyolefin produced will also vary with the particular transition metal and ligand chosen. For example late transition metals tend to produce polymers with an unusual branching pattern, while early transition metals give polymers with more "normal" branching patterns. For a description of unusual and normal branching patterns see US5880241, which is incorporated by reference herein for all purposes as if fully set forth. The combinations of ingredients to use in the polymerization and the products produced may be readily determined by experimentation.

It is preferred that the polymer produced by the first and second processes herein have a degree of polymerization (average number of monomer units in a polymer molecule) of at least about 20, more preferably at least about 40, and especially preferably at least about 100.

In the first and second polymerization processes herein, the temperature at which the polymerization is carried out is generally about -100°C to about $+200^{\circ}\text{C}$, preferably about -60°C to about 150°C , and more preferably about -20°C to about 100°C . The pressure of the olefin (if it is a gas) at which the polymerization is carried out is preferably atmospheric pressure to about 275 MPa.

The first and second polymerization processes herein may be run in the presence of various liquids, particularly aprotic organic liquids. The catalyst system, monomer(s), and polymer may be soluble or insoluble in these liquids, but obviously these liquids should not prevent the polymerization from occurring. Suitable liquids include alkanes, cycloalkanes, selected halogenated hydrocarbons, and aromatic hydrocarbons. Specific useful solvents include hex-

ane, toluene, benzene, methylene chloride, chlorobenzene, p-xylene, and 1,2,4-trichlorobenzene.

Cocatalysts such as alkylaluminum compounds and/or boranes and/or other Lewis acids may optionally be present in the first and second processes. It is believed that the presence of certain Lewis acids may enhance the productivity of the catalyst and/or the rate of polymerization of the olefin(s). Also Lewis acids may form so-called Zwitterionic complexes which are also useful in these processes. For an explanation of Zwitterionic complexes, see U.S. Patent Application _____ (filed concurrently on 31 May 2001, Applicant's reference CL1655 US NA) (also filed concurrently on 31 May 2001 as PCT/US01/_____, Applicant's reference CL1655 PCT), which is hereby incorporated by reference herein for all purposes as if fully set forth.

In the third polymerization process described herein one or more polar comonomers are used with one or more hydrocarbon olefins, and preferably ethylene, to form a polar copolymer. Useful polar comonomers include, but are not limited to compounds of the formula $H_2C=CHR^{20}C(O)Y$ (X), $H_2C=CHR^{20}CN$ (XI), $H_2C=CR^{25}C(O)Y$ (XII), or $H_2C=CHR^{20}CCN$, wherein R^{20} is alkylene or substituted alkylene, R^{25} is hydrogen, and Y is $-OH$, $-NR^{21}R^{22}$, $-OR^{23}$, and $-SR^{24}$, wherein R^{21} and R^{22} are each independently hydrogen, hydrocarbyl or substituted hydrocarbyl, R^{23} and R^{24} are each hydrocarbyl or substituted hydrocarbyl, and R^{25} is hydrogen. More generally vinyl polar monomers of the formula $H_2C=CHX$, wherein X is a polar group, are preferred. Other more specific preferred polar comonomers are (X) wherein R^{20} is $-(CH_2)_q-$ wherein q is 0 or an integer of 1 to 20 and Y is $-OR^{23}$, and (XII), wherein it is especially preferred that q is zero. Norbornenes containing functional groups are also useful polar comonomers.




Some of Ni complexes which may contain bidentate ligands and may be useful in the third process herein may be found in JP-A-11158214, JP-A-11158213, JP-A-10017617, JP-A-09255713, JP-A-11180991, JP-A-256414(2000), JP-A-10007718, JP-A-10182679, JP-A-128922(2000), JP-A-10324709, JP-A-344821(2000), JP-A-11292917, JP-A-11181014, WO00/56744, WO96/37522, WO96/37523, WO98/49208, WO00/18776, WO00/56785, WO00/06620, WO99/50320, WO00/68280, WO00/59956, WO00/50475, WO00/50470, WO98/42665, WO99/54364, WO98/33823, WO99/32226, WO99/49969, WO99/15569, WO99/46271, WO98/03521, WO00/59961, DE-A-19929131, US5886224, US5714556, US6060569, US6069110, US6174976, US6103658, US6200925, US5929181, US5932670, US6030917, US4689437, EP-A-0950667 and EP-A-0942010, and S. D. Ittel, et al., Chem. Rev., vol. 100, p. 1169-1203 (2000) (and references therein), all of which are hereby incorporated by reference for all purposes as if fully set forth, as well as the complexes described herein derived from (I), (II) or (XII).


All of the complexes mentioned in these publications, and all nickel complexes of bidentate neutral and mono-anionic ligands, may not in general be catalysts for the copolymerization of ethylene and one or more polar comonomers, but the conditions described herein give a good chance for them to be such catalysts. To determine whether such a complex is a polar olefin copolymerization catalyst, one may simply try a copolymerization of ethylene and a polar comonomer such as methyl acrylate or ethyl-10-undecylenoate under the conditions described herein. These conditions include principally temperature and ethylene pressure. During most polymerizations there are other conditions usually present, such as activation of the polymerization catalyst, exclusion of polymerization catalyst poisons, use of a molecular weight regulating compound such as hydrogen, agitation,

supportation, etc. Except for those conditions specifically described herein for the third polymerization, the other conditions described, for example, in the above references may be used in such test polymerizations and in polymerizations of the third process in general, and reference may be had thereto for further details.

In the third process herein a preferred low temperature is about 80°C, more preferably about 90°C, and a preferred high temperature is about 150°C, more preferably about 130°C. A preferred lower ethylene pressure is about 5 MPa or more. A preferred upper limit on ethylene pressure is about 200 MPa, more preferably about 20 MPa.

Preferred bidentate ligands in the third process herein are:





(XXI)

wherein:

R^{26} and R^{27} are each independently hydrocarbyl or substituted hydrocarbyl, provided that the carbon atom bound to the imino nitrogen atom has at least two carbon atoms bound to it;

R^{28} and R^{29} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl, or R^{28} and R^{29} taken together are hydrocarbylene or substituted hydrocarbylene to form a carbocyclic ring;

R^{60} and R^{61} are each independently functional groups bound to the rest of (XV) through heteroatoms (for example O, S or N), or R^{60} and R^{61} (still containing their heteroatoms) taken together form a ring.

each R^{50} is independently hydrocarbyl or substituted hydrocarbyl;

each R^{51} is independently hydrogen, hydrocarbyl or substituted hydrocarbyl; and

each R^{52} is hydrocarbyl, substituted hydrocarbyl, hydrocarbyloxy, or substituted hydrocarbyloxy.

When (XVI), (XVII) and (XVIII) are used as the complexes, especially as their nickel complexes it is preferred that they be used as their complexes with Lewis acids ("Zwitterionic complexes") such as tris(pentafluorophenyl)borane. These Zwitterionic complexes are sometimes better polymerization catalysts than the complexes which do not contain the Lewis acid. These Zwitterionic compounds may be formed before the complex is added to the polymerization process,

or may be formed in situ by reaction with Lewis acid which is present.

Other copolymerizable olefins may also be present in the third process. α -Olefins of the formula $H_2C=CH(CH_2)_zCH_3$ wherein z is 0 or an integer of 1 to 21, for example propylene or 1-butene, may be used. It is preferred that any other comonomers present constitute less than 50 mole percent, more preferably less than 25 mole percent of the product copolymer.

One problem noted with using some polar comonomers, for example acrylate-type comonomers, under certain conditions is the tendency of these comonomers to form homopolymers. It is believed that these homopolymers arise from a "competitive" free radical-type polymerization "originating" from some free radicals which may be present or generated in the third process polymerization. Some types of polar comonomers such as acrylates are well known to readily undergo such polymerizations. These usually unwanted free radical polymerizations may be suppressed to varying extents by the presence of free radical polymerization inhibitors such as phenothiazine in the third polymerization process, but these may interfere with the desired polymerization process, or cause other problems. This may be particularly acute in the third polymerization process herein because of the relatively high process temperatures. It has been found that the presence of alkali metal or ammonium salts, preferably alkali metal salts, of relatively noncoordinating anions in the third polymerization process retards or eliminates the formation of homopolymer of the polar comonomer (or copolymers containing only polar comonomers if more than one polar comonomer is used). Particularly preferred alkali metal cations are Li, Na and K, and Li and Na are especially preferred. Useful weakly coordinating anions include BAF,

tetrakis(pentafluorophenyl)borate, $N(S(O)_2CF_3)_2^-$, tetraphenylborate, trifluoromethanesulfonate, and hexafluoroantimonate, and preferred anions are BAF, tetrakis(pentafluorophenyl)borate, and $N(S(O)_2CF_3)_2^-$. A useful molar ratio of these salts to the number of moles of Ni compounds present is about 10,000 to about 5 to 1.0, more preferably about 1,000 to about 50 to 1.0. These salts will preferably be used in a third polymerization process in which there is a liquid phase present, for example a polymerization which is a solution or liquid suspension polymerization.

In any of the polymerization processes herein in which a polar comonomer is copolymerized, and any formation of any polar copolymer, it is preferred that the molar ratio of the total of the polar comonomers present to any added Lewis acid is at least 2:1, preferably at least 10:1. Polar comonomers, such acrylic-type monomers, have been copolymerized in certain situations by destroying their Lewis basic (or coordinating) character by reacting them with a Lewis acid, to form a Lewis acid "salt" of the polar comonomer.

While this may often help to form the polar copolymer, later removal of the stoichiometric amount (of polar comonomer) of Lewis acid is difficult and expensive.

The olefin polymerizations herein may also initially be carried out in the "solid state" by, for instance, supporting the transition metal compound on a substrate such as silica or alumina, activating it if necessary with one or more cocatalysts and contacting it with the olefin(s). Alternatively, the support may first be contacted (reacted) with one or more cocatalysts (if needed) such as an alkylaluminum compound, and then contacted with an appropriate Ni compound. The support may also be able to take the place of a Lewis or Bronsted acid, for instance, an acidic clay such as montmorillonite, if needed. Another method of making a

supported catalyst is to start a polymerization or at least make a transition metal complex of another olefin or oligomer of an olefin such as cyclopentene on a support such as silica or alumina. These "heterogeneous" catalysts may be used to catalyze polymerization in the gas phase or the liquid phase. By gas phase is meant that a gaseous olefin is transported to contact with the catalyst particle. For the copolymerization of polar olefins using supported catalysts, especially in a liquid medium, a preferred case is when the ligand is covalently attached to the supports, which helps prevent leaching of the transition metal complex from the support.

In all of the polymerization processes described herein oligomers and polymers of the various olefins are made. They may range in molecular weight from oligomeric olefins, to lower molecular weight oils and waxes, to higher molecular weight polyolefins. One preferred product is a polymer with a degree of polymerization (DP) of about 10 or more, preferably about 40 or more. By "DP" is meant the average number of repeat (monomer) units in a polymer molecule.

Depending on their properties, the polymers made by the first and second processes described herein are useful in many ways. For instance if they are thermoplastics, they may be used as molding resins, for extrusion, films, etc. If they are elastomeric, they may be used as elastomers. If they contain functionalized monomers such as acrylate esters, they are useful for other purposes, see for instance previously incorporated US5880241.

Depending on the process conditions used and the polymerization catalyst system chosen, polymers, even those made from the same monomer(s) may have varying properties. Some of the properties that may change are molecular weight and molecular weight distribution, crystallinity, melting point,

and glass transition temperature. Except for molecular weight and molecular weight distribution, branching can affect all the other properties mentioned, and branching may be varied (using the same transition metal compound) using methods described in previously incorporated US5880241.

It is known that blends of distinct polymers, varying for instance in the properties listed above, may have advantageous properties compared to "single" polymers. For instance it is known that polymers with broad or bimodal molecular weight distributions may be melt processed (be shaped) more easily than narrower molecular weight distribution polymers. Thermoplastics such as crystalline polymers may often be toughened by blending with elastomeric polymers.

Therefore, methods of producing polymers which inherently produce polymer blends are useful especially if a later separate (and expensive) polymer mixing step can be avoided. However in such polymerizations one should be aware that two different catalysts may interfere with one another, or interact in such a way as to give a single polymer.

In such a process the transition metal containing polymerization catalyst disclosed herein can be termed the first active polymerization catalyst. Monomers useful with these catalysts are those described (and also preferred) above. A second active polymerization catalyst (and optionally one or more others) is used in conjunction with the first active polymerization catalyst. The second active polymerization catalyst may be a late transition metal catalyst, for example as described herein, in previously incorporated US5880241, US6060569, US6174975 and US5714556, and/or in US5955555 (also incorporated by reference herein for all purposes as if fully set forth). Other useful types

of catalysts may also be used for the second active polymerization catalyst. For instance so-called Ziegler-Natta and/or metallocene-type catalysts may also be used. These types of catalysts are well known in the polyolefin field, see for instance Angew. Chem., Int. Ed. Engl., vol. 34, p. 1143-1170 (1995), EP-A-0416815 and US5198401 for information about metallocene-type catalysts; and J. Boor Jr., Ziegler-Natta Catalysts and Polymerizations, Academic Press, New York, 1979 for information about Ziegler-Natta-type catalysts, all of which are hereby included by reference. Many of the useful polymerization conditions for all of these types of catalysts and the first active polymerization catalysts coincide, so conditions for the polymerizations with first and second active polymerization catalysts are easily accessible. Oftentimes the "co-catalyst" or "activator" is needed for metallocene or Ziegler-Natta-type polymerizations. In many instances the same compound, such as an alkylaluminum compound, may be used as an "activator" for some or all of these various polymerization catalysts.

In one preferred process described herein the first olefin(s) (the monomer(s) polymerized by the first active polymerization catalyst) and second olefin(s) (the monomer(s) polymerized by the second active polymerization catalyst) are identical, and preferred olefins in such a process are the same as described immediately above. The first and/or second olefins may also be a single olefin or a mixture of olefins to make a copolymer. Again it is preferred that they be identical particularly in a process in which polymerization by the first and second active polymerization catalysts make polymer simultaneously.

In some processes herein the first active polymerization catalyst may polymerize a monomer that may not be polymerized by said second active polymerization catalyst,

and/or vice versa. In that instance two chemically distinct polymers may be produced. In another scenario two monomers would be present, with one polymerization catalyst producing a copolymer, and the other polymerization catalyst producing a homopolymer, or two copolymers may be produced which vary in the molar proportion or repeat units from the various monomers. Other analogous combinations will be evident to the artisan.

In another variation of this process one of the polymerization catalysts makes an oligomer of an olefin, preferably ethylene, which oligomer has the formula $R^{70}CH=CH_2$, wherein R^{70} is n-alkyl, preferably with an even number of carbon atoms. The other polymerization catalyst in the process then (co)polymerizes this olefin, either by itself or preferably with at least one other olefin, preferably ethylene, to form a branched polyolefin. Preparation of the oligomer (which is sometimes called an α -olefin) by a second active polymerization-type of catalyst can be found in previously incorporated US5880241, as well as in WO99/02472 (also incorporated by reference herein).

Likewise, conditions for such polymerizations, using catalysts of the second active polymerization type, will also be found in the appropriate above-mentioned references.

Two chemically different active polymerization catalysts are used in this polymerization process. The first active polymerization catalyst is described in detail above. The second active polymerization catalyst may also meet the limitations of the first active polymerization catalyst, but must be chemically distinct. For instance, it may have a different transition metal present, and/or utilize a different type of ligand and/or the same type of ligand that differs in structure between the first and second active polymerization catalysts. In one preferred process, the ligand

type and the metal are the same, but the ligands differ in their substituents.

Included within the definition of two active polymerization catalysts are systems in which a single polymerization catalyst is added together with another ligand, preferably the same type of ligand, which can displace the original ligand coordinated to the metal of the original active polymerization catalyst, to produce in situ two different polymerization catalysts.

The molar ratio of the first active polymerization catalyst to the second active polymerization catalyst used will depend on the ratio of polymer from each catalyst desired, and the relative rate of polymerization of each catalyst under the process conditions. For instance, if one wanted to prepare a "toughened" thermoplastic polyethylene that contained 80% crystalline polyethylene and 20% rubbery polyethylene, and the rates of polymerization of the two catalysts were equal, then one would use a 4:1 molar ratio of the catalyst that gave crystalline polyethylene to the catalyst that gave rubbery polyethylene. More than two active polymerization catalysts may also be used if the desired product is to contain more than two different types of polymer.

The polymers made by the first active polymerization catalyst and the second active polymerization catalyst may be made in sequence, i.e., a polymerization with one (either first or second) of the catalysts followed by a polymerization with the other catalyst, as by using two polymerization vessels in series. However it is preferred to carry out the polymerization using the first and second active polymerization catalysts in the same vessel(s), i.e., simultaneously. This is possible because in most instances the first and second active polymerization catalysts are compatible with

each other, and they produce their distinctive polymers in the other catalyst's presence. Any of the processes applicable to the individual catalysts may be used in this polymerization process with 2 or more catalysts, i.e., gas phase, liquid phase, continuous, etc.

Catalyst components which include transition metal complexes of (I), (II) or (XII), with or without other materials such as one or more cocatalysts and/or other polymerization catalysts are also disclosed herein. For example, such a catalyst component could include the transition metal complex supported on a support such as alumina, silica, a polymer, magnesium chloride, sodium chloride, etc., with or without other components being present. It may simply be a solution of the transition metal complex, or a slurry of the transition metal complex in a liquid, with or without a support being present.

The polymers produced by this process may vary in molecular weight and/or molecular weight distribution and/or melting point and/or level of crystallinity, and/or glass transition temperature and/or other factors. For copolymers the polymers may differ in ratios of comonomers if the different polymerization catalysts polymerize the monomers present at different relative rates. The polymers produced are useful as molding and extrusion resins and in films as for packaging. They may have advantages such as improved melt processing, toughness and improved low temperature properties.

Hydrogen or other chain transfer agents such as silanes (for example trimethylsilane or triethylsilane) may be used to lower the molecular weight of polyolefin produced in the polymerization process herein. It is preferred that the amount of hydrogen present be about 0.01 to about 50 mole percent of the olefin present, preferably about 1 to about

20 mole percent. When liquid monomers (olefins) are present, one may need to experiment briefly to find the relative amounts of liquid monomers and hydrogen (as a gas). If both the hydrogen and monomer(s) are gaseous, their relative concentrations may be regulated by their partial pressures.

Copolymers of ethylene and certain polar comonomers such as $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$ are described herein (first and second polymers), and they contain first branches of the formula $-(\text{CH}_2)_n\text{CH}_3$ and second branches of the formula $-(\text{CH}_2)_m\text{C}(\text{O})\text{R}^{33}$, wherein R^{32} is $-\text{OR}^{34}$ or any group readily derivable from it, R^{33} is R^{32} or any group readily derivable from it, R^{34} is hydrocarbyl or substituted hydrocarbyl, and each R^{35} is hydrogen, hydrocarbyl or substituted hydrocarbyl. By "any group readily derivable from it" is meant any derivative of a carboxylic acid which is readily interconverted from the carboxylic acid itself or a derivative of a carboxylic acid. For example a carboxylic acid ester may be converted to a carboxylic acid by hydrolysis, an amide by reaction with a primary or secondary amine, a carboxylate salt (for example with an alkali or alkaline earth metal) by hydrolysis and neutralization, an acyl halide by hydrolysis and reaction with a compound such as thionyl chloride, nitriles, and others.

The first and/or second polymers, and/or third polymers in some instances, have the following characteristics in various combinations that separates them from other copolymers made from the same monomers. These characteristics are:

the ratio of first branches wherein n is 0 to first branches wherein n is 1 is about 3.0 or more, preferably about 4.0 or more;

the ratio of first branches wherein n is 0 to first branches wherein n is 3 is 1.0 or more, preferably 1.5 or more;

the ratio of second branches wherein m is 0 to second branches wherein m is one or more is at least about 3.0, more preferably at least about 5.0;

the total number of first branches where n is 0, 1, 2 and 3 in said polymer is about 10 or more per 1000 CH₂ groups, preferably about 20 or more;

the incorporation of repeat units derived from H₂C=CHC(O)R³³ is 0.3 mole percent or more based on the total repeat units derived from ethylene and H₂C=CHC(O)R³³, preferably about 0.5 mole percent or more, especially preferably 1.1 mole percent or more, and very preferably about 1.5 mole percent or more (if there are repeat units in which R³³ varies, the total of such units shall be used);

the polymers have end groups of the formula ~~~~~-HC=CH-C(O)-R³² and at least about 5 mole percent, preferably at least about 10 mole percent, of said monomer incorporated is present in said polymer as end groups of the formula ~~~~~-HC=CH-C(O)-R³³, wherein ~~~~~ is the remainder of the polymer chain of said end group (the polymer chain the end group is attached to); and/or

the said unsaturated end groups are at least 0.001 mole percent, preferably at least about 0.01 mole percent, and more preferably at least 0.1 mole percent, of the total repeat units (ethylene and polar comonomer(s)) in said polymer.

In these polymers any number of these characteristics can be combined as features of these polymers, including the preferred characteristics.

The first, second and third polymers may also contain "saturated" end groups of the formula ~~~~~C(O)R³³, which

with present analytical techniques may be indistinguishable from second branches where m is ≥ 5 . In some instances end groups may have the formula $-----CH=CH_2$ (a vinyl end group). Such end groups may sometimes be polymerizable, and therefore polymers with such end groups may be useful as monomers.

It is difficult, and sometimes not possible, to distinguish between ester groups which are saturated polymer ends (no olefin bond associated with the end group), and ester groups at the ends of long branches by ^{13}C NMR spectroscopy (created by chain walking event, a CWE). In both cases the carbonyl group is shifted from about 175.5 ppm for the in-chain comonomer to 170-174 ppm for the saturated end group or CWE. Usually the saturated ester end group or CWE peak in the region 170-174 ppm is very small and present in only trace quantities. Because of the very low levels of this peak, it is difficult to confirm by 2D NMR this hypothesis, and the assignment should be considered tentative. Review of many of the experimental results obtained show that in many examples no saturated end groups and/or CWE are present. However in some examples up to 50 mole percent, more commonly up to 20 mole percent, of the total amount of acrylate ester appears to be present as saturated end groups and/or CWE. These numbers are very approximate, since the contents of the saturated end groups and/or CWE are typically so small the error in the measurement is relatively large.

Some NMR and separations evidence exists that these copolymers may sometimes be capped by short runs of acrylate homopolymers, presumably by free radical polymerization of acrylate ester at the beginning and/or end of the coordination polymerization of a polymer chain.

The first, second and third polymers are useful in many ways, for instance,

1. Tackifiers for low strength adhesives (U, vol. A1, p. 235-236) are a use for these polymers. Elastomeric and/or relatively low molecular weight polymers are preferred.

2. The polymers are useful as base resins for hot melt adhesives (U, vol. A1, p. 233-234), pressure sensitive adhesives (U, vol. A1, p. 235-236) or solvent applied adhesives. Thermoplastics are preferred for hot melt adhesives. The polymers may also be used in a carpet installation adhesive.

3. Base polymer for caulking of various kinds is another use. An elastomer is preferred. Lower molecular weight polymers are often used.

4. The polymers, particularly elastomers, may be used for modifying asphalt, to improve the physical properties of the asphalt and/or extend the life of asphalt paving, see US3980598.

5. Wire insulation and jacketing may be made from any of the polymers (see EPSE, vol. 17, p. 828-842). In the case of elastomers it may be preferable to crosslink the polymer after the insulation or jacketing is formed, for example by free radicals.

6. The polymers, especially the branched polymers, are useful as base resins for carpet backing, especially for automobile carpeting.

7. The polymers may be used for extrusion or coextrusion coatings onto plastics, metals, textiles or paper webs.

8. The polymers may be used as a laminating adhesive for glass.

9. The polymers are useful for blown or cast films or as sheet (see EPSE, vol. 7 p. 88-106; ECT4, vol. 11, p. 843-856; PM, p. 252 and p. 432ff). The films may be single

layer or multilayer, the multilayer films may include other polymers, adhesives, etc. For packaging the films may be stretch-wrap, shrink-wrap or cling wrap. The films are useful for many applications such as packaging foods, geomembranes and pond liners. It is preferred that these polymers have some crystallinity.

10. The polymers may be used to form flexible or rigid foamed objects, such as cores for various sports items such as surf boards and liners for protective headgear. Structural foams may also be made. It is preferred that the polymers have some crystallinity. The polymer of the foams may be crosslinked.

11. In powdered form the polymers may be used to coat objects by using plasma, flame spray or fluidized bed techniques.

12. Extruded films may be formed from these polymers, and these films may be treated, for example drawn. Such extruded films are useful for packaging of various sorts.

13. The polymers, especially those that are elastomeric, may be used in various types of hoses, such as automotive heater hose.

14. The polymers may be used as reactive diluents in automotive finishes, and for this purpose it is preferred that they have a relatively low molecular weight and/or have some crystallinity.

15. The polymers can be converted to ionomers, which when they possess crystallinity can be used as molding resins. Exemplary uses for these ionomeric molding resins are golf ball covers, perfume caps, sporting goods, film packaging applications, as tougheners in other polymers, and usually extruded) detonator cords.

16. The functional groups on the polymers can be used to initiate the polymerization of other types of monomers or

to copolymerize with other types of monomers. If the polymers are elastomeric, they can act as toughening agents.

17. The polymers can act as compatibilizing agents between various other polymers.

5 18. The polymers can act as tougheners for various other polymers, such as thermoplastics and thermosets, particularly if the olefin/polar monomer polymers are elastomeric.

10 19. The polymers may act as internal plasticizers for other polymers in blends. A polymer which may be plasticized is poly(vinyl chloride).

20. The polymers can serve as adhesives between other polymers.

15 21. With the appropriate functional groups, the polymers may serve as curing agents for other polymers with complementary functional groups (i.e., the functional groups of the two polymers react with each other).

22. The polymers, especially those that are branched, are useful as pour point depressants for fuels and oils.

20 23. Lubricating oil additives as Viscosity Index Improvers for multigrade engine oil (ECT3, Vol 14, p. 495-496) are another use. Branched polymers are preferred. Ethylene copolymer with acrylates or other polar monomers will also function as Viscosity Index Improvers for multigrade engine
25 oil with the additional advantage of providing some dispersancy.

24. The polymers may be used for roofing membranes.

25. The polymers may be used as additives to various molding resins such as the so-called thermoplastic olefins
30 to improve paint adhesion, as in automotive uses.

26. A flexible pouch made from a single layer or multi-layer film (as described above) which may be used for packaging various liquid products such as milk, or powder such

as hot chocolate mix. The pouch may be heat sealed. It may also have a barrier layer, such as a metal foil layer.

27. A wrap packaging film having differential cling is provided by a film laminate, comprising at least two layers; an outer reverse which is a polymer (or a blend thereof) described herein, which contains a tackifier in sufficient amount to impart cling properties; and an outer obverse which has a density of at least about 0.916 g/mL which has little or no cling, provided that a density of the outer reverse layer is at least 0.008 g/mL less than that of the density of the outer obverse layer. It is preferred that the outer obverse layer is linear low density polyethylene, and the polymer of the outer obverse layer have a density of less than 0.90 g/mL. All densities are measured at 25°C.

28. Fine denier fibers and/or multifilaments. These may be melt spun. They may be in the form of a filament bundle, a non-woven web, a woven fabric, a knitted fabric or staple fiber.

29. A composition comprising a mixture of the polymers herein and an antifogging agent. This composition is especially useful in film or sheet form because of its antifogging properties.

30. If the polymers are functionalized with monomers such as fluoroalkyl acrylate esters or other fluorine-containing monomers, they are useful for selectively imparting surface activity to polyolefins. This would be of use reducing fluid penetration in flash-spun polyolefin films for medical and other applications. The fluoro-functionalized polyolefins would also be useful for dispersing fluoropolymers in lubricant applications.

31. Mixtures of ethylene homopolymers or oligomers together with copolymers of ethylene and acrylates and optionally other monomers are useful as adhesion promoters, sur-

face active agents, tougheners, and compatibilizers for additives.

In the above use listings, sometimes a reference is given which discusses such uses for polymers in general.

5 All of these references are hereby included by reference. For the references, "U" refers to W. Gerhartz, et al., Ed., Ullmann's Encyclopedia of Industrial Chemistry, 5th Ed. VCH Verlagsgesellschaft mBH, Weinheim, for which the volume and page number are given, "ECT3" refers to the H. F. Mark, et
10 al., Ed., Kirk-Othmer Encyclopedia of Chemical Technology, 4th Ed., John Wiley & Sons, New York, "ECT4" refers to the J. I Kroschwitz, et al., Ed., Kirk-Othmer Encyclopedia of Chemical Technology, 4th Ed., John Wiley & Sons, New York, for which the volume and page number are given, "EPSE" re-
15 fers to H. F. Mark, et al., Ed., Encyclopedia of Polymer Science and Engineering, 2nd Ed., John Wiley & Sons, New York, for which volume and page numbers are given, and "PM" refers to J. A. Brydson, ed., Plastics Materials, 5th Ed., Butterworth-Heinemann, Oxford, UK, 1989, and the page is
20 given.

In the Examples, all pressures are gauge pressures. The following abbreviations are used:

ΔH_f - heat of fusion (in J/g)

BAF - tetrakis(bis-3,5-(trifluoromethyl)phenyl)borate

25 DSC - differential scanning calorimetry

GPC - gel permeation chromatography

PMAO-IP - improved processing methylaluminoxane from Akzo-Nobel

RB - round-bottomed

30 RT - room temperature

TCB - 1,2,4-trichlorobenzene

THF - tetrahydrofuran

Am - amyl

- Ar - aryl
BAF - tetrakis(3,5-trifluoromethylphenyl)borate
BArF - tetrakis(pentafluorophenyl)borate
BHT - 2,6-di-t-butyl-4-methylphenol
5 Bu - butyl
Bu₂O - dibutyl ether
CB - chlorobenzene
Cmpd - compound
E - ethylene
10 EG - end-group, refers to the ester group of the acrylate being located in an unsaturated end group of the ethylene copolymer
EGPEA - 2-phenoxyethyl acrylate
Eoc - end-of-chain
15 Equiv - equivalent
Et - ethyl
Et_{sBu} - percent of ethyl branches occurring in sec-butyl ended branches
GPC - gel permeation chromatography
20 HA - hexyl acrylate
Hex - hexyl
IC - in-chain, refers to the ester group of the acrylate being bound to the main-chain of the ethylene copolymer
25 IDA - isodecyl acrylate
Incorp - incorporation
i-Pr - iso-propyl
M.W. - molecular weight
MA - methyl acrylate
30 Me - methyl
MeOH - methanol
Me_{sBu} - percent of methyl branches occurring in sec-butyl ended branches

MI - melt index

Mn - number average molecular weight

Mp - peak average molecular weight

Mw - weight average molecular weight

5 N: - not determined

PDI - polydispersity; Mw/Mn

PE - polyethylene

Ph - phenyl

Press - pressure

10 RI - refractive index

Rt or RT - room temperature

t-Bu - t-butyl

TCB - 1,2,4-trichlorobenzene

Temp - temperature

15 THA - 3,5,5-trimethylhexyl acrylate

THF - tetrahydrofuran

TO - number of turnovers per metal center = (moles monomer consumed, as determined by the weight of the isolated polymer or oligomers) divided by (moles catalyst)

20 tol - toluene

Total Me - Total number of methyl groups per 1000 methylene groups as determined by ^1H or ^{13}C NMR analysis

UV - ultraviolet

Examples 1-89


25 Ligand precursor and catalyst synthesis














All operations related to the catalyst synthesis were performed in a nitrogen drybox or using a Schlenk line with nitrogen protection. Anhydrous solvents were used in all cases. Solvents were distilled from drying agents under nitrogen using standard procedures: chlorobenzene from P_2O_5 ; THF from sodium benzophenone ketyl. Ni[II] allyl chloride and NaBAF were prepared according to the literature.

30

(Tert-butyl)₂PCH₂Li was synthesized by reacting (tert-butyl)₂PCH₃ with tert-butyl lithium in heptane in a 109°C bath for a few hours. The product was filtered and washed with pentane. (Tert-butyl)₂PLi was synthesized by reacting
 5 (tert-butyl)₂PH with n-butyl lithium in heptane at 90°C for 6 h. Ph₂PLi was made by reacting Ph₂PH with n-butyl lithium at RT for 3 d at RT. The NMR spectra were recorded using a Bruker 500MHz spectrometer or a Bruker 300MHz spectrometer.

In the Examples 1-89 the following catalysts were used:





Example 1 - Synthesis of Catalyst 1

In a drybox, 0.50g (tert-butyl)₂PCH₂Li was mixed with 20 mL THF in a Schlenk flask. It was brought out of the drybox and placed in an ice-water bath. One atmosphere of
 5 hexafluoroacetone was applied to the flask. The mixture was allowed to stir at 0°C under 1 atm of hexafluoroacetone for 1 h. The hexafluoroacetone flow was stopped. The reaction

mixture was allowed to warm up to RT, during which time gas evolution was seen. The mixture was then stirred at RT for 1 h and was transferred back to the drybox. The THF was evaporated. The product was dried under full vacuum overnight. A yellow solid was obtained. ^{31}P NMR in $\text{THF}-d_8$: singlet peak at 13.07 ppm. ^1H NMR in $\text{THF}-d_8$: 2.08 ppm (2H, d, JPH = 4.6 Hz, P-CH₂-); 1.22 ppm (18H, d, JPH = 11.2 Hz, -C(CH₃)₃). A small amount of THF (~0.2 eq) existed in the solid product. To this product was added 0.405 g ((allyl)NiCl)₂ and 15 mL THF. The mixture was allowed to stir at RT over the weekend. The mixture was evaporated to dryness, extracted with 30 mL toluene, filtered through Celite®, followed by 3x5 mL toluene wash. Solvent was evaporated. The product was dried under full vacuum overnight. The product became powdery after tritulating with pentane. Yellow brown solid (0.82 g) was obtained. ^{31}P NMR in CD_2Cl_2 : singlet peak at 78.81 ppm.

Example 2 - Synthesis of catalyst 2

A 100-mL round-bottomed flask was charged with 292 mg (1.60 mmol) of benzophenone dissolved in ca. 15 mL THF. Then the (t-Bu)₂P-CH₂Li (266 mg, 1.60 mmol) dissolved in ca. 15 mL THF was added. The solution turns from colorless to dark blue. It was stirred for one hour after which time, a solution of (Ni(C₃H₅)Cl)₂ (217 mg, 0.80 mmol) in 15 mL THF was added. It was stirred for an additional 1 h and the solvent removed. The residue was extracted with hexane and toluene and the solvent removed. The residue was washed with small amounts of hexane and dried. The yield was 395 mg (71%).

^1H NMR (CD_2Cl_2 , 23°C, 300 MHz) d 8.2-7.9 (m, 4H, Ar); 7.4-6.9 (m, 6H, Ar); 5.10 (m, 1H); 4.26 (brs, 1H); 3.25 (dd, J= 14 Hz, J= 5 Hz, 1H), 2.80 (m, 2H), 2.24 (brs, 1H), 1.16 (d, J= 13 Hz, 1H), 0.97 (d, JP-H= 13 Hz, 9H); 0.80 (d, JP-H= 13 Hz). ^{31}P NMR (CD_2Cl_2 , 23°C,): d 84.0. ^{13}C NMR (CD_2Cl_2 , 23°C, 75

MHz) d 156.1 (s); Ar C-H signals overlapping with C6D6 signal; 127.2 (s); 125.7 (d, JP-C= 6 Hz); 109.3 (d, JC-H= 157 Hz); 86.7 (d, JP-C= 10 Hz); 69.1 (m, JP-C= 22 Hz); 41.2 (dt, JP-C= 25 Hz, JC-H= 127 Hz); 37.6 (m, JP-C= 6 Hz); 33.8 (m);
5 29.9 (q, JC-H= 124 Hz).

A single red-orange crystal was grown from CH₂Cl₂/hexane at ambient temperature, and X-ray diffraction data confirmed the structure. No LiCl was present in the structure based X-ray single crystal diffraction analysis.


10 Example 3 - Synthesis of catalyst 3

In a drybox, 0.2273 g (tert-butyl)₂PCH₂Li was mixed with 20 mL THF in a 100 mL RB flask. The mixture was cooled at -30°C for 30 min. Under stirring, 0.50 g monoimine-A was added to the solution while the solution was still cold.


15 The reaction mixture turned yellow blue right away. The mixture was allowed to warm up to RT and to stir at this temperature overnight. THF was evaporated. The product was dried under vacuum for 7 h. A deep yellow green solid (0.912 g) was isolated. ³¹PNMR in THF-d₈: singlet peak at

20 18.56 ppm. To the product was added 0.1847 g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 6.5 h at RT. The mixture was evaporated to dryness. The residue was extracted with 25 mL toluene. It was filtered through Celite®, followed by 3x5 mL toluene wash.

25 The solution was evaporated to dryness. The product was then dried under full vacuum overnight. Dark green solid (0.92 g) was isolated.



A



B

Example 4 - Synthesis of Catalyst 4

In a drybox, 0.35 g (tert-butyl)₂PCH₂Li was added to the -30°C solution of 0.4409 g monoimine-B in 30 mL THF in a 100 mL RB flask. The reaction mixture turned yellow blue immediately. The mixture was allowed to warm up to RT and stirred at this temperature for 19 h. THF was evaporated. The product was dried under vacuum. ³¹PNMR in THF-d₈: Two singlet peaks. One was a sharp and tall peak at 20.54 ppm and another was a wide and short peak at 18.74 ppm. To the product was added 0.2812 g ((allyl)NiCl)₂ and 30 mL THF in a RB flask. The mixture was allowed to stir for 18 h at RT. The mixture was evaporated to dryness. The residue was extracted with 30 mL toluene. It was filtered through Celite®, followed by 3x5 mL toluene wash. The solution was evaporated to dryness. The solid product was then dried under vacuum for 8 h. ³¹PNMR in C₆D₆: two major singlet peak at 81.75 ppm and 79.92 ppm, as well as a minor singlet peak at 20.05 ppm. Electron spray mass spectroscopy showed major peaks at 468 and 470 (due to ⁵⁸Ni and ⁶⁰Ni isotopes), which indicated that the desired product picked up a proton in the spray process. X-ray single crystal diffraction analysis confirmed the structure. No LiCl was present in the structure.

Examples 5 - Synthesis of Catalyst 5

A 100 mL RB flask was charged with 217 mg(0.82 mmol) of 2,2,2-trifluoro-2',4',6'-trimethoxyacetophenone dissolved in

ca. 10-15 mL THF. Then (t-Bu)₂P-CH₂Li (136 mg, 0.82 mmol) dissolved in ca. 10-15 mL THF was added. The initially purple solution (color came from traces impurities in starting ketone) turned clear yellow. It was stirred for one h after which time, a solution of (Ni(C₃H₅)Cl)₂ (111 mg, 0.41 mmol) in 10-15 mL THF was added. It was stirred for an additional one h and the solvent removed. The residue was washed with hexane and dried in vacuo to yield 362 mg (78%). Key NMR signals (incomplete): ¹H-NMR (CD₂Cl₂, 23°C, 300 MHz) δ 6.5-6.2 (brm, 2H, Ar); 5.3 (brm, 1H), 4.8 (brs, 1H); 4.1 (brs, 2H); 3.8 (brs, 9H); 3.7-2.0 (brm); 2.0-0.8 (brm, t-Bu signals). Two isomers (50:50) by ³¹P-NMR (CD₂Cl₂, 23°C, 300 MHz): δ 81.4; 80.2. ¹³C-NMR (CD₂Cl₂, 23°C, 125 MHz): δ 161.3 (s); ca. 112 (brs); ca. 94.0 (brm, J= 158 Hz); 93.2 (br); ca. 86; 68.1; 58.4; 56.3; 55.6. A single red-orange crystal was grown from CH₂Cl₂/hexane at ambient temperature, and the structure confirmed by X-ray diffraction. The complex contained one equivalent of LiCl, and existed as a dimer bridged by LiCl.

Example 6 - Synthesis of Catalyst 6

A 200 mL RB flask was charged with 300 mg (1.10 mmol) of 2,4,6-trimethoxybenzophenone dissolved in ca. 20 mL THF. Then (t-Bu)₂P-CH₂Li (183 mg, 1.10 mmol) dissolved in ca. 20 mL THF was added. It was stirred for one h, after which time, a solution of (Ni(C₃H₅)Cl)₂ (149 mg, 0.55 mmol) in THF (ca. 20 mL) was added. It was stirred for an additional one h and the solvent removed. The residue was washed with hexane and dried in vacuo to yield 664 mg product. Key NMR signals (incomplete): ¹H-NMR (CD₂Cl₂, 23°C, 300 MHz) δ 7.64 (brs, 1H, Ar); 7.51 (brs, 1H, Ar); 7.14 (brt, 2H, Ar); 7.00 (brt, 1H, Ar); 6.14 (s, 2H); 5.28 (m, 1H); 5.0-4.5 (brm, 2H); 3.67 (s, 3H, OCH₃); 3.64 (s, 6H, OCH₃); 3.26 (brs, 1H); 2.87 (dd, 1H, J= 14 Hz, J= 5 Hz); 2.8-2.4 (brm, 2H); 1.7-0.7

(brm, 18H, t-Bu). Two isomers (50:50) by ^{31}P NMR (CD_2Cl_2 , 23°C, 75 MHz): δ 79.0; 78.2. ^{13}C NMR (CD_2Cl_2 , 23°C, 125 MHz): δ 167.9 (d, $J_{\text{P-C}} = 4.5$ Hz); 159.9 (s); 158.5 (brs); 154.4 (brs); 127.6 (dd, $J_{\text{C-H}} = 158$ Hz, $J = 7.5$ Hz); 126.1 (dt); 125.7 (dt, $J = 150$ Hz); 111.0 (brd); 95.0 (dd, $J_{\text{C-H}} = 159$ Hz, $J = 4.7$ Hz); 87.2 (brs); 67.0 (brdt, $J_{\text{P-C}} = 22$ Hz); 57.7 (q, $J_{\text{C-H}} = 145$ Hz); 55.6 (q, $J_{\text{C-H}} = 144$ Hz); ca. 40.0 (brs); 39.7 (dt, $J_{\text{P-C}} = 25$ Hz); 35.3 (d, $J_{\text{P-C}} = 18$ Hz); 33.7 (d, $J_{\text{P-C}} = 16$ Hz); 30.0 (brq, $J_{\text{C-H}} = 127$ Hz). A single red-orange crystal was grown from CH_2Cl_2 /hexane at ambient temperature, and an X-ray diffraction confirmed the structure. The complex contained one equivalent of LiCl, and existed as a dimer bridged by LiCl.

Example 7 - Synthesis of Catalyst 7

A 200 mL RB flask was charged with 300 mg (1.17 mmol) of 2,2-dimethoxy-2-phenylacetophenone dissolved in ca. 20 mL THF. Then (t-Bu) $_2$ P-CH $_2$ Li (195 mg, 1.17 mmol) dissolved in ca. 20 mL THF was added. It was stirred for one h, after which time a solution of (Ni(C $_3$ H $_5$)Cl) $_2$ (158 mg, 0.59 mmol) in THF (ca. 20 mL) was added. It was stirred for an additional h and the solvent removed. The residue was washed with hexane and dried in vacuo to yield 438 mg (67%). Two isomers (50:50) by ^{31}P NMR (CD_2Cl_2 , 23°C, 300 MHz): δ 82.1 (s) and δ 81.5 (s). A single red-orange crystal was grown from CH_2Cl_2 /hexane at ambient temperature, and X-ray diffraction data confirmed the structure. The complex contained one equivalent of LiCl, and existed as a dimer bridged by LiCl.

Example 8 - Synthesis of Catalyst 8

In a drybox, 0.3043 g (tert-butyl) $_2$ PLi was added to a -30°C solution of 0.5284 g 2,2,2-trifluoro-2',4',6'-trimethoxyacetophenone (Aldrich) in 15 mL THF in a 100 mL RB flask. The reaction mixture turned yellow. The mixture was allowed to warm up to RT and stir at this temperature overnight. THF was evaporated. The product was dried under

vacuum for 6 h. ^{31}P NMR in $\text{THF}-d_8$: a singlet peak at 41.28 ppm. The product was mixed with 0.1608 g $((\text{allyl})\text{NiCl})_2$ and 15 mL THF in a RB flask. The mixture was allowed to stir for 2 h at RT. It was then evaporated to dryness. The residue was mixed with 10 mL toluene. Pentane (40 mL) was then added into the flask. The brown solid was filtered, followed by 3x pentane wash and dried in vacuo. Brown solid (0.445 g) was obtained. ^{31}P NMR in $\text{THF}-d_8$: two singlet peak at 50.31 ppm and 50.05 ppm.

Example 9 - Synthesis of Catalyst 9

In a drybox, 0.30 g $(\text{tert-butyl})_2\text{PCH}_2\text{Li}$ was added to a -30°C solution of 0.3072 g ethyl trifluoropyruvate (Lancaster) in 15 mL THF in a 100 mL RB flask. The reaction mixture turned golden yellow. The mixture was allowed to warm up to RT and stir at this temperature for 1 h. THF was evaporated. The product was dried under vacuum overnight. The product was mixed with 0.247 g $((\text{allyl})\text{NiCl})_2$ and 15 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was then evaporated to dryness. The residue was dissolved by adding 10 mL toluene. Pentane (40 mL) was then added into the flask. The yellow solid was filtered, followed by 3x pentane wash and dried in vacuo. Yellow solid (0.36 g) was obtained. ^{31}P NMR in $\text{THF}-d_8$: The major singlet peak at 78.24 ppm and two small singlet peaks at 96.72 ppm and 218.21 ppm. A single crystal was grown and the structure was confirmed synchrotron diffraction analysis. The complex contained one equivalent of LiCl , and existed as a dimer bridged by LiCl .

Example 10 - Synthesis of Catalyst 10

In a drybox, 0.502 g $(\text{tert-butyl})_2\text{PLi}$ was added to a -30°C solution of 0.5613 g ethyl trifluoropyruvate (Lancaster) in 25 mL THF in a 100 mL RB flask. The reaction mixture turned yellow and then copper color. The mixture was

allowed to warm up to RT and to stir at this temperature overnight. THF was evaporated. The product was dried under vacuum. ^{31}P NMR in THF- d_8 : singlet peak at 41.22 ppm. The product was mixed with 0.453 g ((allyl)NiCl) $_2$ and 25 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was evaporated to dryness. The residue was mixed with 5 mL toluene. Pentane (40 mL) was then added into the flask. The brown solid was filtered, followed by 3x pentane wash and dried in vacuo. Brown solid (0.745 g) was obtained. ^{31}P NMR in THF- d_8 : Singlet peak at 46.04 ppm.

Example 11 - Synthesis of Catalyst 11

In a drybox, 0.40 g Ph $_2$ PLi was added to a -30°C solution of 0.4357 g monoimine-B in 25 mL THF in a 100 mL RB flask. The reaction mixture turned orange. The mixture was allowed to warm up to RT and stir at this temperature for 1 h. THF was evaporated. The product was dried under vacuum. ^{31}P NMR in THF- d_8 : A major singlet peak at -22.60 and two small singlet peaks at -16.15 ppm and -82.25 ppm. The product was mixed with 0.2798 g ((allyl)NiCl) $_2$ and 25 mL THF in a RB flask. The mixture was allowed to stir for 2 h at RT. The mixture was evaporated to dryness. The residue was extracted with toluene, filtered and washed with toluene. Solvent was evaporated. The product was dried in vacuo.

Example 12 - Synthesis of Catalyst 12

In a drybox, 0.40 g Ph $_2$ PLi was added to a -30°C solution of 0.3794 g benzophenone in 25 mL THF in a 100 mL RB flask. The reaction mixture turned blue-green. The mixture was allowed to warm up to RT and to stir at this temperature for 1 h. THF was evaporated. The product was dried under vacuum. ^{31}P NMR in THF- d_8 : A major singlet peak at -14.28 and a small singlet peaks at -26.30 ppm, as well as a tiny singlet peak at -39.62 ppm. The product was mixed with 0.2796 g ((allyl)NiCl) $_2$ and 25 mL THF in a RB flask. The mixture was al-

lowed to stir for 2 h at RT. The mixture was evaporated to dryness. The residue was extracted with toluene, filtered and washed with toluene. Solvent was evaporated. The product was dried in vacuo.

5 Example 13 - Synthesis of Catalyst 13

In a drybox, 0.30 g (tert-butyl)₂PCH₂Li was added to a - 30°C solution of 0.5137g 4,4'-bis(dimethylamino)thio- benzophenone in 20 mL THF in a 100 mL RB flask. The reaction mixture turned golden yellow. The mixture was allowed to warm up to RT and to stir at this temperature for a few h. THF was evaporated. The product was dried under vacuum overnight. ³¹PNMR in THF-d₈: A major singlet peak at 21.53 ppm and some minor peaks at 26.05 ppm, 24.34 ppm, 16.58 ppm and 12.74 ppm. The product was mixed with 0.148 g ((al-
15 lyl)NiCl)₂ and 15 mL THF in a RB flask. The mixture was allowed to stir for 2 h at RT. The mixture was evaporated to dryness. The solid product was dried in vacuo overnight. ³¹PNMR in THF-d₈: A singlet peak at 101.84 ppm.

Example 14 - Synthesis of Catalyst 14

20 In a drybox, 0.40 g (tert-butyl)₂PCH₂Li was added to a - 30°C solution of 0.2485 g benzonitrile in 20 mL THF in a 100 mL RB flask. The reaction mixture turned red-orange. The mixture was allowed to warm up to RT and stir at this temperature for a few hours. THF was evaporated. The product
25 was dried under vacuum overnight. ³¹PNMR in THF-d₈: A broad singlet peak at 7.26 ppm. ¹HNMR in THF-d₈ indicated that it was (t-Bu)₂PCH(Li)C(Ph)=NH: 1.14 ppm (18H, (CH₃)₃C-, d, ³JPH = 10.8Hz); 3.71 ppm (1H, broad singlet); 4.23 ppm (1H, broad singlet, -C(Ph)=NH); 7.11 ppm (1H, ArH, t); 7.18 ppm (2H, ArH, t); 7.64ppm (2H, ArH, d). The product was mixed with
30 0.327 g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 2.5 h at RT. The mixture was evaporated to dryness. The solid product was extracted with

10 mL toluene and was filtered through Celite®, followed by 3x10 mL toluene wash. Toluene was evaporated. The solid product was dried in vacuo overnight. Dark brown solid (0.379 g) was obtained. ³¹PNMR in THF-d₈: A singlet peak at 73.06 ppm. . ¹HNMR in THF-d₈ indicated that it is the expected ((t-Bu)₂PCH₂C(Ph)=NNi(allyl)) complex: 1.26 and 1.41 ppm (9H each, (CH₃)₃C-, d, ³JPH = 12.9Hz for both); 1.59 and 2.49 ppm (1H each, d, PCHH'); 3.11, 3.59, 3.68, 4.24 ppm (1H each, broad singlets, allyl-H); 5.02 ppm (1H, m, central allyl-H); 7.26 ppm (3H, s, ArH); 7.53 ppm (2H, s, ArH).

Example 15 - Synthesis of Catalyst 15

In a drybox, 0.40 g (tert-butyl)₂PLi was added to a -30°C solution of 0.2186 g trimethylacetonitrile in 20 mL THF in a 100 mL RB flask. The reaction mixture turned yellow. The mixture was allowed to warm up to RT and to stir at this temperature for 3 d. THF was evaporated. The product was dried under vacuum overnight. ³¹PNMR in THF-d₈: 45.93 ppm and a minor peak at 21.13 ppm. The product was mixed with 0.357 g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was evaporated to dryness. The solid product was extracted with toluene and was filtered through Celite®, followed by 3x toluene wash. Toluene was evaporated. The solid product was dried in vacuo overnight. Red-brown solid (0.476 g) was obtained.

Example 16 - Synthesis of Catalyst 16

In a drybox, 0.40 g (tert-butyl)₂PCH₂Li was added to a -30°C solution of 0.2003 g trimethylacetonitrile in 20 mL THF in a 100 mL RB flask. The reaction mixture turned yellow. The mixture was allowed to warm up to RT and stir at this temperature for 3 d. THF was evaporated. The product was dried under vacuum overnight. ³¹PNMR in THF-d₈: A major singlet peak at 17.67 ppm and a minor peak at 12.78. The prod-

uct was mixed with 0.327g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was evaporated to dryness. The solid product was mixed with 10 mL toluene first and then 40 mL pentane. The solid was filtered, followed by 3x pentane wash and dried in vacuo overnight. ³¹PNMR in THF-d₈: A singlet peak at 73.48 ppm. ¹HNMR in THF-d₈: 1.18ppm (d, -P(CH₃)₃, 18H); 1.34 ppm (d, -C(CH₃)₃, 9H); 1.49ppm, 2.38 ppm (1H each, d, PCHH'); 3.01 ppm, 3.23 ppm, 3.44 ppm, 3.97 ppm (1H each, brs, allyl-H); 4.92 ppm (1H, central allyl-H, m).

Example 17 - Synthesis of Catalyst 17

In a drybox, 0.40 g (tert-butyl)₂PLi was added to a -30°C solution of 0.5529 g benzil in 20 mL THF in a 100 mL RB flask. The reaction mixture turned dark red-brown. The mixture was allowed to warm up to RT and stir at this temperature overnight. THF was evaporated. The product was dried under vacuum overnight. ³¹PNMR in THF-d₈: A major singlet peak at 41.09 ppm and a minor peak at 2.45 ppm. The product was mixed with 0.359 g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was evaporated to dryness. The solid product was mixed with 10 mL toluene first and then 90 mL pentane. The solid was filtered, followed by 3x pentane wash and dried in vacuo overnight. Light brown solid (0.59 g) was obtained.

Example 18 - Synthesis of Catalyst 18

In a drybox, 0.40 g (tert-butyl)₂CH₂PLi was added to a -30°C solution of 0.5066 g benzil in 20 mL THF in a 100 mL RB flask. The reaction mixture turned dark red-brown. The mixture was allowed to warm up to RT and to stir at this temperature overnight. THF was evaporated. The product was dried under vacuum overnight. ³¹PNMR in THF-d₈: A major singlet peak at 14.28 ppm and several minor peaks were ob-

served. The product was mixed with 0.329 g ((allyl)NiCl)₂ and 20 mL THF in a RB flask. The mixture was allowed to stir for 1 h at RT. The mixture was evaporated to dryness. The solid product was mixed with 10 mL toluene first and then 90 mL pentane. The solid was filtered, followed by 3x pentane wash and dried in vacuo overnight. Yellow solid (0.285 g) was obtained. ³¹PNMR in THF-d₈: A major singlet peak at 94.03 ppm and minor peaks at 67.51, 66.72 and 62.29 ppm were observed.

Example 19 - Synthesis of Catalyst 19

A 100 mL RB flask was charged with 102 mg (0.86 mmol) of phenyl isocyanate dissolved in ca. 10 mL THF. Then (t-Bu)₂P-CH₂Li (143 mg, 0.86 mmol) dissolved in ca. 10 mL THF was added. The solution is clear yellow. It was stirred for one h, after which time a solution of (Ni(C₃H₅)Cl)₂ (116 mg, 0.43 mmol) in 15 mL THF was added. The solution turned brown-yellow. It was stirred for an additional one h and the solvent removed. The residue was washed with hexane and dried in vacuo. The yield was 207 mg (57%). Key NMR signals (incomplete): ¹HNMR (CD₂Cl₂, 23°C, 300 MHz) δ 7.7-6.5 (brm, Ar); 5.32 (brs), 5.09 (m); 3.64 (brm); 3.01 (brm); 3.0-2.3 (brm); 2.0-0.6 overlapping signals + two doublets (J= 14 Hz) at 1.42 ppm and 1.27 ppm corresponding to t-Bu signals). ³¹PNMR (CD₂Cl₂, 23°C, 300 MHz): δ 50.6.

Example 20A - Synthesis of (t-Bu)₂POC(CH₃)₂C(CH₃)₂OH

In a drybox, 0.623 g pinacol and 2.0 g (t-Bu)₂PCL were dissolved in 20 mL THF. To this mixture was added over 10 min 0.4438 g KH in portions. The mixture was allowed to stir at RT for 12 d. The mixture was filtered through Celite®, followed by 3x5 mL THF wash. Solvent was evaporated. The viscous liquid was dried overnight. Light tan viscous liquid was obtained. ³¹PNMR in CD₂Cl₂: A singlet peak at 135.29 ppm and a few minor peaks. Crystals grew out of the

liquid in several days. X-ray single crystal analysis indicated that it was the desired product. It existed as tetramer in the solid state through hydrogen bonding.

Example 20B - Synthesis of Catalyst 20

5 Catalyst 20 was generated in-situ by adding 13.9 mg of (t-Bu)₂POC(CH₃)₂C(CH₃)₂OH to a chlorobenzene solution of (TMEDA)NiMe₂ (10.2 mg in 5 mL chlorobenzene, TMEDA = tetramethylethylenediamine).

Example 20C - Polymerization using Catalyst 20

10 The in-situ prepared Catalyst 20 (0.05 mmol, see Example 20B) was screened for ethylene polymerization at 6.9 MPa of ethylene at 50°C for 18 h in a shaker tube. Polyethylene (0.067 g) was obtained. It had melting points of 131°C (166.7 J/g) and 114°C (33.5 J/g).

Example 21 - Synthesis of Catalyst 21

15 In a drybox, 0.489 g (tert-butyl)₂PCH₂Li was mixed with 25 mL THF in a Schlenk flask. It was brought out of the drybox and placed in an ice-water bath. One atmosphere of carbon dioxide was applied to the flask. The mixture was
20 allowed to stir at 0°C under 1 atm of carbon dioxide for 15 min and then at RT for 45 min. The CO₂ flow was stopped. THF was evaporated. The product was dried under full vacuum overnight. Tan yellow solid was obtained. Part of the product (0.4204 g) was mixed with 0.2704 g ((allyl)NiCl)₂ in
25 20 mL THF. The mixture was allowed to stir at RT for 40 min. The mixture was evaporated to dryness and was added to 5 mL toluene to dissolve, followed by addition of about 70 mL pentane. The solid was filtered, followed by 3x5 mL pentane wash. The product was dried under full vacuum over-
30 night. Orange solid (0.48 g) was obtained. ³¹PNMR in THF-d₈: singlet peak at 51.70 ppm. ¹HNMR in THF-d₈: 5.34 ppm (bm, central allyl-H, 1H); 2.67-2.95 (bm, allyl-CH₂ and PCH₂, 6H); 1.34 ppm (d, J_{PH} = 12.4Hz, C(CH₃)₃, 18H). Lithium NMR

in C₆D₆ of 21 and a crystal structure of the Zwitterion tetrafluoroborate derivative indicate that one equivalent of Li⁺ present which can potentially complex to 21 does not in fact complex to 21.

5 Example 22 - Synthesis of Catalyst 22

In a drybox, 0.1009 g (tert-butyl)₂PCH₂C(Ph)₂OLi·THF (see Example 2) was dissolved in 5 mL THF in a 20 mL vial. To this was added 56 mg of ZrCl₄. The solution turned a peach color. It was allowed to stir overnight. Solvent was evaporated and the resulting solid was dried in vacuo.

10 Example 23 - Synthesis of Catalyst 23

In a drybox, 0.1009 g (tert-butyl)₂PCH₂C(Ph)₂OLi·THF (see Example 2) was dissolved in 5 mL THF in a 20 mL vial. To this was added 45.5 mg of TiCl₄. The solution turned dark amber. It was stirred overnight. Solvent was evaporated and the resulting tan solid was dried in vacuo.

15 Ethylene Polymerization Screening

Using the Nickel Catalysts 1-21

In a drybox, a glass insert was loaded with the isolated Ni catalysts (except Catalyst 20 in Example 20, which was generated in-situ). Solvent (TCB or chlorobenzene), optionally comonomers were added to the glass insert. A Lewis acid cocatalyst (typically BPh₃ or B(C₆F₅)₃) was often added to the solution. The insert was then capped and sealed.

25 Outside of the drybox, the tube was placed under ethylene and was shaken mechanically at desired temperature listed in Table 3 for about 18 h. Sometimes an aliquot of the solution was used to acquire a ¹HNMR spectrum. The remaining portion was added to about 20 mL of methanol in order to precipitate the polymer. The polymer was isolated, washed with methanol several times and dried in vacuo.

Ethylene Polymerization Screening by the
Catalysts 22 and 23, in the presence of MAO

In a drybox, a glass insert was loaded with 0.02 mmol of the isolated Zr or Ti catalyst and 9 mL of 1,2,4-trichlorobenzene. It was then cooled to -30°C. PMAO-IP (1mL 12.9wt% (in Al) toluene² solution) was added to the frozen solution. It was put in a -30°C freezer. The insert was then capped and sealed. Outside of the drybox, the cold tube was placed under ethylene and was shaken mechanically at desired temperature listed in Table 3, condition V, for about 18 h. Methanol (about 15 mL) and 2 mL conc. hydrochloric acid was added to the mixture. The polymer was isolated, washed with methanol several times and dried in vacuo.

Polymer Characterization

The results of ethylene polymerization and copolymerization catalyzed by Catalysts 1-23 under different reaction conditions (See Table 3) are reported in Tables 4-13. The polymers were characterized by NMR, GPC and DSC analysis. A description of the methods used to analyze the amount and type of branching in polyethylene is given in previously incorporated US5880241. GPC's were run in trichlorobenzene at 135°C and calibrated against polyethylene using universal calibration based on polystyrene narrow fraction standards. DSC was recorded between -100°C to 150°C at a heating rate of 10°C/min. Data reported here are all based on second heat. ¹HNMR of the polymer samples was run in tetrachloroethane-d₂ at 120°C using a 500MHz Bruker spectrometer.

Table 3

Conditions for Ethylene Polymerization and Copolymerization
Screening.

I	0.02 mmol catalyst, 10 mL TCB, RT, 18 h, 6.9 MPa ethylene, 10 eq B(C ₆ F ₅) ₃
II	0.02 mmol catalyst, 10 mL TCB, RT, 18 h, 1.0 MPa ethylene, 10 eq B(C ₆ F ₅) ₃
III	0.02 mmol catalyst, 10 mL TCB, 60°C, 18 h, 1.0 MPa ethylene, 10 eq B(C ₆ F ₅) ₃
IV	0.02 mmol catalyst, 3 mL TCB, 2mL E-10-U*, 60°C, 18 h, 1.0 MPa ethylene, 40 eq B(C ₆ F ₅) ₃
V	0.02 mmol catalyst, 9 mL TCB, 1 mL PMAO-IP (12.9wt% (in Al) in toluene), RT, 18 h, 6.9 MPa ethylene
VI	0.02 mmol catalyst, 4 mL TCB, 1 mL n-hexyl acrylate, 120°C, 18 h, 6.9 MPa ethylene, 40 eq B(C ₆ F ₅) ₃
VII	0.02 mmol catalyst, 10 mL TCB, 60°C, 18 h, 1.0 MPa ethylene, 10 eq B(C ₆ F ₅) ₃ , 1 eq NaBAF

* Ethyl-10-Undecylenate.

5

Table 4

Ethylene Polymerization at 6.4 MPa Ethylene in Shaker Tubes
(0.05 mmol catalyst, 5 mL chlorobenzene, 18h)

Ex.	Catalyst	Cocatalyst /amt	T(°C)	Yield (g)	#Me/1000CH ₂	mp. (°C)	Mw/PDI	TON* *
24	1	BPh ₃ /5eq	25	10.202	<1	136 (162*)	737,803/3.5	7,287
25	1	B(C ₆ F ₅) ₃ /5eq	25	4.764	9	128	134,256/60.2	3,403
26	1	none	25	0				
27	1	BPh ₃ /5eq	80	4.990	6	133	47,301/3.3	3,564
28	1	B(C ₆ F ₅) ₃ /5eq	80	1.710	12	124	15,813/14.0	1,221
29	2	B(C ₆ F ₅) ₃ /5eq	80	2.280	31	125	4,759/3.0	1,629
30	2	BPh ₃ /5eq	80	0				
31	4	B(C ₆ F ₅) ₃ /10eq	50	4.862	86	114, 106	28,765/41.8	3,466
32	11	B(C ₆ F ₅) ₃ /10eq	50	0.117	25	119, 102		209
33	12	B(C ₆ F ₅) ₃ /2eq	50	0.046	19	119, 102		82

*Heat of fusion (in J/g)

Table 5

Ethylene (Co)polymerization at 2.1 MPa Ethylene in

Shaker Tubes (0.05 mmol catalyst, 5 mL solvent/comonomer, 18 h)

Ex.	Catalyst	Cocatalyst /eq	Solvent/ Comonomer	T (°C)	Yield (g)	Mole% Comonomer	#Me/ 1000 CH ₂	m.p. (°C)	Mw/ PDI	TON E/Comonomer
34	1	BPh ₃ /2	C ₆ H ₅ Cl	50	5.518		<1 ^{a)}	136	173,568/3.1	3941
35	1	BPh ₃ /5	C ₆ H ₅ Cl	50	4.56		2	135	191,589/5.1	3,321
36	1	BPh ₃ /10	C ₆ H ₅ Cl	50	5.132		2	137	268,453/3.5	3,666
37	1	BPh ₃ /10	1-Hexene	50	1.295		12	111	121,450/2.4	/
38	1	BPh ₃ /10	E-4-P*	50	4.972	3.0	1 ^{b)}	117	62,753/3.7	3,100/97
39	2	B(C ₆ F ₅) ₂ /2	C ₆ H ₅ Cl	50	1.816		8	127	20,100/9.2	1,297
40	2	B(C ₆ F ₅) ₂ /10	C ₆ H ₅ Cl	50	12.314		12	125***	19,712/5.1	8,796
41	2	B(C ₆ F ₅) ₂ /10	1-Hexene	50	3.662		48 ^{c)}	99	14,611/5.2	/
42	2	B(C ₆ F ₅) ₂ /30	E-10-U**	80	5.616	9.9	24	-10	7,298/6.0	2,189/240
43	3	B(C ₆ F ₅) ₂ /10	C ₆ H ₅ Cl	50	1.799		28	113	189,503/16.6	1,285
44	3	BPh ₃ /10	C ₆ H ₅ Cl	50	0					
45	3	B(C ₆ F ₅) ₂ /10	1-Hexene	50	0.738		87	72	146,422/3.4	/
46	3	B(C ₆ F ₅) ₂ /30	E-10-U	80	3.427	2.2	105	117,106	264,357/107.9	2,089/47

* Ethyl-4-pentenoate

** Ethyl-10-Undecylenate

*** Heat of fusion: 200J/g.

a). No alkyl branches based on ¹³CNMR.b). No alkyl branches, 2.6mole% ethyl-4-pentenoate based on ¹³CNMR.c). Based on ¹³CNMR, total Me was 34.4 (1.7Me, 2.7Et, 0.7Pr, 25.9Bu, 0.5Am, 2.9Hex+). The enriched butyl branch is consistent with the significant 1-hexene incorporation in ethylene copolymerization.

Table 6

Ethylene (Co)polymerization 1.0 MPa Ethylene at 50°C in
Shaker Tubes (0.05 mmol catalyst, 5 mL solvent/comonomer,
18hr)

Ex	Catalyst	Cocatalyst /eq	Solvent/Co-monomer	Yield (g)	Mole% Co-monomer	#Me/1000CH ₂	Mw/PDI	TON E/Comonomer
47	2	B(C ₆ F ₅) ₃ /30	MUE*	1.928	6.3	11	7,674/3.7	952/64
48	4	B(C ₆ F ₅) ₃ /30	MUE	0.102	6.0	24	17,303/11.7	51/3

5

*Methyl undecenyl ether (CH₂=CH(CH₂)₉OCH₃).

Table 7

Condition I in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI	TON
49	2	7.264	6	128 (234)	32,932/3.82	12,947
50	5	15.560	10	125 (218)	13,921/4.91	27,734
51	6	11.718	14	124 (206)	10,411/3.68	20,886
52	7	10.619	20	117 (185)	2,792/2.57	18,927
53	13	0.029	7	131 (161)	49,268/4.1	52
54	8	8.970	22	125 (142)	187,705/4.9	15,988
55	9	9.728	12	130 (194)	30,547/18.3	17,339
56	10	0.112	22	127 (182)	190,093/182.7 trimodal	200
57	14	6.401	121	120 (81)	67,779/251.5 trimodal	11,409
58	15	8.407	16	126 (102)	93,871/3.1	14,985
59	16	0.088	73	123 (99)	25,262/24.7	157
60	17	1.250	30	129 (141)	73,164/2.4	2228
61	18	14.279	33	118 (148)	4,162/4.7	25,450
62	19	11.233	21	121 (169)	14,451/7.0	20,022
63	21	19.292	52	114 (169), 108	4,593/3.9	34,386

10

Table 8

Condition II in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI	TON
64	2	2.492	19	120 (140)	46,024/4.5	4,442
65	5	1.202	10	127 (181)	52,542/4.3	2,142
66	6	2.631	30	120 (130)	11,521/3.2	4,689
67	7	1.188	21	122 (207)	6,405/3.2	2,117
68	9	2.057	22	125 (175)	32,505/37.8	3,666

Table 9
Condition III in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI	TON
69	2	1.934	11	125 (164)	13,263/3.1	3447
70	5	6.624	13	124 (194)	10,468/3.2	11,807
71	6	6.276	30	115 (198)	5,285/3.6	11,186
72	7	4.196	32	115 (172)	2,688/2.6	7,479
73	18	5.629	38	108 (88)	8,381/9.1	10,033
74	19	9.868	50	100 (63)	7,784/9.8	17,589
75	21	6.560	31	113 (112)	5,581/5.5	11,692

Table 10
Condition IV in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	Mole% Comonomer	m.p. (°C) (ΔH _f)	Mw/PDI	TON E/EU*
76	2	0.648	6	2.8	112 (124)	5,737/2.6	947/28
77	5	3.861	6	4.9	108 (92)	6,315/2.5	4,939/257
78	6	0.129	12	5.1	124, 108 (124)	7,435/4.0	164/9
79	7	0.268	16	4.8	88 (116)	1,665/2.9	347/17
80	15	0.060	15	2.6	114 (132)	29,070/6.8	89/2
81	18	2.360	11	15.0		3,017/2.5	1,798/318
82	19	1.165	21	10.6		7,057/4.0	1,095/130

*Ethylene/Ethyl-10-undecylenate

Table 11
Condition V in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	TON
83	22	5.50	21	132 (157)	9,803
84	23	4.520	18	134 (136)	8,056
85	23*	4.543	8	134 (125)	8,097

*One equivalent of (tert-butyl)2PCH₂CPh₂OLi.THF was added to Catalyst 23.

Table 12
Condition VI in Table 3

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	Mole% Comonomer	mp. (°C) (ΔH _f)	Mw/PDI	TON E/HA
86	21	14.07	27	0.74*	114 (184)	2,757/3.0	24,079, 179

* 0.42 mole% in chain acrylate branch and 0.32 mole% unsaturated chain end.

Table 13
Condition VII in Table 3

Ex.	Catalyst	Yield (g)	#Me/1000CH ₂	mp. (°C) (ΔH _f)	Mw/PDI	TON
87	2	6.902	29	121(145)	15,842/5.6	12,302
88	5	13.547	18	122(167)	8,675/4.6	24,146
89	7	13.858	59	106 (110)	3,033/3.3	24,700

As noted above, one potential problem with the copolymerization of ethylene (and/or other olefins) and a polar comonomer such as an acrylate is the possibility of obtaining a homopolymer of the polar comonomer because of free radical polymerization of that polar comonomer. One method of determining whether such a homopolymer is present is to run an NMR spectrum of the polymer(s). Unfortunately, using ¹H-NMR for some of the more common acrylate monomers such as methyl acrylate the ¹H spectra of the homopolymer and ethylene copolymers overlap, so a quantitative analysis is difficult. Although this analysis can be done by ¹³C-NMR, it is more difficult, expensive and time consuming. However, when an acrylate of the formula H₂C=CHC(O)OR³⁶, wherein R³⁶ is -CH₂CH₂OR³⁷, and R³⁷ is aryl or substituted aryl, preferably aryl, is used, the peaks do not overlap at all in the ¹H-NMR spectra, and that is a great advantage in determining whether the copolymer is "contaminated" with homopolymer.

Total methylys per 1000 CH₂ are measured using different NMR resonances in ¹H and ¹³C NMR. Because of accidental overlaps of peaks and different methods of correcting the calculations, the values measured by ¹H and ¹³C NMR will usu-

ally not be exactly the same, but they will be close, normally within 10-20% at low levels of acrylate comonomer. In ^{13}C NMR the total methyls per 1000 CH_2 are the sums of the 1B_1 , 1B_2 , 1B_3 , and 1B_4 , EOC resonances per 1000 CH_2 , where the CH_2 's do not include the CH_2 's in the alcohol portions of the ester group. The total methyls measured by ^{13}C NMR do not include the minor amounts of methyls from the methyl vinyl ends or the methyls in the alcohol portion of the ester group. By ^1H NMR the total methyls are measured from the integration of the resonances from 0.6 to 1.08 and the CH_2 's are determined from the integral of the region from 1.08 to 2.49 ppm. It is assumed that there is 1 methine for every methyl group, and 1/3 of the methyl integral is subtracted from the methylene integral to remove the methine contribution. The methyl and methylene integrals are also usually corrected to exclude the values of the methyls and methylenes in the alcohol portion of the ester group, if this is practical. Because of the low levels of incorporation, this is usually a minor correction.

Figure 1 shows the ^1H -NMR spectrum of a mixture of an EGPEA ($Z=1$, R^{37} is phenyl) homopolymer in a mixture with an EGPEA copolymer with ethylene. The spectrum was obtained on a 500 MHz Bruker Avance spectrometer on a 5 mm QNP probe on samples diluted -10 mg/0.5 ml in tce-d_2 at 120°C using a 90 degree pulse of 14 μsec , a spectral width of 12.8kHz, an acquisition time of 2.6 sec and a recycle delay of 30 sec. A total of 8 transients were acquired. Spectra were referenced to tce-d_2 at 5.928 ppm. Figure 1 also indicates the assignments of the various peaks. Using EGPEA (and other acrylates described above) separation of the homopolymer and copolymer peaks is clear and quantitative analysis of the mixture is possible.

Another NMR analysis used below is end group analysis of ethylene copolymers with acrylates. 100 MHz ^{13}C NMR spectra were obtained on a Varian® Unity 400 MHz spectrometer on typically 10 wt% solutions of the polymers and 0.05 M CrAcAc in 1,2,4-trichlorobenzene (TCB) in a 10 mm probe unlocked at 120°C using a 90 degree pulse of 19.2 μsec , a spectral width of 35 kHz, a relaxation delay of 5 s, an acquisition time of 0.64 s. and inverse gated decoupling (decoupling only during acquisition). A few samples were run under similar conditions on a Bruker Avance 500 MHz NMR. A typical sample contained 310 mg polymer and 60 mg CrAcAc in TCB with a total volume of 3.1 mL (Varian recommended volume) in a 10 mm NMR tube; care was taken that the sample was very well mixed and uniform in consistency. Samples were preheated for at least 15 min. in the NMR before acquiring data. Data acquisition time was typically 10.5 hr per sample. The T1 values of the carbons of an ethylene/methyl acrylate copolymer sample were measured under these conditions to be all less than 0.9 s. The longest T1 measured was for the Bu+, EOC resonance at 14 ppm, which was 0.84 s. Spectra are referenced to the solvent - the TCB high field resonance at 127.918 ppm.

















Integrals of unique carbons in each branch were measured and were reported as number of branches per 1000 methylenes. Counted in these methylenes are those in the backbone (main chain) and branches, but not methylenes in the alcohol portions of esters, for example the $-\text{OCH}_2\text{CH}_3$ methylene in an ethyl ester. These integrals are accurate to +/- 5% relative for abundant branches and +/- 10 or 20% relative for branches present at less than 10 per 1000 methylenes. Figure 2 shows such a spectrum together with assignments of various carbon atoms.

INDEX	FREQUENCY PPM	HEIGHT
1	17613.645 175.137	8.7---J
2	16655.651 165.612	12.6---W
3	14882.774 147.983	10.5---V
4	13969.102 138.898	19.1---F
5	13546.174 134.693	44.9
6	13489.570 134.130	43.0
7	13483.697 134.072	52.0
8	13448.453 133.721	5119.1
9	13401.995 133.260	5131.0
10	13369.955 132.941	93.1
11	13359.275 132.835	41.8
12	13319.759 132.442	16.6
13	13270.631 131.953	36.9
14	13244.999 131.699	75.8
15	13215.095 131.401	5189.6
16	13181.453 131.067	4823.7
17	13154.219 130.796	84.7 TCB solvent
18	13138.199 130.637	62.3
19	13130.189 130.557	113.2
20	13101.887 130.276	5124.1
21	13063.439 129.893	68.1
22	12993.485 129.198	8.3
23	12938.484 128.651	43.9
24	12864.792 127.918	4827.4
25	12831.684 127.589	55.7
26	12822.072 127.493	36.1
27	12806.586 127.339	25.5
28	12504.876 124.339	5.6---A
29	12418.368 123.479	5.7---C
30	12269.383 121.998	12.3---U
31	11479.598 114.145	17.7---E

INDEX	FREQUENCY PPM	HEIGHT
32	6439.715 64.032	14.7---K
33	6424.764 63.883	9.9
34	4611.303 45.851	7.9---Y
35	3817.780 37.961	4.1
36	3755.302 37.340	21.6---αB ₁
37	3452.525 34.329	12.7
38	3422.087 34.027	4.3
39	3395.921 33.767	18.6---αB ₂
40	3322.229 33.034	11.4---MB ₁
41	3280.043 32.614	21.7
42	3237.857 32.195	14.6
43	3220.769 32.025	54.8---3B ₆ +, EOC
44	3177.515 31.595	27.6
45	3048.822 30.315	23.2
46	3037.608 30.204	35.5
47	3000.228 29.832	2905.6---CH ₂ 's
48	2968.188 29.513	39.1
49	2958.576 29.418	76.7
50	2931.342 29.147	36.8
51	2926.002 29.094	27.5
52	2856.048 28.398	13.0
53	2777.550 27.618	17.4
54	2752.986 27.374	6.7
55	2741.238 27.257	24.4---βB ₂ +
56	2725.752 27.103	17.3
57	2599.195 25.844	18.7
58	2286.271 22.733	53.2---2B ₅ +, EOC
59	2271.319 22.584	27.7
60	1993.640 19.823	11.6---1B ₁
61	1774.166 17.641	4.4
62	1405.173 13.972	52.3---1B ₄ +, EOC
63	1390.755 13.829	30.2
64	1265.799 12.586	5.4

Details about NMR nomenclature (e.g., 2B₅+) and other details of NMR polymer analysis, will be found in previously incorporated US5880241.

- 5 GPC molecular weights are reported versus polystyrene standards. Unless noted otherwise, GPC's were run with RI detection at a flow rate of 1 mL/min at 135°C with a run time of 30 min. Two columns were used: AT-806MS and WA/P/N 34200. A Waters RI detector was used and the solvent was
- 10 TCB with 5 grams of BHT per 3.79 L. Dual UV/RI detection GPC was run in THF at rt using a Waters 2690 separation module with a Waters 2410 RI detector and a Waters 2487 dual absorbance detector. Two Shodex columns, KF-806M, were used along with one guard column, KF-G. In addition to GPC, mo-
- 15 lecular weight information was at times determined by ¹H NMR spectroscopy (olefin end group analysis) and by melt index measurements (g/10 min at 190°C).



Example 90

Synthesis of Catalyst 24

5 In a drybox, 0.100 g Catalyst 21 and 15 mL toluene were combined. To this orange solution was added 0.177 g tris(pentafluorophenyl)boron at RT. The cloudy orange solution was stirred at RT overnight. The reaction mixture was filtered through Celite®, followed by 3x5 mL toluene wash.

10 The filtrate was evaporated to ca. 2 mL and was added 50 mL pentane. The yellow precipitate was filtered and washed

with 3x5 mL pentane. The product was dried in vacuo. Final yield of the yellow solid was 0.088 g (33%). X-ray single crystal analysis confirmed the proposed structure (Zwitter-ionic complex). ^{31}P NMR in CD_2Cl_2 : δ 60.05 (s). ^1H NMR in CD_2Cl_2 : (obtained by 1D NOE, 2D ^1H - ^{13}C correlation (HMQC) and NOESY experiments): δ 5.42 (sept, central allyl-H, 1H); 4.18 (vd, $J = 7.9$ Hz, syn-terminal allyl-H, on the C=O side, 1H); 3.04 - 3.07 (m, overlapped peaks of syn-terminal-allyl proton that is close to $(t\text{-Bu})_2\text{P}$ and anti-terminal-allyl proton that is close to C=O, 2H total); 2.82 - 2.98 (ABX pattern (X is phosphorus), $J_{\text{AB}} = 18.4$ Hz, $^2J_{\text{PH}} = 8.3$ Hz, PCHH' , 2H total); 1.77 (d, $^2J_{\text{PH}} = 12.9$ Hz, anti-terminal-allyl-H that is close to $(t\text{-Bu})_2\text{P}$, 1H); 1.35 (d, $^3J_{\text{PH}} = 14.7$ Hz, $\text{C}(\text{CH}_3)_3$, 9H); 1.18 (d, $^3J_{\text{PH}} = 14.7$ Hz, $\text{C}(\text{CH}_3)_3$, 9H). ^{19}F NMR in CD_2Cl_2 : δ -134.89 (d, $J = 20.2$ Hz, ortho-F, 6F); -159.75 (t, para-F, 3F); -165.63 (t, meta-F, 6F).

Example 91

Synthesis of Catalyst 25

In a drybox, 0.3545 g (1.806 mmole) trans-stilbene oxide and 20 mL THF were combined. The clear solution was cooled at -30°C for 0.5 h. Then 0.3 g (1.806 mmole) $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ was added. The resulting pale yellow reaction was stirred at RT for 3 h. The reaction was evaporated under full vacuum overnight. ^{31}P NMR of the ligand precursor in THF- d_8 : δ 12.00 (s, major); 26.73 (s, minor). Then 0.6443 g (1.778 mmole) ligand precursor and 20 mL THF were combined. To this solution was added 0.2404 g (0.889 mmole) nickel allyl chloride dimer. After stirring overnight, the reaction was evaporated under full vacuum. To the resulting residue was added 20 mL toluene. The solution was filtered through Celite®, followed by 3x10 mL toluene wash. The filtrate was evaporated under full vacuum. To the residue was added 30 mL pentane and the resulting solid was stirred for several min-

utes. The solid was filtered and was washed with 3x10 mL pentane. The sample was dried in vacuo for several hours. Final weight of the light brown solid was 51.4 mg (6%).

Example 92

Synthesis of Catalyst 26

In a drybox, 0.387 g (1.972 mmole) trans-stilbene oxide and 20 mL THF were combined. The clear solution was cooled to -30°C for 0.5 h. Then 0.3 g (1.972 mmole) (t-Bu)₂PLi was added. The amber reaction was stirred at RT for 2.5 h. The reaction was then evaporated under full vacuum. Then 0.6769 g (1.943 mmole) ligand precursor and 20 mL THF were combined. To the reaction was added 0.2627 g (0.9715 mmole) nickel allyl chloride dimer. After stirring overnight, the reaction was evaporated under full vacuum. To the resulting residue was added 20 mL toluene. The solution was filtered through Celite®, followed by 3x10 mL toluene wash. The filtrate was evaporated under full vacuum to dryness. Final weight of the dark brown solid was 0.5148 g (60%).

Example 93

Synthesis of Catalyst 27

In a drybox, 0.300 g (1.806 mmole) (t-Bu)₂PCH₂Li and 20 mL THF were combined in a 50 mL Schlenk flask. The flask was removed from the drybox, placed on the Schlenk line, and degassed. After cooling the pale yellow solution to 0°C with an ice bath, SO₂ was applied at 1 atm. The ice bath was removed after 20 min and the reaction was allowed to warm to RT. After 15 min, SO₂ was discontinued. The reaction mixture was stirred for an additional 25 min. The reaction mixture was then evaporated to remove excess SO₂. The reaction mixture was transferred into a drybox. The solution was evaporated under full vacuum overnight. Then 0.4058 g (1.763 mmole) ligand precursor and 20 mL THF were combined. To this yellow solution was added 0.2385 g (0.882 mmole)

nickel allyl chloride dimer. The dark red reaction mixture was stirred at RT for 2 h. The reaction mixture was then evaporated under full vacuum. The resulting red residue was triturated with 25 mL pentane. The solid was filtered and washed with 3x10 mL pentane. The sample was dried in vacuo for 45 minutes.

Example 94

Synthesis of Catalyst 28

In a drybox, 0.6214 g (3.01 mmole) bis(trimethylsilyl)sulfur diimide and 20 mL THF were combined. The yellow solution was cooled at -30°C for 45 min. Then 0.5 g (3.01 mmole) (t-Bu)₂PCH₂Li was added. The orange-brown reaction mixture was stirred at RT for 1 h. To the reaction mixture was added 0.407 g (1.505 mmole) nickel allyl chloride dimer. The red solution was stirred at RT for 3 h. The reaction mixture was then evaporated under full vacuum overnight. To the residue was added 20 mL toluene. The solution was filtered through Celite®, followed by 3x10 mL toluene wash. The filtrate was evaporated under full vacuum. Final weight of the orange-brown solid was 1.0114 g (72%). ³¹PNMR in THF-d₈: δ 93.78 (s).

Example 95

Synthesis of Catalyst 29

In a drybox, 0.4189 g (3.01 mmole) N-thionylaniline and 20 mL THF were combined. The clear solution was cooled at -30°C for 0.5 h. Then 0.5 g (3.01 mmole) (t-Bu)₂PCH₂Li was added. The resulting orange-brown reaction was stirred at RT for 1 h. To the reaction mixture was added 0.407 g (1.505 mmole) nickel allyl chloride dimer. The red solution was stirred for 3 h at RT. The reaction mixture was then evaporated under full vacuum. To the residue was added 5 mL toluene, followed by 50 mL pentane. The resulting solid was stirred for several min, filtered, and washed with 3x10 mL

pentane. Final weight of the dull orange-yellow solid was 0.884 g (67%). ^{31}P NMR in THF- d_8 : 77.18 (s).

Example 96

Synthesis of Catalyst 30

5 In a drybox, 0.485 g (3.01 mmole) 1-methylisatin and 20 mL THF were combined. The orange solution was cooled at -30°C for 45 min. Then 0.500 g (3.01 mmole) (t-Bu) $_2$ PCH $_2$ Li was added. The reaction mixture turned purple and it was stirred at RT for 1 h. To the reaction mixture was added
10 0.407 g (1.505 mmole) nickel allyl chloride dimer. The red solution was stirred at RT for 3 h. The reaction mixture was then evaporated under full vacuum overnight. To the residue was added 20 mL toluene. The solution was filtered through Celite®, followed by 3x10 mL toluene wash. The fil-
15 trate was evaporated under full vacuum. Final weight of the dark brown solid was 1.463 g.

Example 97

Synthesis of Catalyst 31

In a drybox, 0.6646 g (1.765 mmole) ArN=C(H)-C(H)=NAr
20 (Ar = 2,6-diisopropylphenyl) and 20 mL THF were combined. The yellow solution was cooled at -30°C for 0.5 h. Then 0.2932 g (1.765 mmole) (t-Bu) $_2$ PCH $_2$ Li was added. The resulting orange-red reaction was stirred at RT for 1 h. To the reaction was added 0.2386 g (0.8825 mmole) nickel allyl
25 chloride dimer. The red solution was stirred at RT for 3 h. The reaction was then evaporated under full vacuum. To the residue mixture was added 20 mL toluene. The solution was filtered through Celite®, followed by 3x10 mL toluene wash. The filtrate was evaporated under full vacuum. Final weight
30 of the dark brown solid was 0.6937 g (62%).

Example 98

Synthesis Catalyst 32

In a drybox, 0.250 g (1.64 mmole) sodium chloromethyl-sulfonate and 20 mL THF were combined. The mixture was cooled to -30°C for 0.5 h. Then 0.25 g (1.64 mmole) $(t\text{-Bu})_2\text{PLi}$ was added and the mixture was stirred and allowed to slowly warm up to RT. As it warmed, the reaction mixture became cloudy orange. The reaction mixture was stirred at RT for two days. The resulting cloudy brown solution was evaporated under full vacuum. Then 0.425 g (1.62 mmole) ligand precursor and 20 mL THF were combined. To this brown suspension was added 0.219 g (0.81 mmole) nickel allyl chloride dimer. The resulting red-brown reaction mixture was stirred at RT for 3 h. The reaction mixture was then evaporated under full vacuum to dryness. The sample was triturated with 25 mL pentane. The solid was filtered and washed with 3x10 mL pentane. It was dried in vacuo for 1.5 h. Final weight of the light brown solid was 0.369 g (67%).

Example 99

Synthesis of Catalyst 33

In a dry box, to a 100 mL flask containing 10 mL of THF solution of 1,3-diisopropylcarbodiimide (0.0816 g, 0.64 mmole), was slowly added the THF solution of $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ (0.107 g, 0.64 mmole). The solution changed from yellow to colorless upon stirring overnight. Solvent was removed. The residue was rinsed with pentane. White powder (0.136 g, 0.467 mmole) was obtained in 72% yield. ^1H NMR of the ligand precursor (in C_6D_6): δ 0.98 (d, 18H, $t\text{-Bu-H}$); 1.3 (dd, 12H, $-\text{CH}(\text{CH}_3)_2$); 1.96 (s, d, 2H, PCH_2); 3.80 (m, 2H, $-\text{CH}(\text{CH}_3)_2$). It contained one equivalent of hydrolyzed product that might be resulted of hydrolysis of the lithium salt during the period outside of the drybox. ^{31}P NMR (C_6D_6): δ 21.837 (s); 13.177 (s). In the dry box, 0.0542 g (0.185 mmole) of the

ligand precursor and 0.0441 g (0.092 mmole) allyl-Ni-bromide dimer $\{((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2\}$ were mixed in 10 mL THF in a 50 mL flask. The mixture was stirred for 1 h. THF was removed in vacuo and the residue was extracted with ether. After removal of ether, the product was washed with pentane. Light brown solid (0.0434 g, 0.098 mmole) was obtained in 53% yield. $^{31}\text{PNMR}$ (C_6D_6): δ 61.89 (s).

Example 100

Synthesis of Catalyst 34

In a dry box, to a 100 mL RB flask containing 10 mL THF solution of 1,3-bis-(2,6-diisopropylphenyl) carbodiimide (0.245 g, 0.675 mmole), was slowly added THF solution of $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ (0.112 g, 0.675 mmole). Upon stirring overnight, the solution turned from yellow to colorless. Solvent was removed and the product was washed with pentane. White powder (0.272 g, 0.514 mmole) was obtained in 76% yield. $^1\text{HNMR}$ (C_6D_6): δ 0.98 (d, 24H, $-\text{CH}(\text{CH}_3)_2$); 1.37 (d, 18H, $t\text{-Bu-H}$); 2.41 (d, 2H, PCH_2); 3.26 (m, 2H, $-\text{CH}(\text{CH}_3)_2$); 3.56 (m, 2H, $-\text{CH}(\text{CH}_3)_2$); 6.92 - 7.60 (m, 6H, Ar-H). $^{31}\text{PNMR}$ (C_6D_6): δ 19.12 (s). In the dry box, 0.0814 g (0.154 mmole) of the ligand precursor and 0.0366 g (0.077 mmole) of the allyl-Ni-bromide dimer $\{((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2\}$ were mixed in 10 mL THF in a 50 mL RB flask and the mixture was stirred for 1 h. THF was removed in vacuo and the residue was extracted with ether. Upon removal of the ether, the product was washed with pentane. Yellow powder (0.0906 g, 0.133 mmole) was obtained in 87% yield. $^{31}\text{PNMR}$ (C_6D_6): δ 59.68 (s).

Example 101

Synthesis of Catalyst 35

In a dry box, to the 100 mL RB flask containing 10 mL of THF solution of 1,3-bis(trimethylsilyl) carbodiimide (0.0813 g, 0.436 mmole), was added slowly a THF solution of $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ (0.0725 g, 0.436 mmole). The solution turned

from yellow to colorless after stirring overnight. Solvent was removed. The white solid residue, which is soluble in pentane, was mixed with 0.1036 g (0.218 mmole) of allyl-Ni-bromide complex ($((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2$) in 30 mL THF. The mixture was stirred for an hour. Solvent was then removed under vacuum. The residue was extracted with ether. Solvent was removed. The solid was rinsed with pentane. Orange powder (0.0515 g, 0.102 mmole) was obtained in 23% yield. $^1\text{H NMR}$ (C_6D_6): δ 0.21 (s, 1H, allyl-H); 0.25 (s, 18H, -Si(CH₃)₃); 0.94 (d, 19H, t-Bu-H and allyl-H); 1.28 (s, 2H, PCH₂); 3.0 (s, 1H, allyl-H); 3.3 (s, 3H, -OCH₃); 3.62 (s, 1H, allyl-H). $^{31}\text{P NMR}$ (C_6D_6): δ 57.65.

Example 102

Synthesis of Catalyst 36

In a dry box, to a 100 mL RB flask containing 10 mL of THF solution of 1,3-dicyclohexylcarbodiimide (0.143 g, 0.694 mmole), was added slowly a THF solution of (t-Bu)₂PCH₂Li (0.115 g, 0.694 mmole) at RT. The color of the solution turned yellow and the mixture was stirred overnight. Solvent was removed under vacuum and the white solid residue was mixed with 0.1649 g (0.348 mmole) of allyl-Ni-bromide complex ($((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2$) in 30 mL of THF. The mixture was stirred for 1 h. Solvent was then removed under vacuum. The residue was extracted with ether. Ether was then removed. The solid was rinsed with pentane. Orange powder (0.150 g, 0.287 mmole) was obtained in 41% yield. $^{31}\text{P NMR}$ (C_6D_6): δ 62.55 (s).

Example 103

Synthesis of Catalyst 37

In a dry box, to a 100 mL RB flask containing 10 mL THF solution of 1-naphthylisothiocyanate (0.079 g, 0.426 mmole), was slowly added a THF solution of (t-Bu)₂PCH₂Li (0.0709 g, 0.426 mmole) at -30°C. The solution turned yellow orange and

it was stirred for one h while the solution warmed up to RT. Solvent was removed. The solid residue was mixed with 0.101 g (0.312 mmole) of allyl-Ni-bromide complex ($((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2$) in 30 mL THF. The mixture was stirred for 1 h. Solvent was removed under vacuum. The residue was extracted with ether. Solvent was evaporated and the product was rinsed with pentane. Brown powder (0.176 g, 0.351 mmole) was obtained in 82% yield. $^{31}\text{PNMR}$ (C_6D_6): δ 73.43 (s, major).

Example 104

Synthesis of Catalyst 38

In a dry box, to a 100 mL RB flask containing 10 mL THF solution of cyclohexylisothiocyanate (0.0439 g, 0.311 mmole), was added slowly a THF solution of $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ (0.0568g, 0.311 mmole) at -30°C . The solution turned yellow orange it was stirred for 1 h, during which time the solution warmed up to RT. Solvent was removed. The solid residue was mixed with 0.0739 g (0.156 mmole) of allyl-Ni-bromide complex ($((2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr})_2$) in 30 mL THF. The mixture was stirred for 1 h. Solvent was removed under vacuum. The residue was extracted with ether. The solvent was removed. The product was rinsed with pentane. Brown powder (0.0773 g, 0.169 mmole) was obtained in 54% yield. $^{31}\text{PNMR}$ (C_6D_6): δ 66.69 (s, major).

Example 105

Synthesis of Catalyst 39

In a dry box, benzoylisocyanate (0.1966 g, 1.336 mmole) was dissolved in 20 mL THF in a 100 mL RB flask. The solution was cooled to ca. -30°C in a freezer. $(t\text{-Bu})_2\text{PCH}_2\text{Li}$ (0.2220 g, 1.336 mmole) was added to the above cold solution under stirring. The mixture turned dark red. It was allowed to stir at RT for 4 h. The solution was then evaporated to dryness. To the ligand precursor (ca. 1.300 mmole) was added 20 mL THF. Under stirring, nickel allyl chloride

dimer (0.1760 g, 0.6500 mmole) was added to the mixture. The solution became dark red. It was allowed to stir at RT for 2 h. Solvent was evaporated. Toluene (ca. 8 mL) was added to the brick red residue. Upon brief stirring, large excess of pentane was added. The resulting solid was filtered, followed by 3X pentane wash, and dried in vacuo. Pale orange solid (0.4223 g, 72%) was obtained.

Examples 106-120

Polymerizations with catalysts 24 through 38 are shown in Tables 14 and 15.

Table 14

Condition I in Table 3


Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI	TON
106	24*	7.81	26	118 (52.2)	4,495/4.9	13,900
107	25	2.89	15	123 (0.6)	17,614/8.9	5,150
108	26	8.26	21	122 (173.1)	19,394/11.2	14,700
109	27	4.66	33	129 (147.6)	226,688/8.8	8,300
110	28	1.07	20	127 (182.2)	34,420/33.5	1,900
111	29	6.14	17	123 (159.3)	12,964/5.2	10,900
112	30	9.71	32	123 (172.2)	4,898/8.1	17,300
113	31	7.82	13	121 (126.8)	563,495/5.1	13,900
114	32	11.75	12	131 (225.5)	254,365/106.4	20,940

* No B(C₆F₅)₃ was used. The catalyst self-initiated ethylene polymerization.

Table 15

Ethylene Polymerization Using 0.02 mmole Catalyst, 5 mL TCB and 10 eq B(C₆F₅)₃, at RT under 6.9 MPa Ethylene for 18 h

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw	TON
115	33	4.427	27	129 (173.8)	Trimodal	7604
116	34	0.181	25	117 (116.9)	Trimodal	343
117	35	0.698	15	126 (190.1)	67,352	1160
118	36	3.388	27	128 (165.6)	Insoluble in TCB	4452
119	37	0.083	35	130 (137.2)	Trimodal	140
120	38	0.321	21	129 (168.5)	70,329	535



Examples 121-150

Examples 121-150 are listed in Tables 16-20 below. The structures for these compounds illustrate just one of the possible products and binding modes that may have formed during the synthesis of the ligand and the subsequent synthesis of the nickel compound and are not meant to be restrictive. The polymerizations were carried out according to General Polymerization Procedure A. Varying amounts of acrylate homopolymer are present in some of the samples. In Tables 16-20, the yield of the polymer is reported in grams and includes the yield of the dominant ethylene/acrylate copolymer as well as the yield of any acrylate homopolymer that was formed. Molecular weights were determined by GPC, unless indicated otherwise. All copolymerizations were run for 18 h, unless otherwise noted.

General Polymerization Procedure A: In a drybox, a glass insert was loaded with the nickel compound and, optionally, a Lewis acid (e.g., BPh_3 or $\text{B}(\text{C}_6\text{F}_5)_3$) and borate (e.g., NaBAF or LiBArF) and any other specified cocatalysts. Next, the solvent was added to the glass insert followed by the addition of any co-solvents and then comonomers. The insert was greased and capped. The glass insert was then loaded in a pressure tube inside the drybox. The pressure

tube was then sealed, brought outside of the drybox, connected to the pressure reactor, placed under the desired ethylene pressure and shaken mechanically. After the stated reaction time, the ethylene pressure was released and the glass insert was removed from the pressure tube. The polymer was precipitated by the addition of MeOH (~20 mL). The polymer was then collected on a frit and rinsed with MeOH and, optionally, acetone. The polymer was transferred to a pre-weighed vial and dried under vacuum overnight. The polymer yield and characterization were then obtained.

Table 16

Ethylene Homopolymerizations, (0.02 mmol Cmpd, 25 °C, 1.0 MPa, 10 mL TCB, 10 equiv B(C₆F₅)₃)

Ex.	Cmpd	NaBAF equiv	PE g	PE TO	M.W.	Total Me
121	40	10	1.08 ^a	1,920	M _w =37,044; M _n =4,989; M _w /M _n =7.43	22.4
122	40	1	2.49 ^a	4,440	M _w =34,072; M _n =4,693; M _w /M _n =7.26	44.6
123	42	0	1.01	1,800	M _w =25,754; M _n =905 M _w /M _n =28.46	79.2
124	43	0	1.79	3,190	M _w =12,361; M _n =519; M _w /M _n =23.80	59.4

^aFormation of a surface polymer film on the reaction mixture appeared to limit the productivity of these polymerizations.

Table 17

Ethylene/Acrylate Copolymerizations (6.9 MPa, 100°C) (0.02 mmol Cmpd, 10 mL total of TCB + Acrylate, 20 equiv B(C₆F₅)₃)

Ex.	Cmpd	Acrylate mL	NaBAF equiv	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
125	42	EGPEA 1	0	0.38	0.5	M _n (¹ H)=3,531	19.7
126	41	EGPEA 1	0	0.077	0.3	M _n (¹ H)=16,192	17.7
127	43	EGPEA 1	0	0			
128	44	EGPEA 1	0	0.094	0.4	M _w =3,259; M _p =1,067; M _n =988; M _w /M _n =3.30	nd
129	40	EGPEA 1	0	0.10	1.3 ^a	M _w =11,396; M _p =7,282; M _n =4,581; M _w /M _n =2.49	6.9
130	40	EGPEA 1	1	2.40	0.66 ¹³ C 0.33 IC 0.33 EG	M _w =6,649; M _p =6,271; M _n =3,104; M _w /M _n =2.14	nd
131	40	EGPEA 1	20	8.61	0.38 ¹³ C 0.19 IC 0.19 EG	M _w =6,674; M _p =5,860; M _n =3,209; M _w /M _n =2.08	nd
132	40	EGPEA 2	20	5.50	0.77 ¹³ C 0.39 IC 0.38 EG	M _w =5,238; M _p =4,484; M _n =2,423; M _w /M _n =2.16	nd
133	41	EGPEA 2	20	0.61	A	M _w =5,032; M _p =4,711; M _n =2,330; M _w /M _n =2.16	nd
134	42	EGPEA 2	20	1.06	1.0	M _w =4,237; M _p =3,286; M _n =1,548; M _w /M _n =2.74	14.2
135	43	EGPEA 2	20	0.70	A	nd	nd
136	40	EGPEA 4	20	2.02	0.70	M _w =3,201; M _p =2,755; M _n =1,688; M _w /M _n =1.90	11.0
137	40	MA 0.5	10	13.21	0.41 ¹³ C 0.21 IC 0.20 EG	M _w =5,008; M _p =4,932; M _n =1,582; M _w /M _n =3.16	8.6
138	40	MA 0.5	20	11.45	0.57 ¹³ C 0.33 IC 0.24 EG	M _w =4,461; M _p =3,994; M _n =1,755; M _w /M _n =2.54	10.2
139	40	HA 2	20	1.48	0.60 ¹³ C 0.21 IC 0.39 EG	M _w =4,034; M _p =3,699; M _n =1,849; M _w /M _n =2.18	7.4
140	40	HA 1	20	9.88	0.36 ¹³ C 0.15 IC 0.21 EG	M _w =5,834; M _p =5,525; M _n =2,251; M _w /M _n =2.59	8.2
141	40 .005mmol	EGPEA 1	10	0.40	0.5	M _w =7,123; M _n =3,183; M _p =6,843; M _w /M _n =2.24	8.5

^aLarge amount of homopolymer was formed: overlaps with any copolymer resonances in the ¹H NMR spectrum.

Table 18

Ethylene/Acrylate Copolymerizations (6.9 MPa)(0.02 mmol Cmpd, 18 h, 10 mL total of TCB + EGPEA, 20 equiv $B(C_6F_5)_3$, 10 equiv NaBAF)

Ex.	Cmpd	EGPEA mL	Temp. °C	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
142	40	2	120	12.40	0.69 ^{13}C 0.37 IC 0.32 EG	$M_w=3,813$; $M_n=1,577$; $M_p=3,234$; $M_w/M_n=2.42$	nd
143	40	4	120	5.16	Trace ^a	$M_w=2,660$; $M_p=2,528$; $M_n=1,305$; $M_w/M_n=2.04$	nd
144	41	2	120	5.30	1.1	$M_w=3,331$; $M_p=3,047$; $M_n=1,386$; $M_w/M_n=2.40$	13.8
145	40	4	120	3.30	1.5	$M_w=3,125$; $M_p=3,139$; $M_n=1,476$; $M_w/M_n=2.12$	16.8
146	40	4	120	4.10	2.2		
147	40	2	130	8.99	2.8	$M_w=3,479$; $M_p=3,202$; $M_n=1,510$; $M_w/M_n=2.30$	25.7
148	40 0.001 mmol	2	120	4.57	2.2	$M_w=3,914$; $M_p=3,592$; $M_n=1,761$; $M_w/M_n=2.22$	32

^aLarge amount of acrylate homopolymer was formed, preventing quantitative determination of percent acrylate incorporation in the copolymer. Ester groups incorporated both in branches and in unsaturated end groups.

Table 19

Ethylene/Acrylate Copolymerizations (3.5 MPa, 120°C) (18 h,10 mL total of TCB + EGPEA, 20 equiv $B(C_6F_5)_3$, 10 equivNaBAF)













Ex.	Cmpd	EGPEA mL	Temp. °C	Yield G	Acrylate Incorp. mol%	M.W.	Total Me
149	40 0.01 mmol	1	120	2.48	0.69 ^{13}C 0.37 IC 0.32 EG	$M_w=3,675$; $M_p=3,403$; $M_n=1,701$; $M_w/M_n=2.16$	nd
150	40 0.005 mmol	1	120	0.21	Trace ^a	$M_w=3,272$; $M_p=3,403$; $M_n=1,701$; $M_w/M_n=2.01$	nd










^aLarge amount of acrylate homopolymer was formed, preventing quantitative determination of percent acrylate incorporation in the copolymer.












Table 20













Branching Analysis for Some MA and HA Copolymers of Table 17^a







Ex.	Total M	Me	Et	Hex+ & eoc	Am+ & eoc	Bu+ & oc	M ester
137	8.6	2.4	1.0	6.4	5.8	5.2	2.5
138	10.2	2.5	2.1	7.5	6.1	5.6	3.9
139	7.4	2.4	0.6		5.3	5.0	
140	8.2	3.1			5.1	5.1	

^aPr and Bu branches were not detected in these copolymers.









Examples 151-439

Examples 151-439 are listed in Tables 21-57 below. They were carried out with nickel complexes 45-97 shown above. For each of 45-97 the counterion is BAF. The polymerizations were carried out according to General Polymerization Procedure A. Varying amounts of acrylate homopolymer are present in some of the isolated polymers. In Tables 21-58, the yield of the polymer is reported in grams and includes the yield of the dominant ethylene/acrylate copolymer as well as the yield of any acrylate homopolymer that was formed. Molecular weights were determined by GPC, unless indicated otherwise. Mole percent acrylate incorporation and total Me were determined by ^1H NMR spectroscopy, unless

indicated otherwise. Mole percent acrylate incorporation is typically predominantly IC, unless indicated otherwise. The $\text{LiB}(\text{C}_6\text{F}_5)_4$ used (LiBArF) included 2.5 equiv of Et_2O . All copolymerizations were run for 18 h, unless otherwise noted.

5

Table 21

Reproducibility of Ethylene/Acrylate Copolymerizations Using
45 (0.02 mmol Compd, 6.9 MPa., 120°C, 18 h, 10 mL Total of
TCB + Acrylate, 40 equiv $\text{B}(\text{C}_6\text{F}_5)_3$)

Ex.	Acrylate mL	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
151	EGPEA 2	9.77	1.20 (^{13}C)	$M_p=8,651; M_w=8,930; M_n=3,983; \text{PDI}=2.24$	54.6
152	EGPEA 2	12.47	1.4	$M_p=12,036; M_w=12,662; M_n=4,449; \text{PDI}=2.85$	51.8
153	EGPEA 2	10.73	2.0	$M_p=13,657; M_w=14,740; M_n=5,348; \text{PDI}=2.76$	54.5
154	HA 2	2.08	1.28 (^{13}C)	$M_p=6,838; M_w=6,534; M_n=1,331; \text{PDI}=4.91$	53.2
155	HA 2	2.42	1.16 (^{13}C)	$M_p=6,625; M_w=7,524; M_n=3,305; \text{PDI}=2.28$	54.9

10

Table 22

Variation of Acrylate Concentration, Acrylate Structure,
Solvent and Temperature in Ethylene/Acrylate Copolymeriza-
tions Using 45 (0.02 mmol Compd, 6.9 MPa E, 18 h, 10 mL Total
of TCB + Acrylate, 40 equiv B(C₆F₅)₃)

Ex.	Acrylate mL	Temp °C	Yield g	Acryl. incorp. (mol%)	M.W.	Total Me
156	EGPEA 1	120	16.72	0.7	M _p =12,452; M _w =13,952; M _n =4,319; PDI=3.23	69.8
157	EGPEA 2	120	12.47	1.4	M _p =12,036; M _w =12,662; M _n =4,449; PDI=2.85	51.8
158	EGPEA 4	120	5.37	2.70 (¹³ C)	M _p =6,623; M _w =9,878; M _n =3,388; PDI=2.92	42.6 (¹³ C)
159	EGPEA 2	100	4.21	1.60 (¹³ C)	M _p =20,949; M _w =21,275; M _n =9,605; PDI=2.21	26.1 (¹³ C)
160	EGPEA 4	100	3.13	3.60 (¹³ C)	M _p =12,760; M _w =14,733; M _n =6,092; PDI=2.42	20.6 (¹³ C)
161	IDA ^a 2	80	0.89	1.6 (¹³ C)	nd	nd
162	IDA ^b 1	80	1.75	nd	M _p =30,258; M _w =32,201; M _n =13,047; PDI=2.47	nd
163	HA 1	120	2.70	0.66 (¹³ C)	M _p =8,851; M _w =9,678; M _n =2,252; PDI=4.30	54.7
164	HA 2	120	2.08	1.28 (¹³ C)	M _p =6,838; M _w =6,534; M _n =1,331; PDI=4.91	53.2
165	MA 0.25	120	13.08	0.10 (¹³ C) ^c	M _p =10,797; M _w =12,929; M _n =4,798; PDI=2.69	76.0
166	MA 0.5	120	13.17	0.17 (¹³ C) ^d	M _p =12,267; M _w =13,485; M _n =4,587; PDI=2.94	72.0
167	MA 1	120	15.45	0.19 (¹³ C) ^d	M _p =13,376; M _w =13,971; M _n =4,694; PDI=2.98	78.6

^aTotal Volume = 5 mL: 2 mL IDA + 3 mL Bu₂O; No TCB used. ^bTotal Volume = 5 mL: 4 mL TCB and 1 mL IDA; ^cAcrylate homopolymer not detected by ¹³C NMR spectroscopy. ^dAcrylate homopolymer detected by ¹³C NMR spectroscopy.

Table 23

Variation of Acrylate Concentration and Temperature in Ethylene/EGPEA Copolymerizations with Cmpd. 46 (0.02 mmol Cmpd, 6.9 MPa E, 18 h, 10 mL Total of TCB + EGPEA, 40 equiv

$B(C_6F_5)_3$

Ex.	EGPEA mL	Temp °C	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
168	2	120	2.17	0.03 (^{13}C)	$M_p=12,550$; $M_w=13,744$; $M_n=5,936$; PDI=2.32	
169	2	100	1.88	0.44 (^{13}C)	$M_p=17,362$; $M_w=17,905$; $M_n=8,075$; PDI=2.16	28.6
170	4	120	1.22	Nd ^a	$M_p=8,651$; $M_w=8,930$; $M_n=3,983$; PDI=2.24	
171	4	100	0.032	1.1	$M_p=13,111$; $M_w=13,076$; $M_n=6,062$; PDI=2.16	24.3

^aDue to significant homopolymer formation, percent acrylate incorporation in the copolymer was not determined by 1H NMR spectroscopy.

Table 24

Effect of Counterion on Ethylene/EGPEA Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa E, 120°C, 18 h, 8 mL TCB, 2 mL EGPEA, 40 equiv $B(C_6F_5)_3$)

Ex.	Counterion	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
172	$[B[3,5-C_6H_3-(CF_3)_2]_4]^-$	12.47	1.4	$M_p=12,036$; $M_w=12,662$; $M_n=4,449$; PDI=2.85	51.8
173	$[B(C_6F_5)_4]^-$	16.72	1.5	$M_p=15,316$; $M_w=17,100$; $M_n=6,108$; PDI=2.80	57.1
174	$[N(SO_2CF_3)_2]^-$	5.38	1.9	$M_p=12,551$; $M_w=13,097$; $M_n=4,949$; PDI=1.78	52.6

Table 25

Effect of Bu₂O Addition on Ethylene/Acrylate Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa E, 120°C, 18 h, 8 mL Total of TCB + Bu₂O, 2 mL EGPEA, 40 equiv B(C₆F₅)₃)

Ex.	Bu ₂ O ^a mL	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
175	0	12.47	1.4	M _p =12,036; M _w =12,662; M _n =4,449; PDI=2.85	51.8
176	2	5.10	1.72 (¹³ C)	M _p =6,952; M _w =8,846; M _n =3,044; PDI=2.91	65.0
177	4	8.73	1.08 (¹³ C)	M _p =7,135; M _w =8,894; M _n =3,313; PDI=2.68	66.5
178	8	11.94	b	Dual UV/RI. UV: M _p =7,616; M _w =50,244; M _n =1,819; PDI=27.62; RI: M _p =12,075; M _w =14,395; M _n =5,150; PDI=2.80	Nd

^aAmount of acrylate homopolymer formation increases as the amount of Bu₂O increases. ^bAccording to ¹³C NMR spectroscopy, the polymer was a mixture of polyethylene and poly(EGPEA); no copolymer resonances were observed.

Table 26

Variation of the Lewis Acid (LA) Cocatalyst in Ethylene/Acrylate Copolymerizations, Including Copolymerization in the Absence of a Lewis Acid Cocatalyst (0.02 mmol Cmpd, 6.9 MPa E; 120°C, 18 h, 10 mL Total of TCB + Acrylate)

Ex.	Cmpd	Acrylate mL	LA/equiv	Yield g	Acrylate Incorp. Mol%	M.W.	Total Me
179	45	EGPEA 2	B(C ₆ F ₅) ₃ 40	12.47	1.4	M _p =12,036; M _w =12,662; M _n =4,449; PDI=2.85	51.8
180	45	EGPEA 2	BPh ₃ 40	2.73	2.2	M _p =11,442; M _w =13,348; M _n =4,897; PDI=2.73	49.5
181	45	EGPEA 2	AlPh ₃ 40	1.15	a	M _p =3,207; M _w =4,233; M _n =1,723; PDI=2.46	Nd
182	45	EGPEA 1	B(C ₆ F ₅) ₃ 40	16.72	0.7	M _p =12,452; M _w =13,952; M _n =4,319; PDI=3.23	69.8
183	45	EGPEA 1	B(C ₆ F ₅) ₃ 5	2.62	0.23 (¹³ C)	M _p =12,529; M _w =12,302; M _n =5,147; PDI=2.39	55.8
184	46	THA 2	B(C ₆ F ₅) ₃ 40	2.37	0.23	M _p =12,775; M _w =13,777; M _n =7,165; PDI=1.92	
185	46	THA 2	None	0.63	0.64 (¹³ C)	Dual UV/RI. UV: M _p =8,098; M _w =687,552; M _n =6,306; PDI=109.04; RI: M _p =9,383; M _w =12,732; M _n =5,694; PDI=2.24	34.0

^aDue to significant homopolymer formation, percent acrylate incorporation in the copolymer was not determined by ¹H NMR spectroscopy.

Table 27

Effect of alpha-Diimine Structure on Ethylene/Acrylate Copolymerizations (0.02 mmol Compd, 6.9 MPa E, 120°C, 18 h, 9 mL TCB, 1 mL EGPEA, 40 equiv B(C₆F₅)₃)

Ex.	Compd	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
186	45	16.72	0.7	M _p =12,452; M _w =13,952; M _n =4,319; PDI=3.23	69.8
187	47	14.02	0.8	M _p =9,915; M _w =13,027; M _n =3,660; PDI=3.56	69.5
188	48	0	—	—	—
189	50	3.96	0.55 (¹³ C)	M _p =14,350; M _w =15,584; M _n =7,421	72.0 (¹³ C)
190	51	2.28	1.8	M _p =15,543; M _w =17,651; M _n =7,561; PDI=2.33	64.8
191	55	7.64	1.6	M _p =14,350; M _w =15,584; M _n =7,421	68.6
192	56	8.81	Nd ^c	M _p =946; M _w =7,044; M _n =911; PDI=7.73	Nd
193	57	12.28	1.1	M _p =14,408; M _w =16,770; M _n =6,740; PDI=2.49	71.7
194	58	18.19	1.0	M _p =14,315; M _w =15,940; M _n =5,887; PDI=2.71	85.6
195	59	15.30	0.8	M _p =12,221; M _w =16,421; M _n =5,647; PDI=2.91	78.6
196	60	0	—	—	—
197	61	16.78	0.8	M _p =13,852; M _w =16,074; M _n =4,701; PDI=3.42	77.0
198	62	2.28	0.9	M _p =1,162; M _w =1,609; M _n =642; PDI=2.51	75.2
199	63	1.08	1.6	M _p =10,915; M _w =12,370; M _n =5,370; PDI=2.30	74.2
200	64	5.32	1.6	M _p =42,905; M _w =43,993; M _n =16,290; PDI=2.70	105.0
201 ^a	64	5.55	0.3	RI (THF, rt): M _p =101,394; M _w =1,154,459; M _n =5,516; PDI=209.31	101.5
202 ^a	64	1.66 ^b	0.3	RI (THF, rt): M _p =94,326; M _w =5,952,749; M _n =8,304; PDI=716.88	99.5

^aEx 201 and 202 include 20 equiv B(C₆F₅)₃; Ex. 201 also includes 20 equiv LiB(C₆F₅)₄ and Ex. 202 includes 20 equiv NaBAF; ^bSome polymer was lost in isolation; ^cNot determined due to broad ¹H NMR spectrum.

Table 28

Effect of α -Diimine Structure on Ethylene/Acrylate Copolymerizations (0.02 mmol Compd, 6.9 MPa E; 120°C, 18 h, 8 mL TCB, 2 mL of EGPEA, 40 equiv B(C₆F₅)₃)

Ex.	Compd	Yield g	Acrylate Incomp. mol%	M.W.	Total Me
203	45	12.47	1.4	M _p =12,036; M _w =12,662; M _n =4,449; PDI=2.85	51.8
204	46	2.17	0.03 (¹³ C)	M _p =12,550; M _w =13,744; M _n =5,936; PDI=2.32	°
205	47	4.10	2.0	M _p =8,181; M _w =9,903; M _n =3,243; PDI=3.05	59.9
206	48	0	—	—	—
207	49	0	—	—	—
208	50	1.10	1.7	Dual UV/RI. UV: M _p =19,292; M _w =374,248; M _n =7,268; PDI=51.49; RI: M _p =22,404; M _w =26,916; M _n =11,257; PDI=2.39	60.5
209	51	2.32	3.1	M _p =14,689; M _w =17,651; M _n =4,327; PDI=2.29	77.8
210	52	0.087	a	Dual UV/RI. UV: M _p =21,556; M _w =47,428; M _n =6,142; PDI=7.72; RI: M _p =40,121; M _w =40,676; M _n =18,309; PDI=2.22	a
211	53	9.41	2.9 (¹³ C)	M _p =485; M _w =1,035; M _n =317; PDI=3.27	84.2 (¹³ C)
212	56	0.49		Dual UV/RI. UV: M _p =2,195 and 75; M _w =1,301,735; M _n =3,351; PDI=388.41; RI: M _p =2,652; M _w =84,063; M _n =3,608; PDI=23.30	
213	57	2.94		M _p =9,779; M _w =12,435; M _n =4,519; PDI=2.75	
214	58	7.77	1.7	Dual UV/RI. UV: M _p =21,192; M _w =201,274; M _n =10,087; PDI=19.95; RI: M _p =22,402; M _w =95,991; M _n =11,047; PDI=8.69	60.3

Table 28 (cont'd)

Ex.	Cmpd	Yield g	Acrylate In- corp. mol%	M.W.	Total Me
215	61	5.77	2.4	$M_p=9,535$; $M_w=11,659$; $M_n=4,357$; PDI=2.68	56.1
Examples 216-221 below include 20 equiv of $B(C_6F_5)_3$					
216	71	3.45	0.6	$M_p=20,054$; $M_w=19,855$; $M_n=9,070$; PDI=2.19	63.4
217	72	1.32	1.6	$M_p=14,328$; $M_w=16,242$; $M_n=6,327$; PDI=2.57	66.2
218	73	0.27			
219	69	1.79	1.5	Dual UV/RI. UV: $M_p=15,033$; $M_w=21,410$; $M_n=6,666$; PDI=3.21; RI: $M_p=8,520$; $M_w=16,322$; $M_n=2,159$; PDI=7.56	62.1
220 ^b	45	7.50	1.0	$M_p=13,125$; $M_w=14,026$; $M_n=6,211$; PDI=2.26	51.0
221 ^c	55	3.07	1.3	$M_p=7,458$; $M_w=10,026$; $M_n=3,566$; PDI=2.81	58.2

^a¹H NMR spectrum is broad; ^b20 equiv NaBAF present; ^c20 equiv LiBAF present.

5

Table 29

Effect of Pressure on Ethylene/EGPEA Copolymerizations (0.02
mmol Cmpd, 120°C, 18 h, 8 mL TCB, 2 mL EGPEA, 40 equiv

$B(C_6F_5)_3$)

Ex.	Cmpd	Press. MPa	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
222	45	6.9	12.47	1.4	$M_p=12,036$; $M_w=12,662$; $M_n=4,449$; PDI=2.85	51.8
223	45	4.1	4.30	2.9	$M_p=7,492$; $M_w=11,174$; $M_n=3,738$; PDI=2.99	57.7
224	47	6.9	4.10	2.0	$M_p=8,181$; $M_w=9,903$; $M_n=3,243$; PDI=3.05	59.9
225	47	4.1	0.70	3.3	Dual UV/RI. UV: $M_p=8,392$; $M_n=4,579$; $M_w=174,212$; PDI=38.05; RI: $M_p=9,874$; $M_n=5,504$; $M_w=18,139$; PDI=3.30	59.8

10

Table 30

¹³C NMR Branching Analysis for EGPEA Copolymers

Ex.	Total Me	M	Et	Pr	Bu	Hex+ & eoc	Am+ & eoc	Bu+ & eoc	Me _s Bu (%)	Me _s Bu (%)
151	51.4	32.2	6.5	2.8	2.1	5.5	7.3	9.9	3.68	19.86
158	42.6	23.7	6.9	3.8	2.1	4.6	8.1	8.3	Nd	Nd
169	27.3	19.0	1.7	1.7	1.0	3.2	3.4	4.8	Nd	Nd
159	26.1	17.7	2.9	1.2	1.0	1.9	2.5	4.2	Nd	Nd
160	20.6	14.2	2.0	1.6	0.9	2.0	3.8	2.8	Nd	Nd
211	84.2	36.9	10.2	3.1	4.1	21.8	31.0	34.0	9	54.8
199	72.0	45.1	6.2	3.3	4.3	7.8	13.4	17.4	Nd	Nd

5

Table 31

¹³C NMR Branching Analysis for MA Copolymers

Ex.	Total Me	Me	Et	Pr	Bu	Hex+ & eoc	Am+ & eoc	Bu+ & eoc	Me _s Bu (%)	Me _s Bu (%)
167	78.2	45.2	9.9	4.1	4.7	9.8	14.5	19.0	4.4	19.9
166	72.0	41.7	10.0	3.9		8.5	11.9	16.3	4.2	18.9
165	76.0	42.7	11.0	4.0		8.7	12.8	18.3	5.8	23.1
250	52.2	30.1	8.0	2.4	2.8	6.2	8.4	11.7	Nd	Nd
251	62.4	35.1	8.7	3.6	4.6	7.4	11.3	15.0	Nd	Nd
252	65.5	39.1	8.5	2.6	3.8	7.7	12.7	15.3	Nd	Nd
253	79.6	44.9	11.1	3.4	4.1	10.0	14.7	20.1	Nd	Nd
254	61.9	47.5	9.0	3.6	5.0	8.9	14.0	1.8	Nd	Nd
255	35.7	23.1	4.2	1.9	1.4	3.0	5.8	6.9	Nd	Nd
256	43.9	27.1	5.5	2.6	1.9	4.4	6.4	8.7	Nd	Nd

Table 32

¹³C NMR Branching Analysis for HA Copolymers

Ex.	Total Me	Me	Et	Pr	Bu	Am+ & eoc	Bu+ & eoc	Me _s Bu (%)	Me _s Bu (%)
154	53.2	27.5	5.3	3.1	2.8	16.4	17.3	trace	trace
163	54.7	29.4	6.4	3.5	3.3	13.4	15.4	3.8	14.2
155	54.9	32.2	6.4	3.0	2.2	13.6	13.3	Nd	Nd
253	32.8	22.1	3.2	1.5	1.1	6.2	6.0	Nd	Nd
257	23.9	16.7	1.7	1.5	1.8	5.9	4.0	Nd	Nd
258	28.3	19.7	3.2	1.4	1.4	3.7	4.0	Nd	Nd

Table 33

¹³C NMR Branching Analysis for THA Copolymers

Ex.	Total Me	Me	Et	Pr	Bu	Hex+ & eoc	Am+ & eoc	Bu+ & eoc	Me _s Bu (%)	Me _s Bu (%)
184	34.0	22.7	3.2	2.3	1.8	3.7	4.1	5.8	3.3	15.7

5

Table 34

Effect of Counterion on Ethylene/EGPEA Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa E, 100°C, 18 h, 9 mL TCB, 1 mL EGPEA, 20 equiv B(C₆F₅)₃)

Ex.	Counterion	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
226	[B[3,5-C ₆ H ₃ -(CF ₃) ₂] ₄] ⁺	7.55	0.7	M _p =24,874; M _w =27,982; M _n =11,277; PDI=2.48	46.4
227	[B(C ₆ F ₅) ₄] ⁺	5.41	0.9	M _p =18,648; M _w =20,469; M _n =8,130; PDI=2.52	44.3

10

Table 35

Effect of Solvent on Ethylene/EGPEA Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa E, 100°C, 18 h, 9 mL Solvent, 1 mL EGPEA, 20 equiv B(C₆F₅)₃)

Ex.	Solvent	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
228	TCB	7.55	0.7	M _p =24,874; M _w =27,982; M _n =11,277; PDI=2.48	46.4
229	p-Xylene	11.32	0.6	M _p =21,849; M _w =21,579; M _n =9,271; PDI=2.33	52.7
230	2,2,4-Trimethylpentane	2.04	1.6	M _p =12,625; M _w =13,906; M _n =5,591; PDI=2.74	44.3
231	FC-75	1.04	5.4	M _p =1,837; M _w =3,468; M _n =1,265; PDI=2.74	18.7

15

Table 36

Effect of $B(C_6F_5)_3$ and NaBAF Concentrations on Ethylene/EGPEA Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa E, 100°C, 18 h, 8 mL TCB, 2 mL of EGPEA)

Ex.	$B(C_6F_5)_3$ equiv	NaBAF equiv	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
232	40	20	7.53	1.2	$M_p=16,054$; $M_w=19,338$; $M_n=8,066$; PDI=2.40	38.6
233	40	10	5.38	1.3	$M_p=17,925$; $M_w=18,882$; $M_n=8,495$; PDI=2.22	27.5
234	20	10	7.01	1.5	$M_p=17,546$; $M_w=18,485$; $M_n=7,769$; PDI=2.38	29.6
235	20	10	6.29	1.2	$M_p=14,365$; $M_w=16,722$; $M_n=6,646$; PDI=2.52	29.5
236 ^a	20	10	4.69	1.3	$M_p=16,912$; $M_w=18,207$; $M_n=7,126$; PDI=2.57	33.6

5 ^a250 ppm phenothiazine was added to the acrylate; For entries 1 - 4, the acrylate contained 250 ppm 1,4-benzoquinone.

Table 37

10 Effect of Solvent on Ethylene/Acrylate Copolymerizations Using Cmpd 45 (0.02 mmol Cmpd, 6.9 MPa, 100°C, 18 h, 8 mL Solvent, 2 mL of EGPEA)

Ex.	Solvent	$B(C_6F_5)_3$ equiv	NaBAF equiv	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
237	TCB	40	20	7.53	1.2	$M_p=16,054$; $M_w=19,338$; $M_n=8,066$; PDI=2.40	38.6
238	TCB	20	10	7.01	1.5	$M_p=17,546$; $M_w=18,485$; $M_n=7,769$; PDI=2.38	29.6
239	Toluene	40	20	6.05	1.0	$M_p=14,852$; $M_w=16,995$; $M_n=7,853$; PDI=2.16	48.2
240	2,2,4-Tri- methyl- pentane	40	20	1.51	1.7	$M_p=6,633$; $M_w=7,942$; $M_n=4,157$; PDI=1.91	41.8
241	2,2,4-Tri- methyl- pentane	40	20	2.09	1.3	$M_p=12,923$; $M_w=16,462$; $M_n=6,313$; PDI=2.61	42.7
242	Chloro- benzene	20	10	9.16	1.0	$M_p=16,417$; $M_w=18,316$; $M_n=7,496$; PDI=2.44	33.3
243	p-Xylene	20	10	7.46	1.0	$M_p=16,975$; $M_w=18,211$; $M_n=7,246$; PDI=1.84	33.1

Table 38

Effect of Acrylate Concentration, Acrylate Structure and Temperature on Ethylene/Acrylate Copolymerizations (0.02 mmol Cmpd, 6.9 MPa E, 18 h, 10 mL Total of TCB + Acrylate, 20 equiv B(C₆F₅)₃)

Ex.	Cmpd	Acrylate mL	Temp °C	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
244	45	EGPEA 1	100	7.55	0.7	M _p =24,874; M _w =27,982; M _n =11,277; PDI=2.48	46.4
245	45	EGPEA 1	80	2.20	0.6	M _p = 38,136; M _w =39,514; M _n =20,849; PDI=1.90	49.6
246	45	EGPEA 0.5	80	5.41	0.4	M _p =45,864; M _w =45,281; M _n =23,339; PDI=1.94	81.7
247	45	HA 1	100	5.68	0.66 (¹³ C)	M _p =22,173; M _w =21,451; M _n =9,298; PDI=2.31	32.8 (¹³ C)
248	45	HA 1	80	1.65	1.0	M _p =27,677; M _w =29,086; M _n =12,715; PDI=2.29	26.3
249	47	EGPEA 1	80	0.08	0.8	M _p =17,915; M _w =17,005; M _n =6,567; PDI=	51.4
250	45	MA 0.25	100-135	10.58	0.31 (¹³ C)	M _p =28,080; M _w =21,336; M _n =4,233; PDI=5.04	52.1
251	45	MA 0.5	100-135	8.36	0.51 (¹³ C)	M _p =20,078; M _w =17,262; M _n =3,831; PDI=4.51	62.1
252	47	MA 0.25	100-135	3.61	0.57 (¹³ C)	M _p =4,716; M _w =6,741; M _n =1,796; PDI=3.75	65.1
253	47	MA 0.5	100-135	1.90	0.61 (¹³ C)	Dual UV/RI UV: M _p =3,803; M _w =5,095; M _n =1,350; PDI=3.77; RI: M _p =5,237; M _w =6,717; M _n =3,805; PDI=2.39	78.8
254	57	MA 0.25	100-135	4.22	0.37 (¹³ C)	M _p =8,697; M _w =14,347; M _n =3,656; PDI=3.92	61.5
10 equiv of NaBAF was added to Ex. 255 below and 20 equiv of NaBAF were added to entries 256-261 below.							
255	45	MA 0.5	100	4.28	1.09 (¹³ C)	M _p = 13,677; M _w = 15,046; M _n = 7,270; PDI= 2.07	35.7
256	45	MA 0.5	100	9.36	0.53 (¹³ C)	M _p =16,828; M _w =17,679; M _n =7,546; PDI= 2.34	43.7
257	45	HA 2	100	1.07	1.20 (¹³ C)	M _p =8,501; M _w = 9,737; M _n =4,703; PDI= 2.07	23.9
258	45	HA 1	100	4.76	0.53 (¹³ C)	M _p =16,421; M _w =17,244; M _n =7,900; PDI=2.18	28.3
259	45	EGPEA 2	135	1.20	1.1	M _p = 7,174; M _w =8,652; M _n =3,719; PDI=2.33	74.9
260	45	EGPEA 2	130	5.59	1.2	M _p =9,545; M _w =10,772; M _n =4,927; PDI=2.19	58.2
261	45	EGPEA 2	120	7.01	1.5	M _p =17,546; M _w =18,485; M _n =7,769; PDI=2.38	29.6

Table 39

Effect of α -Diimine Structure on Ethylene/EGPEA Copolymerizations (0.02 mmol Cmpd, 6.9 MPa E, 100°C 18 h, 9 mL TCB,

1 mL EGPEA, 20 equiv $B(C_6F_5)_3$)

Ex.	Cmpd	Yield g	Acrylate Incorp. mol%	M.W.	Total Me
262	55	7.55	0.7	$M_p=24,874$; $M_w=27,982$; $M_n=11,277$; PDI=2.48	46.4
263	68	0.32	0.5	$M_p=13,743$; $M_w=18,058$; $M_n=5,435$; PDI=3.32	60.3
264	69	1.48	0.3	$M_p=838$; $M_w=1,731$; $M_n=796$; PDI=2.17	57.5

Table 40

Effect of α -Diimine Structure on Ethylene/Acrylate Copolymerizations (0.02 mmol Cmpd, 6.9 MPa E, 18 h, 8 mL TCB,

2 mL of EGPEA)

Ex.	Cmpd	Temp (°C)	$B(C_6F_5)_3$ (equiv)	NaBAF (equiv)	Yield (g)	Acrylate Incorp. (mol%)	M.W.	Total Me
265	45	100	40	20	7.53	1.2	$M_p=16,054$; $M_w=19,338$; $M_n=8,066$; PDI=2.40	38.6
266	76	100	40	20	4.22	1.0	$M_p=24,124$; $M_w=27,307$; $M_n=14,435$; PDI=1.89	31.4
267	75	100	40	20	5.68	1.2	$M_p=14,987$; $M_w=16,393$; $M_n=6,919$; PDI=2.37	79.2
268	74	100	40	20	3.42	0.6	$M_p=31,607$; $M_w=34,104$; $M_n=17,087$; PDI=2.00	41.2
269	77	100	40	20	0.025	1.9	$M_n(^1H)$: No olefins detected	33.5
270	45	135	20	10	1.20	1.1	$M_p=7,174$; $M_w=8,652$; $M_n=3,719$; PDI=2.33	74.9
271	64	135	20	10	1.05	0.5	$M_p=25,027$; $M_w=30,553$; $M_n=12,666$; PDI=2.41	111.4
272	45	135	20	10	2.55	1.0	$M_p=6,743$; $M_w=8,241$; $M_n=887$; PDI=9.29	85.8

Table 41

Effect of Borane Concentration and Inhibitor on Ethyl-
ene/EGPEA Copolymerizations (0.02 mmol Cmpd 45, 6.9 MPa E,
120°C, 18 h, 6 mL TCB, 4 mL EGPEA)

Ex.	B(C ₆ F ₅) ₃ equiv	Inhibitor	Yield g	Acrylate In- corp. mol%	% Ester in Copolymer ^a	M.W.	Total Me
273	40	None	5.37	2.70 (¹³ C)	12%	M _p =6,623; M _w =9,878; M _n =3,388; PDI=2.92	42.6 (¹³ C)
274	20	NaBAF 20 equiv	3.02	2.2	20%	M _p =12,928; M _w =13,956; M _n =5,371; PDI=2.60	28.4
275	20	BQ 250 ppm	2.59	2.6	16%	M _p =8,739; M _w =10,424; M _n =3,480; PDI=3.00	27.5
276	20	NaBAF 20 equiv BQ 250 ppm	3.07	2.4	23%	M _p =11,454; M _w =12,303; M _n =4,114; PDI=	29.9

^aThe percent of the ester groups in the ¹H NMR spectrum of the isolated polymer sample that belong to copolymer. Due to the high acrylate concentration, the isolated polymers all contained some homopolymer. The EGPEA used contained 100 ppm hydroquinone in addition to the NaBAF and 1,4-benzoquinone (BQ) inhibitors that were added to the individual runs.

Table 42

Steric Effects on Ethylene/MA Copolymerizations Utilizing
Long Reaction Times (90 h) and Low Catalyst Concentrations

(0.019 mmol Cmpd), (211 equiv B(C₆F₅)₃ and 105 equiv NaBAF

5 were used. Mole % incorp. and total Me determined by ¹³C NMR
spectroscopy.)

Ex	Cmpd	MA mL (p-Xylene mL)	Press MPa	Temp °C	Yield g	Acrylate Incorp mol%	M.W.	Total Me
277	45	0.5 (9.5)	3.5	120	0.892	1.33	M _p =6,812; M _w =7,201; M _n =3,410; PDI=2.05	72.5
278	76	0.5 (9.5)	3.5	120	0.937	1.02	M _p =7,911; M _w =8,993; M _n =4,499; PDI=2.00	82.7
279	74	0.5 (9.5)	3.5	120	0.840	0.93	M _p =8,726; M _w =9,799; M _n =4,511; PDI=2.00	94.9
280	64	0.5 (9.5)	3.5	120	0.106	nd	M _p =13,521; M _w =14,744; M _n =6,125; PDI=2.41	nd
281	45	1.0 (14.0)	3.5	120	0.007	nd	nd	nd
282	45	0.5 (9.5)	6.9	120	3.340	0.82	M _p =12,403; M _w =13,853; M _n =5,681; PDI=2.44	50.4
283	76	0.5 (9.5)	6.9	120	4.221	0.48	M _p =20,376; M _w =20,960; M _n =9,659; PDI=2.17	58.1
284	74	0.5 (9.5)	6.9	120	5.424	0.43	M _p =28,364; M _w =30,997; M _n =12,568; PDI=2.47	68.5
285	64	0.5 (9.5)	6.9	120	0.95	0.30	M _p =47,858; M _w =47,408; M _n =20,796; PDI=2.28	97.2
286	45	1.0 (14.0)	6.9	120	2.518	0.97	M _p =13,043; M _w =14,076; M _n =5,931; PDI=2.37	46.3
287	45	0.5 (9.5)	6.9	100	3.865	0.62	M _p =23,142; M _w =24,270; M _n =10,544; PDI=2.30	30.9
288	76	0.5 (9.5)	6.9	100	3.720	0.45	M _p =34,987; M _w =36,412; M _n =16,929; PDI=2.15	37.4
289	74	0.5 (9.5)	6.9	100	4.041	0.51	M _p =53,630; M _w =50,877; M _n =24,819; PDI=2.05	48.0
290	64	0.5 (9.5)	6.9	100	0.860	0.50	M _p =64,690; M _w =60,660; M _n =31,328; PDI=1.94	78.1
291	45	1.0 (14.0)	6.9	100	1.631	0.83	M _p =17,935; M _w =17,277; M _n =7,070; PDI=2.44	35.7

Table 43

¹³C NMR Branching Analysis for MA Copolymers of Table 42

Ex.	Total Me	Me	Et	Pr	Bu	Hex+ & eoc	Am+ & eoc	Bu+ & eoc
277	72.5	42.6 58.7%	10.0 13.8%	3.8 5.2%	3.9 5.4%	7.1 9.8%	13.1 18.1%	16.2 22.4%
278	82.7	48.9 59.1%	10.3 12.5%	4.4 5.3%	4.2 5.0%	10.3 12.5%	15.0 18.2%	19.2 23.2%
279	94.9	54.5 57.5%	13.4 14.1%	5.2 5.5%	5.3 5.6%	12.7 13.4%	17.0 18.0%	21.8 22.9%
282	50.4	32.0 63.6%	5.7 11.4%	2.6 5.2%	2.5 5.0%	6.7 13.3%	8.3 16.5%	10.0 19.8%
283	58.1	37.5 64.5%	6.6 11.3%	3.0 5.1%	2.7 4.7%	6.3 10.8%	8.8 15.1%	11.1 19.1%
284	68.5	44.4 64.8%	6.9 10.1%	3.5 5.1%	3.3 4.8%	7.1 10.4%	10.1 14.7%	13.6 19.9%
285	97.2	65.4 67.3%	10.0 10.3%	4.1 4.2%	4.1 4.2%	9.4 4.6%	13.3 13.7%	17.8 18.3%
286	46.3	29.6 64.0%	5.1 11.0%	2.4 5.1%	1.9 4.0%	5.2 11.3%	6.7 14.5%	9.2 19.9%
287	30.9	20.4 66.0%	4.1 13.3%	1.4 4.6%	1.0 3.1%	2.7 8.7%	3.7 12.0%	5.0 16.1%
288	37.4	24.0 64.2%	4.8 12.8%	1.9 5.0%	1.1 3.1%	3.8 10.1%	4.6 12.2%	6.8 18.1%
289	48.0	32.6 67.9%	4.7 9.7%	2.5 5.1%	1.7 3.6%	4.5 9.5%	5.9 12.3%	8.3 17.3%
290	78.1	53.9 69.0%	7.3 9.3%	3.3 4.2%	3.1 3.9%	7.7 9.9%	10.6 13.5%	13.7 17.5%
291	35.7	23.2 35.7%	4.0 11.1%	1.7 4.7%	1.8 5.2%	4.4 12.4%	5.4 15.0%	6.8 19.1%

Table 44
Ethylene/EGPEA Copolymerizations in Chlorobenzene (18 h, 10 mL Total Volume of Chlorobenzene + EGPEA)

Ex.	Cmpd mmol	EGPEA mL	B(C ₆ F ₅) ₃ equiv	Na- BAF equiv	Press MPa	Temp °C	Yield g	Acrylate Incorp mol%	M.W.	Total Me
292	45 0.01	1	40	20	6.9	100	10.28	0.4	M _p =22,374; M _w =23,126; M _n =10,630; PDI=2.18	49.5
293	45 0.005	1	80	40	6.9	100	7.84	0.5	M _p =26,320; M _w =26,956; M _n =12,371; PDI=2.18	82.7
294	64 0.005	1	80	40	6.9	100	1.85	0.4	M _p =83,096; M _w =81,919; M _n =39,427; PDI=2.08	71.5
295	55 0.005	1	80	40	6.9	100	1.87	0.7	M _p =22,984; M _w =24,347; M _n =12,365; PDI=1.97	41.3
296	45 0.01	1	40	20	3.5	120	5.59	0.6	M _p =9,544; M _w =10,892; M _n =4,896; PDI=1.97	73.5
297	64 0.01	1	40	20	3.5	120	0.78	0.4	M _p =26,286; M _w =26,534; M _n =13,114; PDI=2.02	134.2
298	55 0.01	1	40	20	3.5	120	1.97		M _p =7,250; M _w =8,005; M _n =3,348; PDI=2.39	
299	45 0.01	1	40	20	6.9	120	12.49	0.6	M _p =14,470; M _w =15,044; M _n =6,519; PDI=2.31	70.6
300	45 0.01	2	40	20	6.9	120	6.01	1.5	M _p =11,778; M _w =12,804; M _n =5,707; PDI=2.24	61.2
301	45 0.01	3	40	20	6.9	120	4.14	2.4	M _p =7,806; M _w =10,643; M _n =4,312; PDI=2.47	48.6
302	45 0.005	1	80	40	6.9	120	7.29	0.6	M _p =11,733; M _w =13,519; M _n =5,644; PDI=2.40	67.2
303	45 0.005	2	80	40	6.9	120	5.07	1.4	M _p =9,852; M _w =11,599; M _n =4,755; PDI=2.44	67.1
304	78 0.02	2	20	10	6.9	120	0.96	1.4 ^a	M _p =30,063; M _w =25,126; M _n =7,262; PDI=3.46	28.0
305	78 0.02	4	20	10	6.9	120	1.06	1.1 ^a	M _p =4,852; M _w =6,734; M _n =2,384; PDI=2.82	12.5
306	45 0.005	1	80	40	3.5	120	2.64	0.8	M _p =10,797; M _w =11,715; M _n =5,047; PDI=2.32	66.8
307	45 0.005	2	80	40	3.5	120	2.95	1.9	M _p =8,636; M _w =9,312; M _n =4,496; PDI=2.07	67.6
308	45 0.01	2	40	20	3.5	120	2.96	1.2	M _p =7,616; M _w =8,630; M _n =3,709; PDI=2.33	66.3
309	45 0.01	3	40	20	3.5	120	2.70	1.9	M _p =5,039; M _w =7,443; M _n =2,709; PDI=2.75	59.0
310	45 0.0025	1	160	80	3.5	120	1.59	0.9	M _p =7,737; M _w =8,732; M _n =4,051; PDI=2.16	73.0
311	45 0.0025	1	160	80	6.9	100	2.52	0.8	M _p =25,609; M _w =25,456; M _n =11,960; PDI=2.13	27.5
312	45 0.0025	2	160	80	6.9	100	2.02	2.1	M _p =20,773; M _w =21,386; M _n =10,385; PDI=2.06	22.1
313	45 0.0025	0.5	160	80	6.9	100	5.85	trace	M _p =23,609; M _w =25,970; M _n =12,143; PDI=2.14	nd
314	45 0.00125	1	160	80	6.9	100	1.67	1.0	M _p =22,495; M _w =23,371; M _n =11,316; PDI=2.07	27.4
315	45 0.00125	1	160	80	6.9	120	2.96	0.9	M _p =12,729; M _w =13,757; M _n =6,189; PDI=2.22	68.2
316	45 0.0025	0.5	160	80	6.9	120	7.27	0.4	M _p =13,244; M _w =15,491; M _n =6,318; PDI=2.45	70.8
317	45 0.0025	2	160	80	6.9	120	3.22	1.5	M _p =12,047; M _w =13,044; M _n =6,043; PDI=2.16	55.6
318	45 0.0025	1	160	80	6.9	120	5.02	0.7	M _p =12,942; M _w =13,493; M _n =6,073; PDI=2.22	58.7

^aDue to the high homopolymer content of the polymer sample, the reported percent acrylate incorporation in the copolymer is an approximation.

Table 45

Ethylene/EGPEA Copolymerizations in TCB: Variation of Catalyst Concentration and Structure, and Temperature (6.9 MPa E, 18 h, 10 mL Total Volume of TCB + EGPEA)

Ex.	Cmpd mmol	EG- PEA mL	B(C ₆ F ₅) ₃ equiv	Na- BAF Equiv	Temp °C	Yield g	Acrylate Incorp mol%	M.W.	Total Me
319	45 0.01	1	40	20	140	3.01	0.5	M _p =7,507; M _w =8,668; M _n =3,753; PDI=2.31	87.5
320	45 0.01	2	40	20	140	2.43	1.6	M _p =6,568; M _w =7,865; M _n =3,535; PDI=2.22	80.8
321	45 0.005	1	80	40	140	2.41	0.7	M _p =7,192; M _w =8,650; M _n =3,909; PDI=2.21	88.7
322	45 0.005	2	80	40	140	1.66	1.6	M _p =6,197; M _w =7,988; M _n =3,234; PDI=2.47	82.0
323	45 0.0025	1	160	80	140	4.54	0.7	M _p =7,443; M _w =8,725; M _n =3,328; PDI=2.62	91.6
324	96 0.02	1	20	10	120	2.14	1.2	M _p =9,128; M _w =12,153; M _n =5,089; PDI=2.39	120.9
325	97 0.02	1	20	10	120	1.79	0.6	M _p =56,495; M _w =56,319; M _n =25,240; PDI=2.23	18.0

5

Table 46

Ethylene/MA Copolymerizations: Variation of Temperature
(0.0025 mmol Cmpd, 160 equiv B(C₆F₅)₃, 80 equiv NaBAF, 6.9
MPa E, 18 h, 0.5 mL MA, 9.5 mL Chlorobenzene)

Ex	Cmpd	Temp °C	Yield g	Acrylate Incorp Mol%	M.W.	Total Me
326	45	100	2.90	0.53 (¹³ C)	M _p =17,308; M _w =18,706; M _n =9,144; PDI=2.05	31.8
327	45	120	2.59	0.45 (¹³ C)	M _p =9,967; M _w =10,394; M _n =4,713; PDI=2.21	51.8

5

Table 47

¹³C NMR Branching Analysis for MA and HA Copolymers of Tables
46, 49 and 50

Ex.	Total Me	Me	Et	Pr	Bu	Hex+ & eoc	Am+ & eoc	Bu+ & eoc
326	31.8	21.3	3.6	1.6	1.6	2.9	4.7	5.3
327	51.8	31.6	5.8	13.1	2.6	4.8	8.9	11.2
346	71.7	45.2	7.6	3.7	3.4	6.2	11.0	15.2
347	71.8	45.9	7.8	3.8	3.8	6.5	11.1	14.4
354	48.6	29.7	6.1	2.9	2.6	3.7	6.9	9.9
364	58.5	36.5	7.8	2.7	2.8		9.6	11.6
366	60.2	36.0	7.9	3.4	2.6	5.7	9.5	12.8
383	31.1	22.0	3.5	1.2	1.6	2.8	4.0	4.5
384	28.5	19.1	2.6	1.6	1.4	2.0	4.4	5.3
388	98.6	68.1	12.2	2.5	2.8	11.2	12.1	15.8

10

Table 48

Ethylene/EGPEA Copolymerizations: Variation of Catalyst Structure and Cocatalyst Concentration (18 h, 6.9 MPa E, 120°C, 0.5 mL EGPEA)

Ex.	Cmpd mmol	Solvent mL	B(C ₆ F ₅) ₃ equiv	Na- BAF Equi v	Yield g	Ac- rylate Incorp mol%	M.W.	Total Me
328	45 0.00125	CB 9.5	320	160	1.80	0.4	M _p =13,525; M _w =13,741; M _n =6,126; PDI=2.24	59.8
329	45 0.00125	CB 9.5	640	160	3.72	0.3	M _p =11,892; M _w =13,222; M _n =6,184; PDI=2.14	61.6
330	45 0.00125	CB 9.5	1600	160	2.90	0.4	M _p =11,920; M _w =12,850; M _n =6,419; PDI=2.00	65.3
331	45 0.00125	CB 9.5	320	320	3.05	0.3	M _p =12,013; M _w =12,568; M _n =5,783; PDI=2.17	66.8
332	45 0.00125	Toluene 9.5	320	160	3.52	0.3	M _p =10,810; M _w =12,116; M _n =5,518; PDI=2.20	65.4
333	45 0.00125	CB 4.5	320	160	1.47	0.7	M _p =13,399; M _w =14,553; M _n =7,141; PDI=2.04	53.4
334	61 0.0025	CB 9.5	320	160	1.70	0.4	M _p =6,206; M _w =7,385; M _n =3,287; PDI=2.25	65.7
335	57 0.0025	CB 9.5	320	160	0.76	0.3	M _p =15,079; M _w =15,975; M _n =8,241; PDI=1.94	68.5
336	74 0.0025	CB 9.5	320	160	3.58	0.2	M _p =29,889; M _w =34,141; M _n =17,674; PDI=1.93	72.6
337	71 0.0025	CB 9.5	320	160	0.055	0.2	M _p =13,750; M _w =15,066; M _n =7,535; PDI=2.00	91.2

5

Table 49
Ethylene/Acrylate Copolymerizations: Variation of Catalyst Structure, Catalyst and Cocatalyst Concentration (18 h, 6.9 MPa E, 120°C)

Ex.	Cmpd mmol	Solvent/mL Acrylate/mL	B(C ₆ F ₅) ₃ Equiv	Na- BAF equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
338	45, 0.00125	CB/9, EGPEA/1	640	160	1.79	0.6	M _p =11,857; M _w =12,974; M _n =5,887; PDI=2.20	59.4
339	45, 0.0025	CB /14, EGPEA/1	640	160	3.47	0.4	M _p =11,853; M _w =12,966; M _n =5,513; PDI=2.35	64.2
340	45, 0.00125	CB /14, EGPEA/1	640	160	2.02	0.5	M _p =12,305; M _w =12,062; M _n =5,229; PDI=2.31	67.1
341	45, 0.00125	CB /14, EGPEA/1	960	320	2.26	0.4	M _p =11,788; M _w =12,131; M _n =5,524; PDI=2.20	60.9
342	45, 0.0025	CB /13, EGPEA/2	960	160	2.54	0.7	M _p =10,220; M _w =11,156; M _n =5,349; PDI=2.09	62.1
343	74, 0.00125	CB /14, EGPEA/1	960	160	0.77	0.2	M _p =29,720; M _w =32,471; M _n =17,281; PDI=1.88	66.1
344	74, 0.0025	CB /13, EGPEA/2	960	160	1.35	0.5	M _p =26,232; M _w =27,641; M _n =14,194; PDI=1.95	69.6
345	74, 0.00125	Toluene/14, EGPEA/1	960	160	1.55	0.2	M _p =30,222; M _w =32,909; M _n =18,006; PDI=1.83	69.6
346	74, 0.00125	CB /14.5, MA/0.5	960	160	0.82	0.3 (¹³ C)	M _p =23,118; M _w =23,916; M _n =10,009; PDI=2.39	71.7 (¹³ C)
347	74, 0.0025	CB /14, MA/1	960	160	1.32	0.4 (¹³ C)	M _p =11,962; M _w =13,390; M _n =6,417; PDI=2.09	71.8 (¹³ C)
348	45, 0.00125	TCB/9.5, EGPEA/0.5	640	320	2.33	trace	M _p =14,132; M _w =15,668; M _n =6,596; PDI=2.38	nd
349	45, 0.00125	TCB/9, EGPEA/1	640	320	2.03	0.9	M _p =11,996; M _w =13,748; M _n =6,235; PDI=2.21	51.9
350	45, 0.0019	TCB/9.5, EGPEA/0.5	421	210	4.71	0.4	M _p =13,326; M _w =15,974; M _n =6,186; PDI=2.58	57.4
351	45, 0.0019	TCB/9, EGPEA/1	421	210	3.29	0.8	M _p =11,534; M _w =13,641; M _n =5,635; PDI=2.42	60.2
352	45, 0.0019	TCB/9.5, EGPEA/0.5	210	210	4.43	0.4	M _p =12,953; M _w =13,730; M _n =5,116; PDI=2.68	nd
353	45, 0.0019	p-Xylene/9.5, EGPEA/0.5	421	210	5.62	0	M _p =14,910; M _w =32,190; M _n =8,859; PDI=3.63	71.8
354	45, 0.0019	TCB/9.75, MA/0.25	421	210	0.81	0.3 (¹³ C)	M _p =11,398; M _w =13,504; M _n =5,827; PDI=2.32	48.6 (¹³ C)
355	78, 0.01	TCB/9, EGPEA/1	80	40	0.59	Nd ^a	M _p =64,840; M _w =57,576; M _n =24,348; PDI=2.36	nd
356	78, 0.01	TCB/9, EGPEA/1	80	40	0.56	Nd ^a	M _p =64,496; M _w =59,869; M _n =30,765; PDI=1.95	nd
357	76, 0.0019	TCB/9.5, EGPEA/0.5	421	210	3.95	0.5	M _p =21,762; M _w =23,924; M _n =12,118; PDI=1.97	67.5

Table 49 (cont'd)

Ex.	Compd mmol	Solvent/mL Acrylate/mL	B(C ₆ F ₅) ₃ Equiv	Na- BAF equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
358	45, 0.0019	TCB/9, EGPEA/1	421	210	3.74	0.6	M _p =12,616; M _w =15,891; M _n =6,055; PDI=2.62	57.1
359	45, 0.0019	p-Xylene/8, Butyl Ether/1 EGPEA/1	421	210	1.24	0.7	M _p =8,918; M _w =9,634; M _n =4,250; PDI=2.27	62.8
360	45, 0.0019	p-Xylene/4.5, Butyl Ether/4.5, EGPEA/1	421	210	0.91	0.8	M _p =6,913; M _w =8,108; M _n =4,024; PDI=2.02	67.6
361	45, 0.0019	Butyl Ether/9, EGPEA/1	421	210	0.97	1.0	M _p =6,100; M _w =6,969; M _n =3,626; PDI=1.92	66.8
362	45, 0.00125	p-Xylene/9, EGPEA/1	640	320	0.98	0.5	M _p =21,762; M _w =23,924; M _n =12,118; PDI=1.97	67.5
363	45, 0.0019	TCB/9, HA/1	421	210	0.025	Nd	Nd	Nd
364	45, 0.00125	p-Xylene/9, HA/1	640	320	2.53	0.6 (¹³ C)	M _p =11,816; M _w =11,804; M _n =5,225; PDI=2.26	58.5 (¹³ C)
365	45, 0.0019	TCB/9.5, MA/0.5	421	210	0.083	Nd	Nd	Nd
366	45, 0.00125	p-Xylene/9.5, MA/0.5	640	320	2.58	0.75 (¹³ C)	M _p =10,362; M _w =10,505; M _n =5,123; PDI=2.05	67.5 (¹³ C)
367	79, 0.0019	TCB/9, EGPEA/1	421	105	0.018	Nd	Nd	Nd
368	59, 0.0019	TCB/9, EGPEA/1	421	105	0.51	1.1	M _p =6,858; M _w =7,745; M _n =3,968; PDI=1.95	47.2
369	80, 0.0019	TCB/9, EGPEA/1	421	105	0.59	0.6	M _p =11,196; M _w =14,898; M _n =6,228; PDI=2.39	60.0
370	81, 0.0019	TCB/9, EGPEA/1	421	105	0.004	Nd	Nd	Nd
371	45, 0.0019	p-Xylene/9, EGPEA/1	421	105	3.20	0.6	M _p =14,259; M _w =14,764; M _n =6,250; PDI=2.36	55.6
372	45, 0.0019 ^c	TCB/9, EGPEA/1	421	105	2.64	0.6	M _p =13,840; M _w =15,593; M _n =7,075; PDI=2.20	57.1
373	82, 0.0019	TCB/9, EGPEA/1	421	105	0.32	Nd	M _p =35,840; M _w =37,957; M _n =20,356; PDI=1.86	Nd
374	45, 0.0019	TCB/9, EGPEA/1	421	105	0.18	2.0	M _p =13,679; M _w =15,497; M _n =7,382; PDI=2.10	60.4
375	45, 0.0019	p-Xylene/9, EGPEA/1	421	105	0.86	1.2	M _p =6,984; M _w =8,147; M _n =3,927; PDI=2.07	55.6
376	64, 0.002	p-Xylene/3, EGPEA/2	200	100	0.25	4.2 ^b	M _p =13,668; M _w =14,464; M _n =6,967; PDI=2.08	59.4
377	64, 0.002	p-Xylene/8, EGPEA/2	200	100	0.76	3.1	M _p =25,728; M _w =26,593; M _n =13,836; PDI=1.92	87.2
378	64, 0.002	p-Xylene/4.5, MA/0.5	200	100	0.52	2.3 (¹³ C)	M _p =30,000; M _w =31,999; M _n =14,434; PDI=2.22	98.6 (¹³ C)
379	64, 0.002	p-Xylene/4.5, MA/0.5	800	100	0.68	Nd	M _p =28,722; M _w =31,214; M _n =13,352; PDI=2.34	Nd

^aAny copolymer resonances are obscured by the homopolymer resonances. ^bPercent acrylate incorporation in the copolymer is an estimate due to the high homopolymer content of the sample. ^c+100 equiv MeA(BHT)₂

Table 50

Ethylene/Acrylate Copolymerizations: Variation of Solvent
and Acrylate Substituent (18 h, 6.9 MPa E, 100°C)

Ex.	Cmpd mmol	Solvent/mL Acrylate/mL	B(C ₆ F ₅) ₃ Equiv	Na- BAF equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
380	45 0.0019	Toluene/9 EGPEA/1	421	105	1.28	1.1	M _p =20,773; M _w =21,618; M _n =10,131; PDI=2.13	38.0
381	45 0.0019	Toluene/9 HA/1	421	105	1.40	0.4	M _p =20,340; M _w =20,560; M _n =9,573; PDI=2.15	49.2
382	45 0.0019	CB/9 HA/1	421	105	0.57	0.5	M _p =18,173; M _w =18,605; M _n =8,670; PDI=2.15	43.4
383	45 0.0019	Toluene/9.5 MA/0.5	421	105	1.99	0.6 (¹³ C)	M _p =20,997; M _w =21,705; M _n =10,684; PDI=2.03	31.1 (¹³ C)
384	45 0.0019	CB/9.5 MA/0.5	421	105	1.33	0.4	M _p =13,279; M _w =15,028; M _n =7,635; PDI=1.97	28.5

5

Table 51

Ethylene/Hexyl Acrylate Copolymerizations: Variation of
Catalyst Structure (18 h, 6.9 MPa E, 120°C, 1 mL Hexyl Ac-
rylate, 9 mL p-Xylene)

10

Ex.	Cmpd 0.005 mmol	B(C ₆ F ₅) ₃ equiv	LiB(C ₆ F ₅) ₄ equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
385	79	80	40	1.92	1.3	M _p =20,773; M _w =21,618; M _n =10,131; PDI=2.13	78.4
386	81	80	40	0.011	Nd	Nd	Nd
387	53	80	40	0.41	2.3	M _p =782; M _w =1,183; M _n =409; PDI=2.89	98.4

Table 52

Ethylene/EGPEA Copolymerizations: Variation of p-
Substituent on the N-Aryl Ring (0.0019 mmol Cmpd, 18 h, 6.9
MPa E, 120°C, 1 mL EGPEA, 9 mL TCB)

Ex.	Cmpd	B(C ₆ F ₅) ₃ equiv	LiB(C ₆ F ₅) ₄ equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
388	45	211	105	3.98	0.8	M _p =14,113; M _w =16,389; M _n =6,722; PDI=2.44	53.2
389	83	211	105	3.78	0.8	M _p =15,156; M _w =16,926; M _n =7,557; PDI=2.24	54.4
390	84	211	105	2.80	1.1	M _p =14,422; M _w =15,390; M _n =6,960; PDI=2.21	48.7

5

Table 53

Ethylene/2,2,3,3,3-Pentafluoropropyl acrylate (PPA) Copolym-
erizations (0.0019 mmol Cmpd, 18 h, 10 mL Total Volume of p-
Xylene + PPA, 100°C, 6.9 MPa E)

10

Ex.	Cmpd	PPA mL	B(C ₆ F ₅) ₃ equiv	NaBAF equiv	Yield g	Ac- rylate Incorp mol%	M.W.	Total Me
391	45	1	211	105	5.93	0.2	M _p =25,838; M _w =26,041; M _n =10,736; PDI=2.43	31.3
392	74	1	211	105	4.09	0.3	M _p =67,066; M _w =64,176; M _n =32,073; PDI=2.00	45.5
393	45	2	211	105	3.76	0.3	M _p =22,227; M _w =22,623; M _n =10,036; PDI=2.25	28.6
394	74	2	211	105	3.36	0.3	Bimodal: M _p =56,152; M _w =49,560; M _n =18,664; PDI=2.66	48.4

Table 54

Ethylene/EGPEA Copolymerizations: Variation of Catalyst Structure, Pressure and Temperature (18 h, 1 mL EGPEA, 9 mL *p*-Xylene, 0.0019 mmol Cmpd, 211 equiv B(C₆F₅)₃, 105 equiv NaBAF)

Ex.	Cmpd	Press MPa	Temp °C	Yield g	Acrylate incorp mol%	M.W.	Total Me
395	85	3.5	80	0.016	trace	Nd	
396	86	3.5	80	0.437	0.8 0.6 IC 0.2 EG	M _p =916; M _w =1,670; M _n =739; PDI=2.26	39.9
397	87	3.5	80	0.429	2.1	M _p =26,655; M _w =28,284; M _n =13,707; PDI=2.06	31.1
398	88	3.5	80	0.203	2.2	M _p =2,832; M _w =3,358; M _n =1,754; PDI=1.92	44.4
399	89	3.5	80	0	—	—	—
400	85	6.9	120	0.318	0.7	M _p =327; M _w =1,150; M _n =305; PDI=3.77	57.7
401	86	6.9	120	1.49	0.6, 0.4 IC, 0.2 EG	M _p =488; M _w =864; M _n =364; PDI=2.37	82.1
402	87	6.9	120	3.14	0.5	M _p =15,311; M _w =15,880; M _n =7,213; PDI=2.20	65.7
403	88	6.9	120	0.565	1.1	M _p =1,702; M _w =2,418; M _n =1,148; PDI=2.11	95.7
404	89	6.9	120	0	—	—	—
405	90	6.9	120	1.86	1.3	M _p =4,834; M _w =5,311; M _n =2,530; PDI=2.10	52.5
406	91	6.9	120	0.50	1.6, 1.3 IC, 0.3 EG	M _p =1,382; M _w =2,217; M _n =982; PDI=2.26	78.4
407	92	6.9	120	1.32	0.8	M _p =22,852; M _w =24,968; M _n =12,472; PDI=2.00	69.9
408	93	6.9	120	0	—	—	—
409	94	6.9	120	1.24	1.4	M _p =4,172; M _w =4,579; M _n =2,254; PDI=2.03	60.8
410	95	6.9	120	0	—	—	—
411	78	6.9	130	0.047	Nd ^b	M _p =20,248; M _w =20,678; M _n =7,869; PDI=2.63	Nd
412	64	6.9	130	0.336	0.7	M _p =31,486; M _w =32,872; M _n =14,840; PDI=2.22	108.5
413	74	6.9	130	2.87	1.0, 0.7 IC, 0.3 EG	M _p =19,881; M _w =20,567; M _n =8,185; PDI=2.51	97.0

^aPredominant alpha olefin end groups; some internal olefin end groups also present. ^bDiagnostic ¹H NMR copolymer resonances, if present, are obscured by homopolymer resonances.

Table 55

Ethylene/EGPEA Copolymerizations: Variation of Catalyst Structure, Cocatalyst Concentration, and Borate Counterion and Structure (0.0019 mmol Cmpd, 18 h, 2 mL EGPEA, 8 mL *p*-Xylene, 100°C, 6.9 MPa E)

Ex.	Cmpd	B(C ₆ F ₅) ₃ equiv	Borate 105 equiv	Yield G	Acrylate Incorp mol%	M.W.	Total Me
414	74	211	NaBAF	0.746	3.4 ^a	M _p =28,528; M _w =29,829; M _n =11,409; PDI=2.61	32.1
415	74	211	LiBArF	0.647	1.9	M _p =39,148; M _w =36,313; M _n =14,745; PDI=2.46	41.3
416	74	421	NaBAF	0.217	1.3	M _p =26,280; M _w =27,880; M _n =13,106; PDI=2.13	36.9
417	74	421	LiBArF	0.358	1.2	M _p =33,089; M _w =33,479; M _n =15,943; PDI=1.57	44.6
418	76	421	LiBArF	0.738	1.2	M _p =29,924; M _w =29,685; M _n =12,971; PDI=2.29	36.1
419	92	421	LiBArF	0.385	1.1	M _p =34,623; M _w =35,775; M _n =18,240; PDI=1.96	33.4
420	64	421	LiBArF	0.009	0.7	M _n (¹ H): No olefins	58.8
421	93	421	LiBArF	0.021	1.5	M _n (¹ H): No olefins	33.2
422	96	421	LiBArF	0.109	Nd	Nd	Nd
423	90	421	LiBArF	0.982	2.5	M _p =7,599; M _w =8,271; M _n =3,746; PDI=2.21	26.3
424	74	211	LiBArF	0.86	1.6	M _p =26,306; M _w =28,886; M _n =10,439; PDI=2.77	37.6
425	74	105	LiBArF	1.23	2.2	M _p =16,233; M _w =21,189; M _n =8,573; PDI=2.47	38.5
426	74	53	LiBArF	4.75	0	M _p =76,091; M _w =76,631; M _n =24,522; PDI=3.13	Nd

^aThere is overlap of copolymer and homopolymer resonances in the ¹H NMR spectrum due to the relatively large amount of homopolymer formed. Therefore, the percent acrylate incorporation in the copolymer is an approximation.

Table 56

Ethylene/EGPEA Copolymerizations: Variation of Catalyst
Structure and Concentration (18 h, 1 mL EGPEA, 9 mL p-
Xylene, 80°C, 6.9 MPa E)

Ex.	Cmpd mmol	B(C ₆ F ₅) ₃ equiv	LiB(C ₆ F ₅) ₄ equiv	MeAl(BHT) ₂ equiv	Yield g	Acrylate Incorp mol%	M.W.	Total Me
427	59 0.01	40	20	0	6.73	1.6 0.9 IC 0.7 EG	M _p =21,259; M _w =21,724; M _n =10,233; PDI=2.12	15.3
428	59 0.0019	211	105	20	0.739	1.1	M _p =19,634; M _w =20,285; M _n =8,383; PDI=2.42	10.9
429	94 0.01	40	20	0	3.87	1.3 0.9 IC 0.4 EG	M _p =11,047; M _w =11,998; M _n =4,529; PDI=2.65	24.5
430	94 0.0019	211	105	20	1.22	0.7	M _p =9,998; M _w =12,341; M _n =4,993; PDI=2.47	17.1
431	53 0.01	40	20	0	2.26	1.0 0.9 IC 0.1 EG	M _p =1,562; M _w =2,097; M _n =818; PDI=2.56	31.8

5


Table 57

Ethylene/Acrylate Copolymerizations: Variation of Catalyst Structure, Acrylate Structure and Temperature (0.004 mmol Cmpd, 18 h, 100 equiv B(C₆F₅)₃, 50 equiv LiB(C₆F₅)₄, 9 mL *p*-Xylene, 6.9 MPa E)


Ex.	Cmpd	Temp. °C	Acrylate 1 mL	Yield G	Acrylate Incorp mol%	M.W.	Total Me
432	45	80	EGPEA	0.070	0.6 0.5 IC 0.1 EG	M _p =24,391; M _w =28,348; M _n =11,007; PDI=2.58	8.5
433	45	80	HA	0.294	1.0	M _p =45,116; M _w =71,337; M _n =14,837; PDI=4.81	14.2
434	94	80	EGPEA	0.074	0.5	M _p =9,723; M _w =13,173; M _n =6,276; PDI=2.10	8.0
435	94	80	HA	0.362	0.8	M _p =14,965; M _w =15,692; M _n =6,605; PDI=2.38	12.4
436	90	80	HA	0.286	0.8	M _p =17,982; M _w =17,990; M _n =6,559; PDI=2.74	9.7
437	45	40	EGPEA	0	—	—	—
438	91	40	EGPEA	0	—	—	—
439	94	40	EGPEA	0	—	—	—

Examples 440-555

In these Examples sometimes alkylaluminum compounds are used as cocatalysts. These alkylaluminums were purchased from commercial sources, PMAO-IP (97) (polymethylaluminumoxane from Akzo-Nobel, Inc., 12.7 wt % aluminum in toluene, (0.88 g/ml at 30°C)) or synthesized by literature methods, (AlMe₂(Et₂O)₂)(MeB(C₆F₅)₃) (98) (WO0011006), AlMe(2,6-*t*-Bu-4-Me(OC₆H₂))₂ (99) (A. P. Shreve, et al., Organometallics, vol. 7, p. 409 (1988)), and (Al-*i*-Bu₂(OC₆F₅))₂ (100) (D. G. Hender-shot, et al., Organometallics, vol. 10 p. 1917 (1991)).



99



100

The transition metal complexes (101-117) are either isolated compounds or *in situ* generated from a combination of compounds. Such combinations are shown under the compound designation (number). Syntheses of compounds other than α -diimines or their complexes are described in the following references:

45-97, 101, 102, 103, 104, 105, 109, 110, 116 and 117, are α -diimines and/or Ni complexes the same as or similar to those described in US6034259 and references therein, and US6103658, and these α -diimines and/or Ni complexes are made by methods similar to those described therein. The synthesis of the ligand for 79 is reported in Y. Yamamoto et al., J. Organometal. Chem., vol. 489, p. 21-29 (1995), and K. Sugano, et al., Chem. Lett., vol. 1991 p. 921-924.

The synthesis of the α -diimine for 110 is described in US6103658.


Methods for making 115 are found in US6174975.

Synthesis of 108 is found in previously incorporated U.S. Patent Application _____ (filed concurrently on 31 May 2001, Applicant's reference CL1655 US NA).

Syntheses of 106 and 107 are found herein.

All of the immediately documents are hereby included by reference.

Metal complexes or ingredients for *in situ* preparations are shown below:



5 General Polymerization Procedure for Examples 440-555.

In a drybox, a glass insert was loaded with a combination of ligand and metal precursor or an isolated metal precatalyst and 2 mL of solvent. The solution was cooled to -30°C and a solid portion of aluminum cocatalyst (such as 98, 99 or 100) or solution of PMAO-IP (97) was added followed by 4 mL of

10

solvent and the solution was cooled to -30°C . This cooling was done to prevent any polymerization catalyst decomposition prior to contact with the monomers, in case the catalyst was thermally unstable. A solution was made with salt (see below), comonomer and 3 mL of solvent. The solution was added to the glass insert and then cooled to -30°C . The insert was capped and placed into double ziplock bags. Outside the drybox the rack was transferred to a pressure tube and flushed with ethylene. The pressure tube was pressurized with ethylene and heated to the desired temperature and mechanically shaken for the duration of time listed in the table. The reaction solution was quenched with 30 mL of methanol or acidic methanol (10:90 HCl methanol solution) and the polymer was isolated by filtration, rinsed with additional methanol and dried under vacuum.

Polymerization results are presented in Tables 58-64. A short description/explanation for each table is given below. "Salt" in these tables indicates the addition of NaBAF or $\text{LiB}(\text{C}_6\text{F}_5)_4$ to the polymerization solution and it appeared to inhibit or prevent acrylate homopolymerization, and will be shown as simply Na or Li in the table.

Table 58: Table 58 contains examples with Ni catalysts, diimine with $\text{Ni}(\text{acac})_2$, and alkylaluminum cocatalysts for EGPEA and ethylene copolymerization. At these high ratios of Ni to salt and Al cocatalysts we had some significant acrylate homopolymerization. The acrylate homopolymer was found in two forms, a powder which was a mixture of copolymer with some acrylate homopolymer as identified by ^1H NMR, and a gelatin consisting of acrylate homopolymer which was physically separated and not included in the polymer weight in the tables. The solution volume was approximately 10 mL in each case, therefore, the solvent added was 10 mL minus the volume added for the liquid comonomer.

Table 59: Table 59 shows examples of some of the better catalysts under conditions with low concentration of Ni and high concentration of salt and Al cocatalysts. In these examples consistently good yields of EGPEA/ethylene copolymer were obtained. Further characterization of these polymers is indicated by Mw from GPC as well as incorporation of acrylate (mole %) in the copolymer that was calculated from ^1H NMR spectra of the polymer.

Table 60: This table has very low Ni concentrations and more acrylate homopolymer and low yields of polymer are obtained overall.

Table 61: Different combinations of Ni compounds and cocatalysts are used.

Table 62: Examples for E-10-U copolymerizations with ethylene.

Table 63: Hexyl acrylate copolymerization with Ni catalyst.

Table 64: Other catalysts for EGPEA copolymerization.

Table 58

Ethylene and EGPA copolymerization (18 h, 6.9 MPa E, 0.02
mmol Ni)

Ex.	Catalyst mmol	Salt (eq)	Al (eq)	EGPEA	solvent	Temp	Yield (g)
440	104	Li (5)	100 (50)	1 mL	1,2,4-TCB	120 °C	1.439
441	104	Li (5)	100 (50)	2 mL	1,2,4-TCB	120 °C	1.033
442	104	Na (5)	97 (200)	2 mL	1,2,4-TCB	120 °C	6.011
443	104	Li (5)	100 (50)	2 mL	p-xylene	120 °C	2.982
444	104	Li (5)	99 (50)	1 mL	1,2,4-TCB	120 °C	6.522
445	103	Li (5)	100 (50)	1 mL	p-xylene	100 °C	1.287
446	103	Na (5)	97 (200)	1 mL	p-xylene	100 °C	5.077
447	104	Li (5)	100 (50)	1 mL	p-xylene	100 °C	9.073
448	104	Na (5)	97 (200)	1 mL	p-xylene	100 °C	3.96
449	104	Na (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	2.179
450	103	Li (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	3.053
451	103	Li (5)	97 (200)	1 mL	1,2,4-TCB	100 °C	5.977
452	104	Li (5)	97 (200)	1 mL	1,2,4-TCB	100 °C	6.114
453	105	Li (5)	97 (200)	1 mL	1,2,4-TCB	100 °C	1.109
454	105	Li (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	3.392
455	116	Na (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	1.931
456	103	Na (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	1.269
457	103	Na (5)	97 (200)	1 mL	1,2,4-TCB	100 °C	5.066
458	105	Na (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	4.628
459	104	Na (10)	100 (50)	1 mL	1,2,4-TCB	100 °C	0.387
460	104	Na (5)	97 (200)	1 mL	1,2,4-TCB	100 °C	6.538
461	104	Li (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	1.131
462	104	Li (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	4.477
463	104	no salt	100 (50)	1 mL	1,2,4-TCB	100 °C	1.198
464	104	Na (1)	100 (50)	1 mL	1,2,4-TCB	120 °C	0.50
465	104	Na (1)	100 (50)	1 mL	1,2,4-TCB	120 °C	0.260
466	104	Na (1)	97 (200)	1 mL	1,2,4-TCB	120 °C	5.411
467	104	Na (5)	100 (50)	1 mL	1,2,4-TCB	120 °C	0.176
468	104	Na (1)	100 (50)	1 mL	1,2,4-TCB	100 °C	0.254
469	104	Na (1)	97 (200)	1 mL	1,2,4-TCB	100 °C	4.231
470	104	Na (5)	100 (50)	1 mL	1,2,4-TCB	100 °C	1.460

Table 59
Ethylene and EGPEA Copolymerization (6.9 MPa E, p-xylene solvent)

Ex.	Catalyst	mmol Ni	Salt eq	Al eq	mL acrylate	Hrs	Temp	Yield	kg/g Ni	Mw	Mol% Ac
471	101	0.002	Li (250)	98 (250)	1.0	18	120	4.766	41	19051	0.36
472	101	0.002	Li (250)	98 (250)	1.5	18	120	3.170	27	16830	0.64
473	106	0.002	Li (250)	98 (250)	1.0	18	120	8.332	71	5539	0.17/0.19 ^a
474	101	0.001	Li (750)	98 (500)	1.0	18	120	2.576	44	16000	0.57
475	101	0.004	Li (125)	98 (125)	1.0	18	100	7.24	31	27476	0.70
476	101	0.002	Li (250)	98 (250)	1.0	18	100	4.749	40	25432	0.42
477	101	0.002	Li (250)	98 (250)	1.5	18	100	3.213	27	22992	0.61
478	106	0.002	Li (250)	98 (250)	1.0	18	100	4.398	37	7262	0.19/0.16 ^a
479	101	0.001	Li (750)	98 (500)	1.0	18	100	3.374	57	24042	0.30
480	101	0.004	Li (125)	98 (125)	1.0	64	120	15.08	64	17153	0.29
481	101	0.002	Li (250)	98 (250)	1.0	64	120	10.521	90	16817	0.47
482	101	0.002	Li (250)	98 (250)	1.5	64	120	9.455	80	17930	0.8
483	106	0.002	Li (250)	98 (250)	1.0	64	120	7.833	67	5469	0.20/0.18 ^a
484	107	0.002	Li (250)	98 (500)	1.0	64	120	1.191	10	2045	ND
485	101	0.004	Li (125)	98 (125)	1.0	64	100	13.073	56	26512	0.41
486	101	0.002	Li (250)	98 (250)	1.0	64	100	8.807	75	25472	1.2
487	101	0.002	Li (250)	98 (250)	1.5	64	100	6.183	53	23585	0.84
488	106	0.002	Li (250)	98 (250)	1.0	64	100	7.100	60	6803	0.15/0.13 ^a
489	107	0.002	Li (250)	98 (500)	1.0	64	100	0.834	7	3135	ND
490	102	0.004	Li (125)	100 (250)	1.0	18	120	7.259	31	13945	0.25
491	102	0.004	Li (125)	98 (125)	1.0	18	120	9.147	39	14056	0.35
492	102	0.004	Li (125)	98 (125)	2.0	18	120	3.23	14	11652	0.94
493	101	0.004	Li (125)	100 (250)	1.0	18	120	6.165	26	13988	0.33
494	101	0.004	Li (125)	98 (125)	1.0	18	120	9.355	40	15724	0.49
495	102	0.02	Li (10)	100 (25)	1.0	18	120	6.58	6	N/A	0.55
496	102	0.02	Li (10)	98 (25)	1.0	18	120	18.921	16	N/A	0.34
497	106	0.004	Li (25)	98 (50)	1.0	18	100	4.190	18	N/A	0.22/0.29 ^a
498	108	0.004	Li (25)	98 (50)	1.0	18	100	0.123	0.5	N/A	ND
499	107	0.004	Li (25)	98 (50)	1.0	18	100	2.114	9	N/A	0.38/0.37 ^a
500	101	0.004	Li (25)	98 (50)	1.0	18	100	2.750	12	N/A	0.42
501	102	0.004	Li (25)	98 (50)	1.0	18	100	1.547	7	10621	0.48

Footnotes for Table 59:

N/A indicates that a sample was not submitted for ¹H NMR or GPC. ND (not determined) indicates that the formation of excess acrylate homopolymer overlaps the region for determining copolymer content. For the incorporation of acrylate in the ethylene copolymer (Mol% Ac) the in chain (i) and end of chain (e) position is indicated.

5

Table 60

Ethylene and acrylate Copolymerization (18 h, 120°C, 6.9 MPa E, p-xylene solvent, Al compound

98)

Ex.	Catalyst	mmol Ni	Salt eq	Al eq	mL acrylate	Yield	Kg/g Ni	Mw	Mol% Ac
502	101	0.001	Li (500)	(500)	1.0 EGPEA	3.443	59	17680	copoly
503	101	0.0005	Li (1000)	(1000)	1.0 EGPEA	1.998	34	16178	copoly
504	106	0.001	Li (500)	(500)	1.0 EGPEA	1.560	27	5500	copoly
505	106	0.0005	Li (1000)	(1000)	1.0 EGPEA	1.08	37	5550	ND
506	109	0.001	Li (500)	(500)	1.0 EGPEA	0.576	10	17704	ND
507	101	0.001	Li (500)	(500)	0.5 MA	3.024	52	15041	copoly
508	101	0.0005	Li (1000)	(1000)	0.5 MA	1.507	51	N/A	N/A
509	106	0.001	Li (500)	(500)	0.5 MA	0.225	4	N/A	N/A
510	106	0.0005	Li (1000)	(1000)	0.5 MA	0.390	13	N/A	N/A
511	109	0.001	Li (500)	(500)	0.5 MA	0.553	9	N/A	N/A
512	101	0.001	Li (500)	(500)	0.5 HA	1.08	18	N/A	N/A
513	101	0.0005	Li (1000)	(1000)	0.5 HA	0.982	33	N/A	N/A
514	106	0.001	Li (500)	(500)	0.5 HA	0.314	5	N/A	N/A
515	106	0.0005	Li (1000)	(1000)	0.5 HA	0.303	10	N/A	N/A
516	109	0.001	Li (1000)	(1000)	0.5 HA	0.672	11	N/A	N/A

N/A indicates that a sample was not submitted for ¹H NMR or GPC.

ND (not determined) indicates that the formation of excess acrylate homopolymer overlaps the region for determining copolymer content.
copoly = acrylate-ethylene copolymer detected by ¹H NMR.

10

Table 61

Ethylene and EGPEA Copolymerization (18 h, 120°C, 6.9 MPa E,
p-xylene solvent, 1.0 ml EGPEA)

Ex.	Catalyst	Mmol Ni	Salt eq	Al eq	Yield	Mw
517	104	0.004	Li (125)	98 (125)	8.451	17004
518	117	0.004	Li (125)	98 (125)	0.543	17988,26687
519	106	0.002	Li (250)	98 (250)	2.644	4787
520	115	0.01	Li (30)	99 (20) /B(C ₆ F ₅) ₃ (10)	0.307	N/A
521	110	0.01	Li (30)	99 (20) /B(C ₆ F ₅) ₃ (10)	1.417	26934
522	102	0.01	Li (30)	99 (20) /B(C ₆ F ₅) ₃ (10)	8.456	14038
523	101	0.01	Li (30)	99 (20) /B(C ₆ F ₅) ₃ (10)	8.283	13607
524	111	0.01	Li (30)	100 (50)	0.897	N/A
525	101	0.01	Li (30)	98 (25)	11.741	11838
526	101	0.01	Li (30)	99 (25)	2.647	11370
527	102	0.01	Li (30)	99 (25)	2.412	11766
528	106	0.002	Li (150)	98 (250)	1.612	4235
529	106	0.002	Li (150)	100 (500)	1.559	3812, 6321
530	106	0.002	Li (150)	99 (500)	0.450	N/A
531	107	0.002	Li (150)	98 (250)	0.929	N/A
532	107	0.002	Li (150)	100 (500)	1.595	1785
533	107	0.002	Li (150)	99 (500)	0.782	N/A
534	108	0.002	Li (150)	98 (250)	0.263	N/A
535	108	0.002	Li (150)	100 (500)	0.839	N/A
536	108	0.002	Li (150)	99 (500)	0.387	N/A

copoly = acrylate-ethylene copolymer detected by ¹H NMR, ND (not determined) indicates that the
polyacrylate region swamped out the
region of interest for the copolymer therefore it is not determined. N/A indicates that a sample for
¹H NMR or GPC was not submitted.

Table 62

Ethylene and E-10-U Copolymerization (18 h, p-xylene sol-
vent)

Ex.	Cat alyst	mmol Ni	Salt eq	Al eq	mL E-10- U	T °C	Pres. MPa	Yield	Mw
537	102	0.01	0	98 (50)	2.0	60	1.0	2.50	N/A
538	106	0.002	Li (150)	98 (250)	1.0	120	6.9	8.525	6043
539	106	0.004	Li (75)	98 (125)	1.7	120	6.9	0.531	4820
540	115	0.01	Li (30)	99 (50)	1.7	120	6.9	0.101	N/A
541	106	0.004	Li (75)	98 (125)	1.7	60	3.5	0.018	N/A
542	115	0.01	Li (30)	99 (50)	1.7	60	3.5	0.091	N/A
543	111	0.02	Na (1)	100 (50)	1.1	80	5.2	9.770	N/A
544	112	0.02	Na (1)	100 (50)	1.1	80	5.2	0.160	N/A

N/A indicates that a sample for ¹H NMR or GPC was not submitted.

Table 63

Copolymerization of ethylene and HA (18 h, 100°C, 6.9 MPa E)

Ex.	Catalyst	mmol Ni	Salt eq	Al eq	mL acrylate	solvent	Yield	Mw
545	104	0.02	Na (5)	97 (200)	1.0 HA	1,2,4TCB	4.881	4177
546	104	0.02	Na (5)	97 (200)	2.0 HA	1,2,4TCB	3.392	21281
547	104	0.02	Li (5)	99 (50)	1.0 HA	1,2,4TCB	6.443	21943
548	104	0.02	Li (5)	99 (50)	1.0 HA	p-xylene	7.655	29495

Table 64

5 Copolymerization of Ethylene and EGPEA (18 h, 120°C, 6.9 MPa E, 0.01 mmol Ni)

Ex.	Catalyst	Salt eq	Al eq	mL acrylate	solvent	Yield	Mw
549	103	Li (50)	98 (50)	1.0	p-xylene	19.010	13399
550	116	Li (50)	98 (50)	1.0	p-xylene	16.671	15559
551	102	Li (50)	98 (50)	1.0	p-xylene	11.724	12804
552	102	Na (50)	97 (100)	1.0	1,2,4-TCB	5.848	26061
553	102	Na (50)	97 (50)	1.0	1,2,4-TCB	5.550	11620
554	103	Na (50)	97 (100)	1.0	1,2,4-TCB	10.108	12359
555	103	Na (50)	97 (50)	1.0	1,2,4-TCB	9.116	14836

Examples 556-651


10 Various isocyanates were used with a single precursor, di-t-butylphosphinomethyl lithium to prepare variously substituted ligands (see below). Nickel complexes were then prepared *in situ*, and polymerizations carried out.

15 All reactions were performed under an atmosphere of nitrogen. The isocyanates for the catalyst preparation were obtained from commercial sources, and were purified by distillation, sublimation, or recrystallization; the compounds were stored under nitrogen before use. TCB was purchased anhydrous and used as is. Additional solvents were distilled from drying agents under nitrogen using standard procedures: chlorobenzene from P₂O₅; and THF, from sodium benzo-
20 phenone ketyl, Ni(II) allyl chloride and NaBAF were prepared according to the literature.

Ninety-five isocyanates were prepared as THF solutions (0.0500 M) and are listed in Table 65. These solutions were

prepared in glass vials capped with Teflon[®] lined silicone septa to maintain an inert atmosphere and prevent evaporation.

Preparation of catalyst solutions was performed according to equation 1.



In a typical procedure, each sample was prepared by adding sequentially 150(±3) μ L of an isocyanate solution (0.0500 M in THF) followed by 150(±3) μ L of a solution of (t-Bu)₂PCH₂Li (0.0500 M in THF), followed by 150(±3) μ L of a solution of (NiCl(η^3 -C₃H₅))₂ (0.0250 M in THF) to a septa sealed 2 mL glass vial. The solvent was then removed from each vial by purging with a nitrogen gas stream and each vial was then dried for 2 h in a vacuum chamber. A solution of cocatalyst (B(C₆F₅)₃, B(C₆H₅)₃ or NaBAF) 300 μ L (0.1250 M in chlorobenzene or TCB) was added into each vial. Each vial was placed in a high-pressure reactor. The reactor was pressurized to the desired pressure (typically 6.9 MPa or 1.0 MPa) with ethylene and kept at that pressure for 18 h. At the end of the run, the solvent was removed from each vial under vacuum. After this operation each vial was weighed to obtain a polymer yield. To rapidly determine the presence of copolymer, a sample was taken out of each vial and placed in an NMR tube, CDCl₃ was added and the solution was analyzed submitted by ¹H NMR spectroscopy. In some (usually promising) cases, samples were dissolved in TCE and submitted for high temperature ¹³C NMR spectroscopy.

Condition 1

Run at room temperature and 6.9 MPa of ethylene. Five equivalents of tris(pentafluorophenyl)borane were present as a cocatalyst. Eighteen hours was chosen as the run time to allow for comparison of the lowest and highest yielding catalysts. Results are presented in Table 65. The experimental procedure was repeated several times and despite some changes in yields, activity trends remained the same.

Condition 2

This was the same as Condition 1, except the ethylene pressure was 1.0 MPa. Results are shown in Table 65.

Condition 3

This was the same as Condition 1, except 5 equivalents of triphenylborane was used as a cocatalyst and the polymerization was run at 1.0 MPa ethylene pressure. This condition was repeated several times with similar results each time. Results are shown in Table 65.

Condition 4

This was run under the same conditions as Condition 1 except, one equivalent of NaBAF was added (150 μ l of a 0.05M solution in THF) after the addition of nickel allyl chloride.

Condition 5

Run at room temperature and under 6.9 MPa of ethylene. Five equivalents of tri(pentafluorophenyl)borane were used. The cocatalyst, instead of being dissolved in pure TCB was dissolved in a 1:5 (v:v) mixture of EGPEA and TCB. Because EGPEA has a high boiling point, vials were weighed out immediately after the polymerization reaction without drying. Relative yields were obtained by difference of the weights of the "wet" vials and the pre-tared vials. Results are presented in Table 65. This condition was repeated several

times and despite some changes in yields, activity trends remain the same.

Condition 6

5 This was the same as Condition 5 except the polymerization was run at 100°C. Results are presented in Table 65. This condition was repeated several times and despite some changes in yields, activity trends remain the same.

Condition 7

10 This was run in the same manner as Condition 6 except 1 equivalent of NaBAF added (150 µl of a 0.05M solution in THF) was also added after the nickel allyl chloride was added. Results are given in Table 65. ¹³C NMR analysis indicates that the polymer in Example 582 gives a copolymer with 1.04 mol% incorporation under this condition.

15 Condition 8

This condition was the same as Condition 7, except the EGPEA contained 250 ppm of benzoquinone as a free radical polymerization inhibitor. Results are given in Table 65. ¹³C NMR analysis indicates that the polymers produced in Ex-
20 amples 583 and 591 gave copolymers with trace incorporation of EGPEA, the polymer of Example 585 had 0.17 mol% incorporation of EGPEA, the polymer of Example 632 had 0.51 mol% incorporation of EGPEA, and the polymer of Example 640 had 0.90 mol% incorporation of EGPEA, all under this condition.

25

Table 65

Ex.	NAME	CONDITION							
		1	2	3	4	5	6	7	8
556	TRANS-2-PHENYLCYCLOPROPYL ISOCYANATE	1.2262	0.3589	0.0875	0.1950	0.4978	0.4518	0.249	0.3437
557	PHENYL ISOCYANATE	0.6409	0.1067	0.046	0.0982	0.4686	0.6287	0.3906	0.3762
558	2-BROMOPHENYL ISOCYANATE	0.5133	0.1321	0.0485	0.0994	0.4733	0.7043	0.3068	0.3811
559	2-FLUOROPHENYL ISOCYANATE	0.3426	0.1074	0.0703	0.1568	0.437	0.5479	0.4299	0.4407
560	2,4-DIFLUOROPHENYL ISOCYANATE	0.5988	0.1008	0.0615	0.1875	0.4797	0.7257	0.448	0.4373
561	2,6-DIFLUOROPHENYL ISOCYANATE	0.3429	0.1111	0.0392	0.0974	0.4859	0.6638	0.4485	0.4626
562	2-CHLOROPHENYL ISOCYANATE	0.4882	0.1215	0.0462	0.1257	0.5097	0.6995	0.4705	0.4645
563	2,3-DICHLOROPHENYL ISOCYANATE	0.4516	0.1075	0.0434	0.1196	0.413	0.7917	0.4686	0.4702
564	2,6-DICHLOROPHENYL ISOCYANATE	0.4058	0.1061	0.0506	0.1088	0.4688	0.7486	0.4394	0.3883
565	2-METHOXYPHENYL ISOCYANATE	1.0975	0.113	0.0584	0.1183	0.4762	0.5993	0.5925	0.4257
566	2,4-DIMETHOXYPHENYL ISOCYANATE	1.0943	0.1198	0.0415	0.1243	0.5168	0.6874	0.561	0.3869
567	2-ETHOXYPHENYL ISOCYANATE	1.1473	0.1133	0.044	0.1469	0.4535	0.7136	0.4882	0.4019
568	2-(TRIFLUOROMETHYL)PHENYL ISOCYANATE	0.4246	0.1013	0.0424	0.2715	0.5181	0.7255	0.4381	0.4564
569	O-TOLYL ISOCYANATE	0.6267	0.1229	0.0862	0.1757	0.4151	0.7253	0.5005	0.4611
570	2,6-DIMETHYLPHENYL ISOCYANATE	0.5454	0.1198	0.0603	0.1429	0.4016	0.6963	0.4101	0.3991
571	2-ETHYLPHENYL ISOCYANATE	0.6052	0.1166	0.0781	0.1382	0.4254	0.6031	0.4255	0.4705
572	3-BROMOPHENYL ISOCYANATE	0.587	0.1001	0.0761	0.1376	0.4664	0.6937	0.3257	0.4718
573	3,4-DICHLOROPHENYL ISOCYANATE	0.813	0.0945	0.0536	0.1796	0.4698	0.7749	0.5005	0.5852
574	4-BROMOPHENYL ISOCYANATE	0.6361	0.1074	0.0577	0.1428	0.4594	0.7041	0.5411	0.4898
575	4-FLUOROPHENYL ISOCYANATE	0.8563	0.1152	0.0986	0.1222	0.4424	0.6754	0.5557	0.3903
576	4-CHLOROPHENYL ISOCYANATE	0.7498	0.1242	0.0641	0.1239	0.4887	0.3319	0.4404	0.4185
577	4-METHOXYPHENYL ISOCYANATE	0.5989	0.1302	0.0778	0.1245	0.4746	0.7178	0.6034	0.5034
578	4-(TRIFLUOROMETHYL)PHENYL ISOCYANATE	0.651	0.0773	0.0539	0.1410	0.469	0.7685	0.4609	0.4037
579	P-TOLYL ISOCYANATE	0.7736	0.1045	0.0744	0.1335	0.4849	0.6127	0.2255	0.5482

Table 65 (cont'd)

Ex.	NAME	CONDITION							
		1	2	3	4	5	6	7	8
580	TERT-BUTYL ISOCYANATE	1.0498	0.0808	0.1742	0.3829	0.422	1.3345	0.6914	0.6516
581	(S)-(-)-1-PHENYLETHYL ISOCYANATE	0.873	0.1171	0.0923	0.1276	0.4037	0.8667	0.6858	0.6728
582	ISOPROPYL ISOCYANATE	0.2012	0.0777	0.0107	0.1421	0.2749	0.6658	0.394	0.5266
583	ETHYL ISOCYANATE	1.3347	0.1538	0.0805	0.1814	0.4434	1.2218	0.5436	0.6256
584	ALLYL ISOCYANATE	0.9033	0.1644	0.0976	0.1347	0.6952	1.0612	0.4884	0.6627
585	N-BUTYL ISOCYANATE	1.1664	0.1843	0.0637	0.1220	0.4643	1.8471	0.4761	0.6228
586	CYCLOHEXYL ISOCYANATE	0.8991	0.0932	0.1353	0.2726	0.488	1.791	0.6514	0.6029
587	1-NAPHTHYL ISOCYANATE	0.7214	0.0943	0.1161	0.1352	0.4344	0.7355	0.3902	0.4148
588	2,6-DIISOPROPYLPHENYL ISOCYANATE	0.4853	0.1204	0.0914	0.1423	0.3988	0.6511	0.329	0.077
589	BENZYL ISOCYANATE	1.1479	0.1492	0.1403	0.2398	0.5289	0.7776	0.5322	0.62
590	3,5-BIS(TRIFLUOROMETHYL)PHENYL ISOCYANATE	0.7095	0.1125	0.1214	0.1271	0.4763	0.8135	0.4492	0.4084
591	2,5-DIFLUOROPHENYL ISOCYANATE	0.4158	0.1146	0.0131	0.1836	0.4606	0.4177	0.3512	0.4228
592	2,4,5-TRICHLOROPHENYL ISOCYANATE	0.3766	0.1572	0.0236	0.2077	0.4821	0.8006	0.4808	0.5625
593	2,4,6-TRICHLOROPHENYL ISOCYANATE	0.5539	0.1011	0.0304	0.1775	0.4748	0.7127	0.4425	0.4596
594	2-ISOPROPYLPHENYL ISOCYANATE	0.6127	0.1362	0.0693	0.1165	0.4707	0.6892	0.4572	0.4482
595	2,3-DIMETHYLPHENYL ISOCYANATE	0.8057	0.1345	0.0872	0.1027	0.4844	0.7251	0.4875	0.4715
596	4-METHOXY-2-METHYLPHENYL ISOCYANATE	0.6799	0.1668	0.0762	0.1207	0.4756	0.7112	0.3862	0.6706
597	5-CHLORO-2,4-DIMETHOXYPHENYL ISOCYANATE	0.7214	0.1385	0.0716	0.1091	0.4337	0.7176	0.4579	0.6935
598	3,5-DICHLOROPHENYL ISOCYANATE	0.6804	0.106	0.0931	0.1802	0.4473	0.7304	0.4414	0.6873
599	5-CHLORO-2-METHOXYPHENYL ISOCYANATE	0.5286	0.113	0.057	0.1062	0.4621	0.7468	0.4694	0.4146
600	3,4,5-TRIMETHOXYPHENYL ISOCYANATE	0.636	0.1275	0.0592	0.1148	0.4942	0.7509	0.523	0.7049
601	3,5-DIMETHOXYPHENYL ISOCYANATE	0.6032	0.1015	0.0839	0.1171	0.4479	0.7324	0.5068	0.6608
602	3-(METHYLTHIO)PHENYL ISOCYANATE	0.7208	0.0708	0.0715	0.0954	0.4626	0.7488	0.4867	0.3239
603	3,5-DIMETHYLPHENYL ISOCYANATE	0.7576	0.1096	0.088	0.1073	0.4382	0.6381	0.4942	0.5342
604	2-METHOXY-5-METHYLPHENYL ISOCYANATE	0.721	0.0987	0.0217	0.1216	0.4154	0.6463	0.4118	0.3875
605	4-IODOPHENYL ISOCYANATE	0.5297	0.0883	0.0413	0.0881	0.4478	0.6757	0.1696	0.4612
606	4-PHENOXYPHENYL ISOCYANATE	0.5906	0.1005	0.0936	0.0609	0.4485	0.6619	0.4136	0.4024
607	4-(METHYLTHIO)PHENYL ISOCYANATE	0.4779	0.0937	0.1195	0.1086	0.4006	0.737	0.4584	0.5003

Table 65 (cont'd)

Ex.	NAME	CONDITION							
		1	2	3	4	5	6	7	8
608	4-ISOPROPYLPHENYL ISOCYANATE	0.5101	0.0769	0.0509	0.2092	0.4664	0.6183	0.407	0.4313
609	OCTYL ISOCYANATE	0.9398	0.2845	0.1001	0.1300	0.486	1.4104	0.4526	0.4872
610	2,4,6-TRIMETHYLPHENYL ISOCYANATE	0.7957	0.1156	0.067	0.1761	0.3983	0.6478	0.2829	0.2392
611	2-ISOPROPYL-6-METHYLPHENYL ISOCYANATE	0.6618	0.1211	0.0738	0.0693	0.3989	0.577	0.3896	0.186
612	2,6-DIETHYLPHENYL ISOCYANATE	0.5731	0.1098	0.0834	0.1372	0.4013	0.5009	0.4077	0.3754
613	4-(TRIFLUOROMETHOXY)PHENYL ISOCYANATE	0.3959	0.0939	0.094	0.1096	0.4692	0.7275	0.454	0.4577
614	4-(TRIFLUOROMETHYLTHIO)PHENYL ISOCYANATE	0.5944	0.1932	0.0353	0.0783	0.4089	0.7622	0.4608	0.4214
615	2-CHLORO-5-(TRIFLUOROMETHYL)PHENYL ISOCYANATE	0.7326	0.105	0.0647	0.0876	0.4005	0.7298	0.2464	0.4005
616	2-CHLORO-6-METHYLPHENYL ISOCYANATE	0.5883	0.1192	0.0613	0.1059	0.486	0.7034	0.3467	0.0977
617	2,4,5-TRIMETHYLPHENYL ISOCYANATE	0.5944	0.1185	0.0966	0.1776	0.4417	0.6765	0.6212	0.4493
618	2-TERT-BUTYL-6-METHYLPHENYL ISOCYANATE	0.8171	0.1604	0.0643	0.0848	0.4026	0.4572	0.1104	0.1466
619	3-CHLORO-2-METHOXYPHENYL ISOCYANATE	0.5302	0.1404	0.0814	0.1427	0.459	0.782	0.4478	0.4052
620	3-CHLORO-4-FLUOROPHENYL ISOCYANATE	0.4591	0.0945	0.1072	0.1099	0.4595	0.7624	0.4699	0.4507
621	4-BROMO-2,6-DIMETHYLPHENYL ISOCYANATE	0.5464	0.13	0.1132	0.1166	0.4638	0.6462	0.4518	0.4093
622	2,6-DIBROMO-4-FLUOROPHENYL ISOCYANATE	0.391	0.1774	0.0342	0.1319	0.401	0.7821	0.4095	0.4055
623	PHENETHYL ISOCYANATE	0.8483	0.2427	0.1198	0.1491	0.4586	1.256	0.4523	0.4349
624	2,4-DICHLOROBENZYL ISOCYANATE	0.8151	0.1546	0.1385	0.1366	0.5296	0.7782	0.5995	0.7227
625	2-(METHYLTHIO)PHENYL ISOCYANATE	0.5143	0.0504	0.0428	0.2408	0.4157	0.7048	0.4431	0.2206
626	2-BIPHENYL ISOCYANATE	0.5349	0.0985	0.0553	0.0910	0.4516	0.6602	0.2644	0.3317
627	3-IODOPHENYL ISOCYANATE	0.6515	0.1149	0.0254	0.1153	0.4593	0.6019	0.4004	0.4163
628	4-BIPHENYL ISOCYANATE	0.6505	0.1266	0.0859	0.1763	0.4478	0.6759	0.5337	0.6352
629	1-(4-BROMOPHENYL)ETHYL ISOCYANATE	0.6759	0.1045	0.1104	0.1413	0.3993	0.8374	0.5492	0.639
630	3-ISOCYANATOPROPYLTRIETHOXSILANE	0.781	0.1447	0.0601	0.1449	0.4447	0.7711	0.68	0.63
631	2,6-DICHLOROPYRID-4-YLISOCYANATE	0.3357	0.0929	0.0374	0.2234	0.464	0.4699	0.4956	0.4817

Table 65 (cont'd)

	NAME	CONDITION							
		1	2	3	4	5	6	7	8
632	2-BROMO-4,6-DIFLUOROPHENYL ISOCYANATE	0.3853	0.3034	0.0332	0.1377	0.4981	0.7634	0.3552	0.4703
633	(R)-(+)-1-PHENYLETHYL ISOCYANATE	1.1374	0.0968	0.1314	0.1229	0.3998	0.7987	0.6867	0.6773
634	1-(1-NAPHTHYL)ETHYL ISOCYANATE	0.6728	0.096	0.1357	0.0961	0.3994	0.776	0.6416	0.6752
635	3,4-DIFLUOROPHENYL ISOCYANATE	0.5316	0.0918	0.1369	0.1027	0.3697	0.6019	0.3812	0.3829
636	3-ISOPROPENYL-ALPHA,ALPHA-DIMETHYLBENZYL ISO-CYANATE	0.8534	0.0668	0.1206	0.1723	0.3914	0.807	0.5119	0.5786
637	2-(TRIFLUOROMETHOXY)PHENYL ISOCYANATE	0.4523	0.1001	0.1084	0.1736	0.4919	0.7178	0.3949	0.3472
638	1-ADAMANTYL ISOCYANATE	1.1437	0.1182	0.1838	0.3750	0.5557	1.0394	0.6603	0.6336
639	1,1,3,3-TETRAMETHYLBUTYL ISOCYANATE	1.109	0.1097	0.0803	0.1382	0.387	1.0645	0.6671	0.6077
640	4-BROMO-2-FLUOROPHENYL ISOCYANATE	0.3947	0.1083	0.0481	0.1094	0.4643	0.763	0.4426	0.5667
641	2-FLUORO-5-METHYLPHENYL ISOCYANATE	0.4424	0.1073	0.0694	0.1698	0.4776	0.7708	0.4446	0.5312
642	2,3,4-TRIFLUOROPHENYL ISOCYANATE	0.9257	0.163	0.0954	0.1493	0.4571	0.7804	0.4449	0.5111
643	4-(DIMETHYLAMINO)PHENYL ISOCYANATE	0.5244	0.1365	0.0726	0.1531	0.4774	0.7787	0.6345	0.6669
644	2-(DIFLUOROMETHOXY)PHENYL ISOCYANATE	0.6934	0.1497	0.0594	0.2253	0.4678	0.7701	0.532	0.3925
645	4-(DIFLUOROMETHOXY)PHENYL ISOCYANATE	0.7621	0.1233	0.0703	0.1651	0.4521	0.7201	0.558	0.6245
646	2-CHLOROBENZYL ISOCYANATE	0.8213	0.2136	0.1897	0.1704	0.6774	1.0548	0.5373	0.7148
647	4-FLUOROBENZYL ISOCYANATE	0.9973	0.2161	0.1757	0.1925	0.5137	0.7897	0.4974	0.6074
648	4-METHOXYBENZYL ISOCYANATE	0.7301	0.2021	0.1636	0.2216	0.4744	0.8084	0.5537	0.719
649	4-FLUORO-2-(TRIFLUOROMETHYL)PHENYL ISOCYANATE	0.4066	0.0944	0.0717	0.1451	0.5543	0.7581	0.1094	0.5099
650	2,6-DIBROMO-4-ISOPROPYLPHENYL ISOCYANATE	0.3894	0.125	0.0461	0.1033	0.4346	0.7307	0.1975	0.4574
651	3-PYRIDYL ISOCYANATE	0.3692	0.1585	0.066	0.3655	0.491	0.6084	0.2017	0.069

Example 652

Synthesis of Catalyst Derived From t-Butyl Isocyanate

A 500-mL round-bottomed flask was charged with 536 mg (5.40 mmol) of t-butyliisocyanate dissolved in ca. 30 mL THF. Then (t-Bu)₂P-CH₂Li (898 mg, 5.40 mmol) dissolved in ca. 30 mL THF was added. The reaction was stirred for one h after which time, a solution of (Ni(C₃H₅)Cl)₂ (730 mg, 2.70 mmol) in THF (ca. 30 mL) was added and stirred for an additional one h and the solvent removed. The residue was washed with hexane and dried in vacuo to yield 1.80 g (83%) of a purple powder. ¹H-NMR (CD₂Cl₂, 23°C, 300 MHz): δ 6.0-4.0 (broad signals), 4.0-2.0 (broad signals), 1.0-0.0 (broad signals, t-Bu), ³¹P-NMR (CD₂Cl₂, 23°C, 300 MHz): δ 46.7 (s).

Examples 653-673

Toluene was purified according to R. H. Grubbs et. al., Organometallics, 1996, 15, p. 1518-1520. Methyl acrylate was sparged with nitrogen and passed through a column of activated neutral alumina in the drybox before use. In a drybox 1.77 g NaBAF, B(C₆F₅)₃ (see Table 66), methyl acrylate (see Table 66) and all but 20 mL of the toluene were combined. The total volume of the reaction mixture was 100 mL and the amount of methyl acrylate and toluene were calculated on this basis. This solution was transferred to a metal addition cylinder in the drybox, and the solution was then charged to a nitrogen-purged 450 mL jacketed autoclave. In the drybox 45 (0.0286 g) was dissolved in the remaining 20 mL of toluene and mixed for 30 minutes on a lab Vibramixer®. This solution was transferred via cannula under positive nitrogen pressure to a small metal addition cylinder attached to the autoclave. While stirring, the autoclave was charged with ethylene to 350 kPa and vented three times. The reactor and its contents were heated to the reaction temperature (Table 66) using a steam/water mixture in

the autoclave jacket. After achieving the desired operating temperature, the autoclave was pressurized with ethylene to 350 to 690 kPa below the desired operating pressure (Table 66). The catalyst addition cylinder was charged with ethylene to the desired operating pressure, and the catalyst solution was then pressure injected to begin the polymerization. Ethylene was fed to maintain a constant pressure. After 6 h, the reaction was cooled to RT. All volatiles were removed from the reaction solution using a rotary evaporator. The evaporated residue was washed with three 50-100 mL portions of methanol with decanting of the methanol into a fritted glass filter after each wash. The methanol insoluble solids were then transferred to the filter with methanol and washed on the filter with additional methanol. The solids were dried for 18 hours at 60°C in a vacuum oven. Molecular weights of the isolated polymer samples were determined by GPC. ¹³C NMR of the dried polymers was used to calculate the weight% of homopoly(methyl acrylate), the mole% MA content of the ethylene/methyl acrylate copolymer, and the amount of branching in the polymer. (See Figure 3 for ¹³C peak assignments and formulas for the mole% calculations.) Weight% calculations were done using the mole% values and the molecular weights of the components.

Table 66


Ex.	Temp (°C)	E Press. (MPa)	Methyl Ac- rylate (vol%)	B (C ₆ F ₅) ₃ (mole equiv/Ni)	Isolated Yield (g)	Wt% Homo- poly MA	Mole% MA in copolymer	Branching CH ₃ /1000 CH ₂	Mw	Mw/Mn
653	100	4.1	20.0	200	0.7	65.65	1.60	32.3	2353	1.96
654	140	6.9	5.0	100	13.5	3.26	0.68	88.1	6273	2.11
655	100	6.9	5.0	200	3.67	0.01	0.57	33.0	17478	2.02
656	140	6.9	5.0	300	24.96	2.22	0.31	86.7	6031	2.00
657	100	6.9	20.0	300	0.72	14.46	1.17	59.2	4427	1.98
658	100	6.9	20.0	100	1.94	69.63	1.89	52.9	6494	2.33
659	140	6.9	20.0	200	7.3	48.59	1.41	86.9	3896	2.53
660	140	6.9	5.0	100	13.67	5.60	0.58	94.6	5850	2.15
661	100	6.9	20.0	100	1.85	74.44	1.96	37.1	5678	2.42
662	100	4.1	5.0	100	1.16	2.14	0.92	47.3	13332	1.97
663	100	4.1	5.0	300	1.59	2.13	1.04	46.2	11085	2.07
664	120	5.5	12.5	100	6.05	22.72	1.69	56.0	5888	1.95
665	120	4.1	5.0	200	7.59	2.71	0.88	68.8	7429	2.03
666	100	5.5	5.0	200	2.74	1.53	0.76	37.3	13347	2.02
667	140	4.1	5.0	200	14.44	6.91	1.00	99.2	4192	2.36
668	140	4.1	20.0	300	4.86	54.01	3.20	97.4	2298	1.99
669	140	4.1	20.0	100	4.0	74.77	1.15	121.5	2144	2.17
670	100	4.1	5.0	100	1.47	7.61	1.24	45.2	11389	2.57
671	100	4.1	5.0	300	2.58	1.82	0.64	42.1	8923	2.25
672	100	4.1	12.5	200	0.71	13.88	1.93	43.2	4858	1.82
673	140	4.1	20.0	100	4.6	75.97	2.60	110.5	2200	3.07

Examples 674-769

All reactions were performed under a nitrogen atmosphere. The additives were obtained from commercial sources and used as received. Solvents were purchased anhydrous and distilled from P_2O_5 (chlorobenzene), sodium benzophenone ketyl (THF), CaH_2 (acetonitrile) or used as received (TCB, methanol).

The additives were prepared as solutions (0.0375 M) in THF (Ex. 674-722), acetonitrile (Ex. 723-739), methanol (Ex. 740-754) and water (Ex. 755-758). These solutions were prepared in glass vials capped with Teflon[®] lined silicone septa to maintain inert atmosphere and prevent evaporation.

The nickel compounds used are shown below.



General Polymerization Procedure: In a nitrogen flushed box, a 150 μ L or 750 μ L of additive solution (0.0375 M) was added to a septum sealed 2 mL glass vial. The septum cap was removed and the solvent was removed under a nitrogen gas stream and the sample was dried for 20 min in a vacuum chamber. Additives for Ex. 763-773 were added to separate 2 mL glass vials by weighing solid (0.0056 mmol or 0.028 mmol) directly into the vial. The vial was recapped and a solu-

tion (3 mL of THF) of catalyst A, B or C was added to the vial. Catalysts B and C may contain 0-2 equiv of LiCl and we have assumed 1 equiv for the purposes of calculating a molecular weight. The septum cap was removed and the solvent was removed under a nitrogen gas stream and the sample was dried for 20 min in a vacuum chamber. The vial was recapped with a septum cap. A 0.300 mL polymerization solution containing solvent, cocatalyst(s) and acrylate monomer, if any, was added into each vial. Each vial was placed into a high-pressure reactor and pressurized with ethylene to the desired pressure and temperature for a total of 18 h. For ethylene polymerization experiments the volatiles were removed from each vial in a heated (approx. 50°C) vacuum chamber. The weight of the vial was measured and the tare weight of the vial was subtracted to calculate the weight of polymer generated (catalyst residue is not taken into consideration). For ethylene copolymerization experiments the vial is weighed directly and the tare weight of the vial was subtracted to calculate the relative weight of polymer generated (the solvent, monomer and catalyst residue are not subtracted from this weight). The amounts of polymers produced (in g) are given in Table 67. Polymerization conditions are given below.

Condition 1: Catalyst B with 5 equiv of additive and 0.300 mL of chlorobenzene. The polymerization was conducted at 6.9 MPa of ethylene at RT for 18 h.

Condition 2: Catalyst B with 1 equiv of additive, 5 equiv of $B(C_6F_5)_3$ and 0.300 mL of chlorobenzene. The polymerization was conducted at 1.0 MPa of ethylene at RT for 18 h.

Condition 3: Catalyst B with 5 equiv of additive, 1 equiv of NaBAF and 0.300 mL of chlorobenzene solution (the chlorobenzene solution contained 2.5 volume % of diethyl

ether). The polymerization was conducted at 6.9 MPa ethylene at RT for 18 h.

5 Condition 4: Catalyst A with 1 equiv of additive, 5 equiv of $B(C_6F_5)_3$, 5 equiv of $LiB(C_6F_5)_4$ and 0.300 mL of TCB solution (the TCB solution contained 20 volume % of EGPEA). The polymerization was conducted at 6.9 MPa of ethylene at 100°C for 18 h.

10 Condition 5: Catalyst B with 1 equiv of additive, 5 equiv of $B(C_6F_5)_3$, 5 equiv of $LiB(C_6F_5)_4$ and 0.300 mL of 1,2,4-TCB solution (the 1,2,4-TCB solution contained 20 volume % of EGPEA). The polymerization was conducted at 6.9 MPa of ethylene at 100°C for 18 h.

15 Condition 6: Catalyst A with 5 equiv of additive, 5 equiv of $LiB(C_6F_5)_4$ and 0.300 mL of TCB solution (the TCB solution contained 20 volume % of EGPEA). The polymerization was conducted at 6.9 MPa of ethylene at 100°C for 18 h.

20 Condition 7: Catalyst C with 1 equiv of additive, 5 equiv of $B(C_6F_5)_3$ and 0.300 mL of chlorobenzene. The polymerization was conducted at 3.5 MPa of ethylene at RT for 18 h.

Table 67

Ex.	ADDITIVE	CONDITION	1	2	3	4	5	6	7
674	4-CHLOROPHENYLBORONIC ACID		0.090	0.568	0.123	0.635	0.707	0.428	0.125
675	ALUMINUM CHLORIDE		0.296	0.076	0.138	0.472	0.405	0.100	0.261
676	ALUMINUM ISOPROPOXIDE		0.009	0.188	1.000	0.668	0.597	0.430	0.177
677	ALUMINUM PHENOXIDE		0.020	0.706	0.482	0.614	0.694	0.412	0.175
678	ALUMINUM TRIS(2,2,6,6-TETRAMENTYL-3,5-HEPTANEDIONATE)		0.105	0.067	0.059	0.572	0.612	0.422	0.133
679	ALUMINUM TRI-SEC-BUTOXIDE		0.028	0.169	0.348	0.691	0.691	0.439	0.162
680	BORON TRIFLUORIDE TERT-BUTYL METHYL ETHERATE		0.187	0.814	0.256	0.684	0.736	0.414	0.312
681	COPPER(I) ACETATE		0.004	0.402	0.011	0.680	0.749	0.409	0.150
682	COPPER(I) BROMIDE		0.005	0.426	0.032	0.671	0.667	0.423	0.134
683	COPPER(II) ACETATE		0.009	0.296	0.013	0.685	0.681	0.429	0.073
684	COPPER(II) BROMIDE		0.005	0.174	0.012	0.602	0.456	0.390	0.123
685	COPPER(II) CHLORIDE		0.004	0.218	0.072	0.603	0.137	0.449	0.146
686	COPPER(II) TRIFLUOROMETHANESULFONATE		0.057	0.052	0.042	0.618	0.789	0.460	0.073
687	DIBUTYL TIN DICHLORIDE		0.011	0.414	0.209	0.623	0.559	0.431	0.126
688	DIBUTYL TIN DIACETATE		0.012	0.525	0.324	0.501	0.775	0.424	0.107
689	DIETHYL(3-PYRIDYL)BORANE		0.008	0.392	0.018	0.654	0.752	0.433	0.249
690	DIMETHYLBORON FLUORIDE		0.330	0.237	0.471	0.685	0.759	0.478	0.249
691	DIPHENYLZINC		0.011	0.431	0.242	0.499	0.571	0.432	0.635
692	INDIUM(III) TRIFLUOROMETHANESULFONATE		0.494	0.094	0.598	0.532	0.767	0.445	0.257
693	LITHIUM TRIFLUOROMETHANESULFONATE		0.018	0.532	0.019	0.694	0.765	0.451	0.152
694	SODIUM TETRAPHENYLBORATE		0.237	0.081	0.046	0.610	0.775	0.494	0.183
695	TIN(II) ACETATE		0.015	0.233	0.385	0.453	0.454	0.416	0.089
696	TIN(II) BROMIDE		0.104	0.461	0.410	0.548	0.430	0.423	0.112
697	TIN(II) FLUORIDE		0.001	0.568	0.028	0.648	0.734	0.439	0.179
698	TRIMETHYLBORANE		0.014	0.536	0.032	0.645	0.725	0.456	0.258
699	TRIS(4-ETHOXYPHENYL)BISMUTH		0.019	0.095	0.035	0.620	0.742	0.438	0.145

Table 67 cont'd

Ex.	ADDITIVE	CONDITION	1	2	3	4	5	6	7
700	TRIS(DIMETHYLAMINO)BORANE		0.002	0.109	0.022	0.639	0.735	0.421	0.116
701	ZINC(II) BROMIDE		0.381	0.104	0.291	0.588	0.519	0.436	0.211
702	ZINC(II) CHLORIDE		0.207	0.106	0.196	0.538	0.483	0.434	0.121
703	1-NAPHTHALENEBORONIC ACID		0.010	0.090	0.044	0.706	0.795	0.517	0.092
704	PHENYLBORONIC ACID		0.011	0.082	0.204	0.622	0.688	0.522	0.147
705	TRIPHENYLBISMUTH		0.015	0.054	0.025	0.560	0.719	0.429	0.248
706	SAMARIUM(II) IODIDE		0.030	0.100	0.028	0.504	0.411	0.438	0.156
707	SODIUM TETRAKIS(P-TOLYL)BORATE		0.064	0.327	0.024	0.703	0.839	0.470	0.142
708	AMMONIUM CERIUM(IV) NITRATE		0.019	0.094	0.026	0.609	0.425	0.440	0.123
709	2-METHOXY PHENYLBORONIC ACID		0.009	0.121	0.392	0.690	0.762	0.490	0.120
710	4-FLUOROPHENYL BORONIC ACID		0.049	0.825	0.144	0.705	0.757	0.528	0.109
711	4-METHOXYPHENYL BORONIC ACID		0.016	0.574	0.121	0.732	0.786	0.494	0.104
712	ALUMINUM ACETYLACETONATE		0.017	0.088	0.019	0.644	0.664	0.432	0.115
713	ALUMINUM HEXAFLUOROACETYLACETONATE		0.153	0.479	0.562	0.654	0.716	0.445	0.071
714	ALUMINUM TRIFLUOROMETHANESULFONATE		0.021	0.078	0.027	0.633	0.594	0.422	0.105
715	DIMETHYLANILINIUMTETRAKIS(PENTAFLUORO PHENYL)BORATE		0.210	0.852	0.548	0.638	0.713	0.403	0.308
716	LITHIUMTETRAKIS(PENTAFLUOROPHENYL) BORATE-DIETHERATE		0.064	0.967	0.037	0.667	0.736	0.461	0.138
717	YTTERBIUM (III) TRIFLUOROMETHANESULFONATE HYDRATE		0.672	0.094	0.242	0.660	0.484	0.453	0.087
718	TIN(II) ACETYLACETONATE		0.079	0.253	0.424	0.358	0.450	0.423	0.233
719	TIN (II) HEXAFLUOROACETYLACETONATE		0.231	0.260	0.608	0.429	0.417	0.431	0.372
720	P-TOLYLBORONIC ACID		0.010	0.632	0.221	0.669	0.749	0.509	0.128
721	TRIS(4-TOLYL)BISMUTH		0.016	0.191	0.028	0.689	0.736	0.428	0.143
722	TRIPHENYL ALUMINUM		0.670	0.370	0.418	0.664	0.513	0.430	1.036
723	ALUMINUM (III) PHENOXIDE		0.003	0.552	0.039	0.664	0.774	0.452	0.420
724	CERIUM(III) FLUORIDE		0.002	0.597	0.038	0.603	0.714	0.435	0.177
725	COPPER(I) BROMIDE		0.047	0.279	0.133	0.625	0.463	0.449	0.217
726	COPPER(I) CHLORIDE		0.009	0.193	0.147	0.683	0.517	0.464	0.158

Table 67 cont'd

Ex.	ADDITIVE	CONDITION	1	2	3	4	5	6	7
727	COPPER(I) IODIDE		0.118	0.642	0.030	0.655	0.684	0.453	0.136
728	COPPER(II) ACETATE		0.007	0.201	0.010	0.663	0.686	0.418	0.055
729	COPPER(II) BROMIDE		0.009	0.091	0.015	0.661	0.419	0.429	0.088
730	COPPER(II) CHLORIDE		0.005	0.185	0.012	0.741	0.435	0.419	0.111
731	COPPER(II) TRIFLUOROMETHANESULFONATE		0.018	0.061	0.022	0.739	0.833	0.459	0.065
732	SAMARIUM(III) CHLORIDE		0.003	0.437	0.140	0.699	0.727	0.432	0.143
733	TIN(II)TRIFLUOROMETHANESULFONATE		0.849	0.084	0.661	0.421	0.530	0.442	0.106
734	YTTRIUM(III) CHLORIDE		0.151	0.101	0.060	0.442	0.351	0.377	0.212
735	ZINC(II) TRIFLUOROMETHANESULFONATE		0.651	0.364	0.529	0.652	0.599	0.444	0.172
736	YTTRIUM(III) TRIFLUOROMETHANESULFONATE		0.561	0.105	0.234	0.723	0.564	0.463	0.169
737	TIN(II) OXIDE		0.002	0.656	0.028	0.699	0.766	0.450	0.145
738	TRIFLUOROMETHANESULFONIMIDE		0.014	0.299	0.019	0.714	0.760	0.438	0.107
739	CALCIUM(II) TRIFLUOROMETHANESULFONATE		0.335	0.101	0.057	0.728	0.783	0.454	0.125
740	CERIUM(III) CHLORIDE		1.028	0.091	0.491	0.635	0.418	0.167	0.202
741	COPPER(II) CHLORIDE		0.008	0.072	0.014	0.780	0.428	0.444	0.085
742	COPPER(II) TRIFLUOROMETHANESULFONATE		0.018	0.065	0.017	0.709	0.844	0.449	0.086
743	LANTHANUM(III) CHLORIDE		1.143	0.085	0.634	0.643	0.469	0.448	0.133
744	LANTHANUM(III) TRIFLUOROMETHANESULFONATE		0.420	0.124	0.332	0.613	0.726	0.417	0.116
745	MAGNESIUM(II) TRIFLUOROMETHANESULFONATE		0.342	0.125	0.499	0.644	0.744	0.458	0.129
746	SCANDIUM(III) TRIFLUOROMETHANESULFONATE		0.469	0.082	0.401	0.637	0.270	0.444	0.118
747	TIN(II) TRIFLUOROMETHANESULFONATE		0.681	0.094	0.933	0.464	0.507	0.440	0.090
748	TRIETHANOLAMINE BORATE		0.010	0.128	0.013	0.494	0.583	0.426	0.081
749	SAMARIUM(III) TRIFLUOROMETHANESULFONATE		0.717	0.095	0.599	0.727	0.685	0.455	0.124
750	SODIUM TETRAKIS(1-IMIDAZOYL)BORATE		0.012	0.746	0.019	0.476	0.432	0.437	0.120
751	YTTRIUM(III) TRIFLUOROMETHANESULFONATE		0.506	0.091	0.313	0.751	0.563	0.468	0.111
752	TRIFLUOROMETHANESULONIMIDE		0.012	0.363	0.017	0.738	0.779	0.446	0.077
753	TIN(II) ACETYLACETONATE		0.006	0.079	0.011	0.451	0.361	0.430	0.104

Table 67 cont'd

Ex.	ADDITIVE	CONDITION	1	2	3	4	5	6	7
754	LANTHANUM(III) TRISTRIFLUOROACETATE		0.882	0.130	0.428	0.489	0.720	0.427	0.200
755	SAMARIUM(III) CHLORIDE		0.015	0.267	0.270	0.421	0.418	0.438	0.138
756	TIN(II) FLUORIDE		0.018	0.581	0.350	0.616	0.755	0.440	0.169
757	YTTRIUM(III) TRIFLUOROMETHANESULFONATE		0.277	0.107	0.248	0.699	0.536	0.465	0.105
758	CALCIUM(II) TRIFLUOROMETHANESULFONATE		0.020	0.300	0.085	0.712	0.745	0.457	0.140
759	LITHIUM TETRAKIS(PENTAFLUOROPHENYL) BORATE·DIETHERATE		0.074	0.233	0.028	0.700	0.709	0.469	0.199
760	SODIUM TETRAKIS(3,5-BIS(TRIFLUOROMETHYL)PHENYL)BORATE		0.094	0.135	0.068	0.664	0.753	0.442	0.191
761	DIMETHYLANILINIUM TETRAKIS(PENTAFLUOROPHENYL)BORATE		0.220	0.167	0.431	0.662	0.758	0.433	0.114
762	[Al(Bu) ₂ (EtO)] ⁺ [B(C ₆ F ₅) ₃ R] ⁻ ^a		1.689	0.232	1.640	0.783	0.798	0.785	1.356
763	Li[Al(OC ₆ F ₅) ₄] ^b		0.747	0.049	0.121	0.646	0.617	0.429	0.238
764	AlMe ₃ ·THF ^c		0.395	0.090	0.316	0.297	0.383	0.424	0.301
765	AlMe(2,6-t-Bu-4-Me(OC ₆ H ₂)) ₂ ^{d,g,h}		0.450	0.462	0.846	0.654	0.608	0.421	0.303
766	Al-i-Bu ₂ (OC ₆ F ₅) ^e		1.132	0.247	1.385	0.720	0.799	0.299	0.630
767	NO ADDITIVE		0.011	0.502	0.032	0.686	0.755	0.412	0.249
768	TRITYL TETRAKIS(3,5-BIS(TRIFLUOROMETHYL)PHENYL)BORATE ^h		0.174	0.447	0.049	0.680	0.829	0.571	0.208
769	TRIPHENYLBORON			0.610	0.648	0.685	0.625	0.429	0.268

Footnotes for Table 67:

Additives for 762-766 and 768 were synthesized by literature methods: a) modification of preparation from WO0011006; b) Y. Sun, et al., *Organometallics*, vol. 19, p. 1625 (2000); c) V. Srinj, et al., *Organometallics*, vol. 8, p. 827 (1989); d) M. Skowronska-Ptasinska, et al., *Journal of Organometallic Chemistry*, vol. 160, p. 403 (1978); e) D. G. Hendershot, et al., *Organometallics*, vol. 10, p. 1917 (1991); f) S. R. Bahr and P. Boudjouk, *Journal of Organic Chemistry*, vol. 57, p. 5545 (1992). Substitutions for additives were made in the following experiments: g) Conditions 4 - 7 additive is Li[Al(OCPh(CF₃)₂)₄] synthesized by a literature method, T. J. Barbach, Thesis, 1998, Colorado State University; h) Conditions 5-7.

Table 68

Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃, 8mL TCB, 2mL HA, at 120°C under 6.9MPa E for 18h

Ex	Catalyst	Sm(OTf) ₃	Yield (g)	#Me/1000CH ₂	Mole% Comonomer	m.p. (°C) (ΔH _f)	Mw/PDI
770	5	1eq	1.429	28	0.6	118 (96.0)	9,859/8.8
771	21	1eq	8.184	31	1.28 (¹³ C) 0.40 IC 0.88 EG	112 (182.7)	1,628/2.4
772	39	0eq	0.216	28	0.8	111 (158.3) 97	Bimodal First 497,946/2.3 Second MP = 887

5

Table 69


Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃, 20eq LiB(C₆F₅)₄, 8mL TCB, 2mL HA, at 120°C under 6.9MPa E for 18h

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	Mole% Comonomer	m.p. (°C) (ΔH _f)	Mw/PDI
773	5	3.998	10	0.54 (¹³ C) 0.25 IC 0.29 EG	124 (209.5)	3,567/2.2
774	7	1.075	19	0.38 (¹³ C) 0.19 IC 0.19 EG	112 (191.2)	1,405/1.8
775	6	1.253	13	0.53 (¹³ C) 0.25 IC 0.28 EG	122 (190.6)	11,123/10.8
776	2	0.461	9	0.41 (¹³ C) 0.20 IC 0.21 EG	125 (186.6)	22,311/10.8
777	26	0.897	11	0.61 (¹³ C) 0.39 IC 0.22 EG	118 (172.3)	3,595/2.1

Table 70




¹³C NMR Branching Analysis for EGPEA Copolymers

Ex	Total Me	M	Et	Pr	Bu	Hex+ & EOC	Am+ & EOC	Bu+ & EOC
773	10.0	1.8	1.3	0.1	1.5	8.4	6.7	6.8
774	18.7	3.8	1.8	0.4	0.7	11.6	11.7	12.8
775	12.7	2.0	1.6	0.4	0.7	7.9	8.2	8.6
776	9.2	1.8	2.0	0.5	1.4	7.8	4.3	4.9
777	11	1.5	2.5	0.4	1.1	8.2	6.9	6.8

Example 778Synthesis of 118.

In a drybox, 0.300g 40 and 0.487g tris(3,5-bis(trifluoromethyl))borane were dissolved in 25mL toluene. This mixture was allowed to stir at RT for 1h. The mixture was filtered through Celite® and the solvent was evaporated. Brown solid (0.160g) was obtained. A single crystal was obtained by slowly evaporate the methylene chloride/heptane solution of 40. X-Ray single crystal analysis confirmed the Zwitterionic structure of this catalyst.

Table 71
Copolymerization Using 0.02mmole Catalyst, with a Total Volume of 10mL of TCB and Polar Monomer, at 80°C under 3.4 MPa of Ethylene

Ex.	Catalyst	B(C ₆ F ₅) ₃	Polar Monomer	Polar Monomer Volume (mL)	Yield (g)
779	2	40eq		2	0.010
780	118	0eq		3	0.345
781	2	40eq	CH ₂ =CH(CH ₂) ₂ C(O)CH ₃	3	0.020
782	2	40eq		3	0.556
783	2	40eq	CH ₂ =CH(CH ₂) ₇ C(CH ₂ O) ₃ CCH ₃	3	10.26 9

5


Table 72
Ethylene Polymerization Using 0.01mmole Catalyst, 20eq LiB(C₆F₅)₄, 10mL TCB, at 60°C under 3.4 MPa Ethylene for 18h

Ex	Catalyst	Yield (g)	#Me/1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI
784	2	1.842	8	126 (166.2)	35,425/2.8
785	6	1.698	5	128 (172.7)	43,111/2.2
786	5	4.377	16	123 (173.9)	17,351/3.0
787	7	9.143	70	105 (157.2)	1,636/4.3
788	30	0.281	17	123 (195.5)	12,383/9.6


10

Table 73
Ethylene/CO Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃, 10mL TCB, at 100°C under 2.8MPa Ethylene/CO (9:1 molar ratio) for 16h

Ex	Catalyst	Yield (g)
789	21	0.345
790	2	0.108
791	5	0.201
792	4	0.024
793	40	0.480



119



120

Syntheses of these compounds will be found in previously incorporated U.S. Patent application _____ (filed concurrently 31 May 2001, Applicant's reference CL1655 US NA) and U.S. Provisional Patent Application _____ (filed concurrently 31 May 2001, Applicant's reference CL1744 US PRV1) (incorporated by reference herein for all purposes as if fully set forth).

Table 74

Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃, 6mL TCB, 4mL HA, at 100°C under 6.9MPa E for 18h

Ex.	Catalyst	Yield (g)	#Me/1000CH ₂	Mole% HA in Polymer	m.p.,(°C) [ΔH _f]	Mw/PDI	TON E/HA
794	120	2.067*	24	3.9	106 [120]	7,664/2.3	3,009/121

* In addition to 2.067 g copolymer, HA homopolymer (0.567 g) was also produced.


Table 75

Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃, 6mL TCB, 4mL HA, or EGPEA at 120°C under 6.9MPa E for 18h


Ex.	Catalyst	Co-Monomer (Mole%)	Yield (g)	#Me/1000CH ₂	m.p. (°C) [ΔH _f]	Mw/PDI	TON E/Comonomer
795	120	HA (4.4)	2.543*	29	97 [86.3]	6,688/2.7	3,587/170
796	120	EGPEA (2.0)	3.182**	22	100 [88.8]	9,821/3.3	4,989/100

* Contained 2.543 g copolymer and 0.772 g homopolymer of HA


** Contained 3.182 g copolymer and 1.963 g homopolymer of EGPEA



121. R, R' = iPr, R'' = H
 122. R, R' = Me, R'' = H
 123. R, R', R'' = Me
 124. R, R'' = Me; R' = Cl
 125. R, R' = Me; R'' = Br



126



127

Table 76

E/HA Copolymerization Using 0.02mmole Catalyst, 40eq

B(C₆F₅)₃, 20eq Li B(C₆F₅)₄, 6mL TCB, 4mL HA, at 100°C under
 6.9MPa E for 18h

Ex.	Catalyst	Mole % HA in Polymer	Yield (g)	#Me/ 1000CH ₂	m.p. (°C) (ΔH _f)	Mw/PDI	TON E/Comonomer
797	121	2.3	0.356 ^a	13	122 (138.6)	4,864/2.6	477/11
798	126	0.2 ^b	0.403 ^c	3	126 (181.4)	19,918/8.0	659/6

^a Contained 0.302 g copolymer and 0.054 g homopolymer of HA

^b 1 mL HA was used rather than 4 mL

^c Contained 0.380 g copolymer and 0.023 g homopolymer of HA

Table 77

Copolymerization Using 0.02mmole Catalyst, 40eq B(C₆F₅)₃,
 20eq Li B(C₆F₅)₄, 8mL TCB, 2mL HA, at 100°C under 6.9MPa E for
 18h

Ex.	Catalyst	Yield (g) ^a	#Me/1000CH ₂	Mole % HA in Polymer	m.p. (°C) (ΔH _f)	Mw/PDI
799	121	1.750	27	0.8	124 (160.1)	10,049/3.47
800	122	1.710	26	1.2	118 (176.1)	3,422/2.42
801	123	0.834	34	1.8	120 (147.9)	3,605/1,521
802	124	0.478	52	2.2	95 (132.9)	2,392/2.37
803	125	0.804	36	1.8	119 (153.5)	3,275/2.40
804	127 ^b	4.257	8	1.1	123 (158.1)	7,725/1.97


^a All of the copolymer products contained a small amount of homopolymer of HA

^b 20 eq of NaBarF was used here rather than 20eq of LiB(C₆F₅)₄; toluene was used as solvent here rather than TCB

Examples 805-833

The reaction mixture including catalyst, solvent, acrylate and cocatalysts was assembled inside a nitrogen

filled drybox and placed in a 50mL stainless steel pressure vessel. A stir bar was added and the vessel sealed and removed from the drybox where it was pressurized with ethylene to the desired pressure. The vessel was heated and stirred
5 with a constant pressure of ethylene for the duration of the reaction.



128

Table 78


Ex.	Catalyst	mmol Ni	NaBARf eq	B(C ₆ F ₅) ₃ eq	C ₆ H ₅ Cl mL	EGPEA mL	Time h	Temp	Yield	Kg / g Ni	Mw	Mol % EGPEA
805	45	0.001659	166	767	15	1.5	66	~127 °C	15.74	161	13761	0.36 / 0.40
806	45	0.001875	150	680	15.5	MA 1.0	18	~124 °C	4.65	42		0.43
807	45	0.0015	188	850	15	2.1	63	125 °C	10.9	124		0.45 / 0.47
808	45	0.0015	188	850	15	1.5	63	117 °C	3.3	38	9948	0.7
809	76	0.0015	188	850	15	1.5	17	125 °C	2.3	26	19213	0.6
810	76	0.0015	188	850	15	1.5	17	120 °C	1.9	22	30124	low
811	128	0.0015	188	850	15	1.5	17	80 °C	4.5	51	39600	low (0.2-0.3)
812	128	0.00075	380	1700	17	2.1	18	82 °C	1.34	31		low
813	74	0.00125	225	1017	15 tol.	MA 1.0	66	120 °C	2.82	38		
814	45	0.0015	188	850	15	1.5	18	120 °C	4.65	51	12758	0.5
815	45	0.0015	188	850	15	MA 1.0	72	123 °C	7.3	83	32036	0.24 (13C)
816	128	0.0015	188	850	15	MA 1.0	72	100 °C	4.2	48	13082	0.29 (13C)
817	51	0.0015	188	850	15	1.5	18	120 °C	0.7	8	20294	0.3
818	45	0.0015	188	850 (Al+B-) ^a	15	1.5	18	120 °C	4.1	47	12133	0.3
819	45	0.0015	188	430 (Al+B-) ^a	16	1.5	18	120 °C	2.8	32	14634	0.6
820	45	0.0015	188	850	15	1.5	18	122 °C	3.5	40		
821	45	0.0015	188	850	15	MA 2	66	122 °C	8.5	97	13162	0.41 (13C)
822	45	0.0015	188	850	15	MA 3	17	123 °C	4.9	56	8305	0.88 (13C)
823	74	0.0015	188	850	15	MA 2	125	125 °C	4.1	47	23003	
824	45	0.0015	188	MAO 1 ml	15	1	18	125 °C	4.4	50	10011	Low

Table 78 (cont'd)

825	45	0.0015	188	MAO 0.3 ml	15	1.5	18	100°C	4.2	48		0.29
826	45	0.0015	188 LiB ^b	850	15	1.5	18	122°C	2.9	33		0.53
827	45	0.0015	188 LiB	MAO 0.2 ml	15	1.5	18	100°C	1	11	12507	0.52
828	45	0.0015	188 LiB	MAO 0.3 ml	15	1.5	18	100°C	1.3	15	11851	0.63
829	45	0.0015	188	MAO 0.3 ml	15	1.5	18	100°C	6.6	75	20849	0.27
830	74	0.0015	188	1300	15	MA 3	115	120°C	3.4	39	15103	0.56
831	40	0.00166	170	766	15	1.5	18	~118°C	5.94	61		0.5*
832	21	0.00166	170	766	16	1.5	18	~125°C	3.74	38		~0.5
833	40	0.0015	188	850	15	1.5	66	123°C	5.2	59		1.2*

^a Al(OEt)₂(Me)₂BMMe(C₆F₅)₃. ^bLiB = Li(B(C₆F₅)₂Et)₂O used in place of NaBARf. ^cIn chain and end-of-chain acrylate. MA = methyl acrylate; MAO = MMAO-12 (12.9 wt%Al in toluene, Akzo-Nobel); EGPEA added before borane

Examples 829-846



129

Preparation of Supports

Support A: Inside a nitrogen filled drybox, dehydrated, spray-dried spherical silica (2g, Grace XPO-2402, dehydrated to ~ 1 mmol OH / g silica) was placed in 6mL dry toluene and AlMe₃ (3 mL, 2M in hexane, Aldrich) added. The slurry was agitated by shaking for 30 min after which the solids were filtered, washed with pentane and dried under vacuum.

Support B: Inside a nitrogen filled drybox, spray-dried spherical silica-alumina (1g, Grace MS 13-1.10, dehydrated at 500°C) was placed in 6mL dry toluene and AlMe₃ (1.8 mL, 2M in hexane, Aldrich) added. The slurry was agitated by shaking for 30 min after which the solids were filtered, washed with pentane and dried under vacuum.

Preparation of Catalysts

Catalyst I: Support A (0.5g) was added to a solution of 45 (76 mg, 0.05 mmol) in anhydrous toluene. The slurry was agitated by shaking for 30 min after which the solids were filtered away from the brown filtrate and dried under vacuum.

Catalyst II: Silica supported MAO (Albemarle Corp, 18 wt% Al on spherical silica) was added to a solution of 45 (76 mg, 0.05 mmol) and B(C₆F₅)₃ (0.133g, 5eq) in anhydrous toluene. The slurry was agitated by shaking for 30 min after which the solids were filtered away from the black / brown filtrate and dried under vacuum. ICP: % Ni = 0.43 %.

Catalyst III: Support A (0.5g) was added to a solution of 45 (76 mg, 0.05 mmol) and B(C₆F₅)₃ (0.133g, 5eq) in anhydrous toluene. The slurry was agitated by shaking for 30 min after which the solids were filtered away from the green / brown filtrate and dried under vacuum. ICP: % Ni = 0.42 %.

Catalyst IV: Inside a nitrogen filled drybox, spray-dried spherical silica alumina (0.5 g, Grace MS 13-1.10, dehydrated at 500°C under flowing N₂), was placed in anhydrous toluene (8 mL) and 45 (38 mg, 0.025mmol) added. The slurry was agitated by shaking for 30 minutes after which the orange brown solids were filtered, washed with toluene and finally pentane and dried under vacuum. ICP: % Ni = 0.28 %.

Catalyst V: Inside a nitrogen filled drybox, spray-dried spherical silica alumina (0.5 g, Grace MS 13-1.10, dehydrated at 500°C under flowing N₂), was placed in anhydrous methylene chloride (8 mL) and 129 (16 mg, 0.022 mmol) added. The slurry was agitated by shaking for 45 min after which the orange solids were filtered, washed with toluene and finally pentane and dried under vacuum. ICP: % Ni = 0.24 %.

Catalyst VI: Support B (0.25g) was added to a solution of 45 (19 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 45 min after which the solids were filtered away from the dark green filtrate, washed with toluene and dried under vacuum.

Catalyst VII: Support A (0.25g) was added to a solution of 45 (19 mg, 0.013 mmol in anhydrous toluene. The slurry was agitated by shaking for 45 min after which the solids were filtered away from the light brown filtrate, washed with toluene and dried under vacuum.

Catalyst VIII: Silica supported MAO (0.25g, Al-bemarle, 18 wt% Al) was added to a toluene solution of 45 (19 mg, 0.013 mmol in 10 mL). The slurry was agitated by shaking for 30 min after which the solids were filtered away from the blue filtrate, washed with toluene and dried under vacuum. ICP; %Ni = 0.36%.

Catalyst IX: Support B (0.25g) was added to a solution of 45 (19 mg, 0.013 mmol) in anhydrous toluene. B(C₆F₅)₃ (56 mg, Boulder Scientific) was added and the slurry was agitated by shaking for 30 min after which the solids were filtered away from the brown filtrate, washed with toluene and dried under vacuum. ICP %Ni = 0.28%.

Catalyst X: Support A (0.25g) was added to a solution of 45 (19 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 60 min after which the brown solids were filtered away from the green filtrate, washed with toluene and dried under vacuum.

Catalyst XI: Support A was added to a solution of 45 (19 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 60 min after which the orange solids were filtered away from the orange filtrate, washed with toluene and dried under vacuum.

Catalyst XII: Support A (0.25g) was added to a solution of 129 (9.6 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 60 min after which the gray solids were filtered away from the purple filtrate, washed with toluene and dried under vacuum.

Catalyst XIII: Support A (0.25g) was added to a solution of 40 (5.6 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 60 min after which the orange solids were filtered away from the orange filtrate, washed with toluene and dried under vacuum.

Catalyst XIV: Support A (0.25g) was added to a solution of 21 (4.5 mg, 0.013 mmol) in anhydrous toluene. The slurry was agitated by shaking for 60 min after which the beige solids were filtered away from the filtrate, washed with toluene and dried under vacuum.

Copolymerization of ethylene with EGPEA

The solid catalyst and cocatalyst components (catalyst ~0.004 mmol, 0.177g NaBAF, and optionally $B(C_6F_5)_3$) were added to a glass insert. Solvent (anhydrous chlorobenzene, 9 mL) and EGPEA, (1mL, filtered through basic alumina, Aldrich) were added last and the insert placed in a metal pressure vessel. Some ethylene was admitted and the vessel was heated to 120°C and then pressurized to 6.9 MPa with ethylene and agitated for 18 h. After this time the reactor was cooled, the pressure released and the contents of the insert placed in stirring methanol to precipitate polymer product. The polymeric product was then filtered, washed well and dried. Results are given in Table 79.

Table 79

Ex	Catalyst (mg)	$B(C_6F_5)_3$ 98 eq	$AlMe(BHT)_2$ 20 eq	Yield (g)	% EGPEA ³ incorporated	kg PE ₁ / g Ni
829	45 (5.8 mg) ⁴	0.2 g	-	6.6	0.5	28
830	45 (5.8 mg) ⁴	0.2 g	40 mg	5.4	0.5	23
831	45 (5.8 mg) ⁴	-	40 mg	2.7	0.7 ²	11
832	VIII (77 mg)	-	-	0.6	0.4	3
833	I (40 mg)	0.2 g	-	3.4	0.5	14
834	IV (77 mg)	0.2 g	-	5.3	0.4	22
835	V (77 mg)	0.2 g	-	2.1	0.5	9
836	X (80 mg)	0.2 g	-	3.6	0.7	15
837	XI (80 mg)	-	40 mg	3.0	0.8 ²	13
838	XII (80 mg)	-	40 mg	2.1	0.9 ²	9
839	XIII (80 mg)	-	40 mg	6.9	0.5	29
840	XIV (80 mg)	-	40 mg	0.1	0.3	0.5

¹ This is calculated based on the amount of nickel added when the catalyst was prepared. As substantial amounts of color washed away from the support this value represents a minimum activity, ² Incorporation may be high due to presence of homopolymer which makes calculation of % incorporation less accurate, ³ Determined by H-NMR at 120°C in TCE-d₂. ⁴ No support.

Inside a nitrogen filled drybox the solid catalyst and cocatalyst components (2.5 mg NaBAF, and optionally $B(C_6F_5)_3$) were added to glass inserts. Solvent (anhydrous chlorobenzene, 0.25 mL) and EGPEA, (0.05 mL, filtered through basic alumina, Aldrich) were added last and the inserts placed in a metal pressure vessel. The vessel was sealed, removed from the drybox and placed under an atmosphere of ethylene at 6.9 MPa and heated to 110-120°C for 16 h. After cooling the vessel was opened and the reactions quenched with methanol, and the polymeric product filtered, washed with methanol and dried. Results are given in Table 80.

Table 80

Ex.	Catalyst (mmol)	Yield (mg)	% EGPEA ³ incorporated	End Groups Int : Term.
841	45 ¹ (0.002)	0.36	1.5	9:1
842	II (0.002)	0.13	1.3	1:1.1
843	III (0.002)	0.13	1.9	1:1.1
844	45 ¹ (0.001)	0.22	1.5	2:1
845	VI (0.001)	0.08	1.9 ²	1:1.3
846	VII (0.001)	0.07	1.2	1:1.3




¹ 20 mg $B(C_6F_5)_3$ added as activator. No support ² Incorporation may be high due to presence of homopolymer which makes calculation of % incorporation less accurate

Examples 847-850

General Procedure for Polymerizations in Tables 81-86

The polymerizations were carried out according to General Polymerization Procedure A. Varying amounts of acrylate homopolymer are present in some of the isolated polymers. For acrylate copolymers, the yield of the polymer is reported in grams and includes the yield of the dominant ethylene/acrylate copolymer as well as the yield of any acrylate homopolymer that was formed. Molecular weights were determined by GPC, unless indicated otherwise. Mole percent acrylate incorporation and total Me were determined by ¹H NMR spectroscopy, unless indicated otherwise. Mole percent acrylate incorporation is typi-

cally predominantly IC, unless indicated otherwise. The $\text{LiB}(\text{C}_6\text{F}_5)_4$ used (LiBArF) included 2.5 equiv of Et_2O .



2,6-Bis-dimethoxyphenyllithium was prepared from
 14.18 g (0.103 mole) of 1,3-dimethoxybenzene, 77 mL of a
 1.6 M solution of BuLi in hexanes and 0.23 mL of
 N,N,N',N'-tetramethylethylenediamine in dry diethyl ether
 (72 mL). Dichloromethylphosphine (5.0 g, 0.04276 mole) was
 added at 0°C, and the reaction mixture was stirred at room
 temperature overnight. Methanol (20 mL) was added, and
 the mixture was concentrated to about half its original
 volume under reduced pressure. The resulting white pre-
 cipitates were filtered and were recrystallized from
 methanol to give white crystals of bis-(2,6-
 dimethoxyphenyl)(methyl)-phosphine with 48% yield (6.6 g)
 and melting point at 112.33 °C. ^1H NMR (CDCl_3) δ 1.75 (s
 (broad), 3H, Me-P), 3.55 (s, 12H, Me-O), 6.4- 7.2 (m, 6H,
 aromatic protons); ^{31}P NMR (CDCl_3) δ - 51. 5 ppm. LS/MS:
 found m/w is 321, calculated m/w is 321. Anal. found: C
 64.30%; H 6.45%; calculated for $\text{C}_{17}\text{H}_{22}\text{O}_4\text{P}$: C 63.49%; H
 6.85%.

Synthesis of A-3. Bis-(2,6-
 dimethoxyphenyl)phosphino]-methyllithium ($(2,6\text{-MeO-Ph})_2\text{P-CH}_2\text{-Li}$) (0.33 g, 0.001 mole) was prepared from a 7 mL THF
 solution of equi-molar amounts of bis-(2,6-

dimethoxyphenyl)-(methyl)phosphine and a 1.6 M solution of butyllithium in hexanes with a catalytic amount of TMEDA added. *tert*-Butylisocyanate (0.125 g, 0.001 mole) in 3 mL of THF was added to the reaction mixture, which was then stirred for 12 hours. Next, 0.24 g (0.0005 mole) of 2-methoxycarbonyl-allyl nickel bromide dimer $[(CH_2=C(CO_2Me)CH_2)Ni(\mu-Br)]_2$ and 0.89 g (0.001 mole) of NaBAF in 4 mL of THF was added to the reaction mixture, which was stirred overnight. The next day, the solvent was pumped off and the residue was redissolved in diethyl ether. The solution was filtered through Celite®, and solvent was removed under vacuum. Viscous brown product (0.92 g) was obtained. ^{31}P NMR (CD_2Cl_2): one major peak at 26.49 ppm.

Synthesis of A-1 and A-4. Synthesis was in a fashion analogous to that reported for A-3 in above, except that $(t-Bu)_2PCH_2Li$ was employed as the base for the synthesis of A-1 and different electrophiles were employed. The electrophiles employed and compound characterization follow:

Cmpd	Electrophile	^{31}P NMR ^a (CD_2Cl_2) δ
A-1	2,4-Dimethoxyphenylisocyanate	60.6 ppm (major); 62.1 ppm (minor)
A-4	2,4,6-Trimethoxybenzophenone	22.5 (major)

^aIn some cases, additional minor resonances were present in the ^{31}P NMR spectrum.

Table 81

Ethylene Homopolymerizations and Ethylene/Acrylate Co-
polymerizations (18 h)

Ex	Cmpd (mmol)	Acrylate mL (Solvent mL)	B(C ₆ F ₅) ₃ (Borate)	Press MPa	Temp °C	Yield g	Ac- rylate Incorp. mol%	M.W.	To- tal Me
847	A-1 (0.004)	EGPEA 1 (<i>p</i> -Xylene 9)	100 equiv (NaBAF 50 equiv)	3.4	60	0.64	0.5 0.3 IC 0.2 EG	M _p =13,148; M _w =14,087; M _n =6,487; PDI=2.17	7.1
848	A-1 (0.02)	EGPEA 1 (<i>p</i> -Xylene 9)	20 equiv (NaBAF 10 equiv)	1	60	0.09	1.4 0.7 IC 0.7 EG	M _p =5,447; M _w =8,088; M _n =3,454; PDI=2.17	13.3
849	A-3 (0.02)	None (<i>p</i> -Xylene 10)	10 equiv (None)	3.4	60	0.80	—	M _p =801; M _w =37,894; M _n =500; PDI=75.77	119
850	A-4 (0.02)	None (<i>p</i> -Xylene 10)	10 equiv (None)	3.4	60	0.33	—	M _p =956; M _w =52,382; M _n =817; PDI=64.09	76.4

5

Table 82

Ethylene/Acrylate Copolymerizations (0.004 mmol Cmpd, 18
h, 100 equiv B(C₆F₅)₃, 50 equiv LiB(C₆F₅)₄, 1 mL EGPEA, 9 mL
p-Xylene)

10

Ex	Cmpd	Press MPa	Temp. °C	Yield g	Acrylate Incorp Mol%	M.W.	Total Me
851	45	2.1	60	0.008	0.7	M _n (¹ H): No Olefins	11.9
852	91	2.1	60	0.008	1.5	M _n (¹ H): No Olefins	13.6
853	94	2.1	60	0.011	1.2	M _n (¹ H): No Olefins	9.4
854 ^a	53	2.1	60	0.041	2.4 2.0 IC 0.4 EG	M _n (¹ H)=3,528.3	24.7

^aPredominant alpha olefin end groups; some internal olefin end groups also present.

Table 83

Ethylene/E-10-U Copolymerizations: Variation of Temperature and Pressure (0.02 mmol Cmpd; 2 mL E-10-U; 8 mL TCB; 40 equiv B(C₆F₅)₃; 18 h)

5

Ex	Cmpd	Press MPa	Temp °C	Yield g	Comonomer Incorp mol%	M.W.
855	46	1	25	3.24	3.3	M _p =67,355; M _w =74,377; M _n =39,452; PDI=1.89
856	46	3.4	60	11.14	2.8	M _p =67,243; M _w =69,152; M _n =34,553; PDI=2.00
857	46	6.9	120	6.09	1.1	M _p =13,731; M _w =20,516; M _n =5,477; PDI=3.75

Table 84

Ethylene/Zonyl TAN (ZTAN) Copolymerization (0.002 mmol Cmpd; 200 equiv B(C₆F₅)₃; 100 equiv NaBAF; 18 h)

10

Ex	Cmpd	ZTAN g (p-Xylene mL)	Press MPa	Temp °C	Yield g	Comonomer Incorp Mol%	M.W.	Total Me
858	45	2 (8)	6.9	120	17.90	Trace	M _p =11,579; M _w =12,467; M _n =4,226; PDI=2.95	Nd
859	45	3 (7)	4.1	80	0.613	0.52 (¹³ C NMR)	M _p =24,805; M _w =23,507; M _n =10,500; PDI=2.24	20.3 ^a (¹³ C NMR)
860	45 (0.002)	3 (7)	6.9	100	1.75	0.30 (¹³ C NMR)	M _p =20,490; M _w =21,489; M _n =10,466; PDI=2.05	27.4 ^b (¹³ C NMR)


^aBranches as determined by ¹³C NMR spectroscopy: 20.3 Total Me; 14.8 Me; 1.9 Et; 0.8 Pr, 1.2 Bu; 1.6 Hex+ and eoc; 2.7 Am+ and eoc; 2.8 Bu+ and eoc. ^bBranches as determined by ¹³C NMR spectroscopy: 27.4 Total Me; 18.9 Me; 2.9 Et; 1.3 Pr, 1.5 Bu; 3.5 Hex+ and eoc; 3.8 Am+ and eoc; 4.2 Bu+ and eoc.

Table 85


Ethylene/Acrylate/alpha-Olefin Terpolymerizations (0.002
mmol Cmpd; 18 h; 6.9 MPa E; 120°C; 8 mL p-Xylene; 200
equiv B(C₆F₅)₃; 100 equiv NaBAF; alpha-Olefins: 1-Hexene,
1-H; Ethyl-10-Undecylenate, E-10-U)

Ex	Cmpd	Acrylate mL	α -Olefin mL	Yield g	Acrylate Incorp ^a mol%	E-10-U Incorp ^a mol%	Total Me ^a
861	45	EGPEA 1	1-H 1	1.64	0.57	<i>b</i>	57.2 ^c
862	45	EGPEA 1	E-10-U 1	2.24	0.86	0.80	45.0 ^d
863	40	EGPEA 1	1-H 1	6.33	0.51 0.23 IC 0.28 EG	<i>b</i>	11.7 ^e
864	40	EGPEA 1	E-10-U 1	3.48	0.42 0.21 IC 0.21 EG	0.33	8.7 ^f

^aAcrylate incorporation, E-10-U incorporation, and Total Me were determined by ¹³C NMR spectroscopy. For 1-H terpolymers, acrylate incorporation was determined by assuming that the copolymer was derived from just ethylene and acrylate. ^bThe larger number of butyl branches relative to ethyl branches is consistent with 1-hexene incorporation. ^c57.2 Total Me; 31.6 Me; 7.2 Et; 2.9 Pr, 7.4 Bu; 4.5 Hex+ and eoc; 8.7 Am+ and eoc; 15.4 Bu+ and eoc; Me_{SBU} = 1.8%; Et_{SBU} = 16.4%. ^d45.0 Total Me; 23.8 Me; 5.6 Et; 6.6 Pr, 2.3 Bu; 4.1 Hex+ and eoc; 0.7 Am+ and eoc; 9.0 Bu+ and eoc; Me_{SBU} = 2.7%; Et_{SBU} = 18.4%. ^e11.7 Total Me; 2.0 Me; 0.8 Et; 0.3 Pr, 1.5 Bu; 5.9 Hex+ and eoc; 5.5 Am+ and eoc; 8.6 Bu+ and eoc. ^f8.7 Total Me; ~0 Me; 0.6 Et; 1.4 Pr, 0.3 Bu; 6.7 Hex+ and eoc; 1.5 Am+ and eoc; 6.7 Bu+ and eoc.



H-1



H-2


Table 86

Ethylene/Acrylate Copolymerizations (0.02 mmol Cmpd; 6.9

MPa E; 1 mL EGPEA; 9 mL TCB; 18 h)


Ex	Cmpd	Borane equiv	Borate equiv	Temp. °C	Yield G	Comonomer Incorporation mol%	M.W.	Total Me
865	H-1	B(C ₆ F ₅) ₃ 20	NaBAF 10	120	1.28	0.2 IC & EG	M _p =5,017; M _w =6,796; M _n =1,840; PDI=3.69	54.3
866	H-2	BPh ₃ 20	none	80	0.14	5.3	Bimodal UV: M _p =21,679; RI M ₀ =20,271;	22.0

Example 867 - Synthesis of (t-Bu)₂PCH₂N(2,6-C₆F₂H₃)OLi




1001

In a dry box, to a 50 mL flask containing 10 mL of THF solution of 1,3-difluoro-2-nitrosobenzene (0.0276 g, 0.193 mmol), was added slowly to a THF solution of (t-Bu)₂PCH₂Li (0.0321 g, 0.193 mmol) at -30°C. The solution was stirred 2 hours and it turned brown. After removal of the solvent, the purple residue was rinsed with pentane and dried under vacuum. A brown powder was obtained.

Example 868 - Synthesis of (t-Bu)₂PCH₂N(2-(3-OLi)C₁₀H₆)OLi

1002


In a dry box, to a 100 mL flask containing 20 mL of THF solution of 2-nitroso-1-naphthol (0.1044 g, 0.603 mmol), NaH (0.016 g, 1.1 equiv.) powder was added slowly at room temperature. When no more H₂ was released, a THF solution of (t-Bu)₂PCH₂Li (0.1002 g, 0.603 mmol) at -30°C was added slowly. The solution was stirred 2 hours and turned brown from yellow. After removing the solvent, a brown powder (0.1402 g, 0.388 mmol) was obtained in 64% yield. ¹H NMR (C₆D₆): complicated. ³¹P NMR (C₆D₆): major peak 29.5636 ppm.

Example 869 - Synthesis of (t-Bu)₂PCH₂N(C₆H₅)OLi

1003

In a dry box, to a 100 mL flask containing 20 mL of THF solution of nitrosobenzene (0.0682 g, 0.64 mmol), was added slowly a THF solution of (t-Bu)₂PCH₂Li (0.1058 g, 0.64 mmol) at -30°C. The solution was stirred overnight and turned purple from yellow. After removing the solvent, a purple powder (0.1321 g, 0.483 mmol) was obtained in 76% yield. ¹H NMR (C₆D₆): complicated; ³¹P NMR (C₆D₆): major peak 38.1167 ppm.

Example 870 - Synthesis of (t-Bu)₂PCH₂N(2-CH₃-C₆H₄)OLi




1004

In dry box, to a 100 mL flask containing 20 mL of THF
5 solution of o-nitrosotoluene (0.0763 g, 0.63 mmol) was
added slowly a THF solution of (t-Bu)₂PCH₂Li (0.1046 g,
0.63 mmol) at -30 °C. The solution was stirred overnight
and turned purple from yellow. After removing the solvent
and rinsing with pentane, a purple powder (0.1538 g, 0.54
10 mmol) was obtained in 85% yield. ¹H NMR (C₆D₆): compli-
cated; ³¹P NMR (C₆D₆): complicated, indicating the desired
product, but also additional products.


Examples 871-874 - Polymerizations of Ethylene at 1000 psi
15 of C₂H₄ in shaker tube:

Ex	Ligand	PE (g)	TO (molPE/ mol cat)
871	1001	3.0595	5110.9
872	1002	7.9434	13827.2
873	1003	6.8919	13165.7
874	1004	3.9511	7226.8


Conditions: 0.02 mmol ligand, 1 equiv. Allyl-Ni
complex, 10 equiv. B(C₆F₅)₃, 5 ml TCB, RT, 18 h.




1005




1006




1007




1008




1009



1010



1011



1012

The syntheses of aminopyrrole ligands is published in
WO00/50470.

Example 875 - Synthesis of Ligand 1005

A 50 mL round bottom flask was charged with 0.3988 g (2.745 mmol) of 40 wt. % glyoxal solution in water, 0.6045 g (5.49 mmol) of 1-amino-2,5-dimethylpyrrole, 15 ml methanol and 1 drop of formic acid. The mixture was stirred overnight and light brown precipitate formed. The solid

was collected by filtration, rinsed with hexane and dried under vacuum. 0.46 g (1.9 mmol) of product was obtained in 69% yield. ^1H NMR (CDCl_3) δ 8.18 (s, 2, C-H), 5.8 (s, 4, Hpy), 2.3 (s, 12, CH_3).

5 Example 876 - Synthesis of Ligand 1006

A 50 mL round bottom flask was charged with 0.25 g (2.9 mmol) of 2,3-butadione, 0.696 g (6.318 mmol) of 1-amino-2,5-dimethylpyrrole, 20 ml methanol and 1 drop of formic acid. The reaction was monitored by TLC with elute
10 of 10% ethyl acetate in hexane. Two major spots were showed on the TLC even after overnight stirring. The clear yellow mixture was stirred 2 days and the solvent was removed. The yellow residue was recrystallized with hexane. 0.26 g (0.96 mmol) of bis-substituted product and
15 0.3652 g (2.0 mmol) of mono-substituted product were obtained. ^1H NMR (CDCl_3) for bis-: δ 5.83 (s, 4, Hpy), 2.12 (s, 6, CH_3), 2.0 (s, 12, CH_3 - Py). ^1H NMR (CDCl_3) for mono-: δ 5.83 (s, 4, H-py), 2.52 (s, 3, CH_3), 1.96 (s, 12, CH_3 - py), 1.92 (s, 3, CH_3).

20 Example 877 - Synthesis of Ligand 1007

A 150 mL round bottom flask was charged with 0.6 g (2.9 mmol) of acenaphthenequinone, 0.6488 g (5.89 mmol) of 1-amino-2,5-dimethylpyrrole, 50 ml methanol and 1 drop of formic acid. The reaction was monitored by TLC with elute
25 of 30% ethyl acetate in hexane and stirred 3 days. The solvent was removed under vacuum and the red residue was separated on a silica gel column with 30% ethyl acetate in hexane. 0.07 g (0.19 mmol) of dark red crystals bis-substituted product and 0.06 g (0.2 mmol) of orange powder
30 mono-substituted product were obtained. ^1H NMR (CDCl_3) for bis-: δ 7.96 (d, 2, H-acen), 7.5 (t, 2, H-acen), 6.74 (d, 2, H-acen), 5.99 (s, 4, H-py), 2.08 (s, 12, CH_3 - Py).

^1H NMR (CDCl_3) for mono-: δ 8.17 (d-d, 2, H-acen), 8.08 (d, 1, H-acen), 7.8 (t, 1, H-acen), 7.54 (t, 1, H-acen), 6.91 (d, 1, H-acen), 5.97 (s, 2, H-py), 2.02 (s, 6, CH_3 -Py).

If the reaction was carried out in toluene with p-

toluenesulfonic acid as catalyst under reflux, the exclusive product was bis-substituted but it was isolated in very low yield.

Example 878 - Synthesis of Ligand 1008

A 50 mL round bottom flask was charged with 0.1418 g (1.65 mmol) of 2,3-butadione, 0.5478 g (3.29 mmol) of 1-amino-2,5-diisopropylpyrrole, 20 ml methanol and 1 drop of formic acid. The reaction was monitored by TLC with elute of 10% ethyl acetate in hexane and stirred 2 days at 50 $^\circ\text{C}$. The solvent was removed under vacuum and the yellow oily residue was separated on a silica gel column with 5% ethyl acetate in hexane. 0.226 g (0.59 mmol) of yellow crystalline product was obtained in 36% yield. ^1H NMR (CDCl_3): 5.86 (s, 4, H-py), 2.53 (m, 4, H-Pr-i), 2.11 (s, 6, CH_3)₂, 1.10 (d, 24, CH_3 -Pr-i).

Example 879 - Synthesis of Ligand 1009

A 100 mL round bottom flask was charged with 0.4418 g (2.43 mmol) of acenaphthenequinone, 0.907 g (4.85 mmol) of 1-amino-2-methyl-5-phenylpyrrole, 50 ml methanol and 1 drop of formic acid. The reaction was monitored by TLC with elute of 30% ethyl acetate in hexane and stirred 7 days at RT. The solvent was removed under vacuum and the red solid residue was separated on a silica gel column with 10% ethyl acetate in hexane. 0.15 g (0.30 mmol) of dark red crystals were obtained in 13% yield. ^1H NMR (CD_2Cl_2): δ 8.06 (m, 2H), 7.72 - 7.6 (m, 6H), 7.32 (m, 4H), 7.18 (m, 2H), 6.92 (d, 1H), 6.86 (d, 1H), 6.66 (d-d, 2H), 6.38 (d, 2H), 2.32 (d, 6, CH_3).

Example 880 - Synthesis of Ligand 1010

A 100 mL round bottom flask was charged with 0.1881 g (2.18 mmol) of 2,3-butadione, 0.817 g (4.37 mmol) of 1-amino-2-methyl-5-phenylpyrrole, 50 ml methanol and 1 drop of formic acid. The reaction was stirred 7 days at RT and yellow precipitate formed. The reaction mixture was filtered through a frit to collect the yellow solid that then was dissolved in ether and dried over Na_2SO_4 . The ether was removed and the yellow solid was dried under high vacuum. 0.46 g (1.17 mmol) yellow powder was obtained in 53% yield. ^1H NMR (CD_2Cl_2): δ 7.20 (m, 8, Ph-H), 7.10 (t, 2, Ph-H), 6.20 (d, 2, Py-H), 5.95 (m, 2, Py-H), 2.05 (s, 6, CH_3), 1.80 (s, 6, CH_3).

Example 881 - Synthesis of Ligand 1011

A 100 mL round bottom flask was charged with 0.129 g (1.5 mmol) of 2,3-butanedione, 0.7021 g (3.0 mmol) of 1-amino-2,5-diphenylpyrrole, 50 ml methanol and 1 drop of formic acid. The reaction was monitored by TLC with elute of 30% ethyl acetate in hexane and stirred 7 days at RT. The solvent was removed under vacuum and the red solid residue was separated on a silica gel column with 10% ethyl acetate in hexane. 0.4963 g (0.97 mmol) of yellow powder was obtained in 64% yield. ^1H NMR (CD_2Cl_2): δ 7.37 (m, 4, ph-H), 7.28 (m, 6, ph-H), 6.49 (s, 2, py-H), 1.76 (s, 6, CH_3).

Example 882 - Synthesis of Catalyst 1012

The ligand 7 (0.1102 g, 0.212 mmol), allyl-Ni dimer ($[(2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr}]_2$) (0.0505 g, 0.106 mmol) and Na(tetra[3,5-bis(trifluoromethyl)]-phenylborane) (0.1879 g, 0.212 mmol) were mixed in 20 mL of ether in a 50 mL of round bottom flask. The reaction mixture was stirred at room temperature for one hour and filtered through a Celite plug on a frit. Removal of the solvent yields a

brown powder that was then rinsed with pentane and dried under high vacuum. 0.3069 g (0.199 mmol) product was collected in 94% yield. ^1H NMR (CD_2Cl_2): δ 7.58 - 7.06 (m, 6, Ar-H), 6.46 (d, 2, Py-H), 6.40 (d, 2, Py-H), 3.65 (s, 2, allyl-H), 3.42 (s, 3, MeO), 1.90 (s, 6, CH_3), 1.85 (s, 2, allyl-H).

Examples 883-898

Copolymerization of ethylene and polar-comonomers

10 Into a glass vial used for shaker reaction, were weighed 0.02 mmol of the ligand, 1 equivalent of allyl-Ni dimer ($[(2\text{-MeO}_2\text{C-C}_3\text{H}_4)\text{NiBr}]_2$) and 10 equivalent of NaBaf. 2 ml of ether was added into the vial and shaken well. After two hours during which time the most of the ether
15 was evaporated off, 20 equivalent of tri(pentafluorophenyl)-borane cocatalyst, 9 ml of 1,2,4-trichlorobenzene and 1 ml of ethylene glycol phenyl ether acrylate was added into the vial. The vials were placed into a shaker tube, sealed, and taken out from the dry
20 box. The shaker tube was connected to a high pressure, ethylene shaker reaction unit. Reaction conditions for polymerization were: 1000 psi ethylene, 120 °C, 18 hours.

Table 87: Results of shaker tube copolymerizations

Ex	Ligand	Polymer yield (g)	Catalyst Produc- tivity (Kg/g)	M _w	M _n	M _n /M _w	Me/1000 CH ₂	Comon. Incorp. (Mol %)	Peak MP (°C) ΔH (J/g)
883	1007	1.4967	1.37	2482	992	2.5	29.2	0.35	89 broad
884	1006	1.0752	0.88	3586	1306	2.75	28.5	0.27	114 shoulder
885	1008	2.3451	2.07	38156	20004	1.91	-	Trace	86 shoulder
886	1008	2.6151	2.75	22933	1106	20.74 b	-	Trace	93 109
887	1011	1.5141	1.09	5371	1209	4.44 b	-	trace	127 shoulder
888	1009	2.674	2.24	2754	1082	2.55 b		trace	66 158
889	1010	1.6429	1.33	3860	1166	3.31 b		trace	117 shoulder
890	1007	0.6397	0.78	20928	2232	9.37 b		trace	120 shoulder

Table 87 cont'd

Ex	Ligand	Polymer yield (g)	Catalyst Productivity (Kg/g)	M _w	M _n	M _n /M _w	Me/1000 CH ₂	Comon. Incorp. (Mol %)	Peak MP (°C) ΔH (J/g)
891	1009	0.6282	0.53	208622	1615	129.15b bimodal			85 broad
892	1010	0.7601	0.61	4855	1644	2.95 b			110 broad
893	1012	1.4557	1.22	16467	1116	14.76 b			125 160
894	1012	1.2511	1.06	17343	844	20.55 b	-	Trace	124 154.0
895	1007	1.1725	1.38	2832	1207	2.35 b			120 shoulder
896	1006	1.5382	0.97	29780	1160	25.68	-	0.15	122 185
897	1008	2.0138	2.08	14466	1293	11.19	-	trace	
898	1012	1.8074	1.56	54346	1881	28.9	-	0	125 shoulder

Notes: a. 20 equivalent of NaBarf,

b. RI data for GPC in THF, dual detector RI-UV,

c. $[\text{AlMe}_2(\text{Et}_2\text{O})]^+[\text{MeB}(\text{C}_6\text{F}_5)_3]^-$ cocatalyst and *p*-xylene solvent,



d. No allyl-Ni dimer needed,

e. Hexyl acrylate comonomer.

CLAIMS

What is claimed is:

1. A Group 3 through 11 (IUPAC) transition metal or a lanthanide metal complex of a ligand of the formula (I),
 5 (II) or (XII)



10 wherein:

R^1 and R^2 are each independently hydrocarbyl, substituted hydrocarbyl or a functional group;

Y is $CR^{11}R^{12}$, $S(T)$, $S(T)_2$, $P(T)Q$, NR^{36} or $NR^{36}NR^{36}$;

X is O , CR^5R^6 or NR^5 ;

15 A is O , S , Se , N , P or As ;

Z is O , Se , N , P or As ;

each Q is independently hydrocarbyl or substituted hydrocarbyl;

20 R^3 , R^4 , R^5 , R^6 , R^{11} and R^{12} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R^7 is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group, provided that when Z is O or Se , R^7 is not present;

25 R^8 and R^9 are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R^{10} is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

each T is independently =O or =NR³⁰;

R^{30} is hydrogen, hydrocarbyl, substituted hydrocarbyl or
5 a functional group;

R^{31} and R^{32} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

R^{33} and R^{34} are each independently hydrocarbyl or substituted hydrocarbyl, provided that each is independently an
10 aryl substituted in at least one position vicinal to the free bond of the aryl group, or each independently has an E_s of -1.0 or less;

R^{35} is hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group, provided that when A is O, S or Se, R^{35}
15 is not present;

each R^{36} is independently hydrogen, hydrocarbyl, substituted hydrocarbyl or a functional group;

m is 0 or 1;

s is 0 or 1;

20 n is 0 or 1; and

q is 0 or 1;

and provided that:

any two of R^3 , R^4 , R^5 , R^6 , R^8 , R^9 , R^{11} and R^{12} bonded to the same carbon atom taken together may form a functional
25 group;

any two of R^1 , R^2 , R^3 , R^4 , R^5 , R^6 , R^7 , R^8 , R^9 , R^{11} , R^{12} , R^{31} , R^{32} , R^{33} , R^{34} , R^{35} and R^{36} bonded to the same atom or vicinal to one another taken together may form a ring; and

when said ligand is (I), Y is C(O), Z is O, and R^1 and
30 R^2 are each independently hydrocarbyl, then R^1 and R^2 are each independently an aryl substituted in one position vicinal to the free bond of the aryl group, or R^1 and R^2 each independently have an E_s of -1.0 or less.

2. The complex of claim 1, characterized in that said transition metal is Ni, Pd, Pt, Fe, Co, Ti, Zr, V, Hf, Cr or Cu.

5

3. The complex of claim 2, characterized in that said transition metal is Ni, Pd, Ti or Zr.

4. The complex of claim 1, characterized in that the
10 ligand is (I) and:

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

15 the transition metal is Ti, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

20 the transition metal is Zr, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

25 the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} is hydrogen, R^{12} is hydrocarbyl or substituted hydrocarbyl, and Z is N; or

the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is O; or

30 the transition metal is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is N; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =N-silyl, Z is N and R⁷ is silyl; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O, Z is N, and R⁷ is hydrocarbyl or substituted hydrocarbyl; or



the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are a ring and Z is O; or


the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are N-hydrocarbyl- or N-substituted hydrocarbylimino, Z is N and R⁷ is hydrocarbyl or substituted hydrocarbyl; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are sulfo, Z is N and R⁷ is hydrocarbyl or substituted hydrocarbyl.

5. The complex of claim 1, characterized in that the complex is a compound of formula (IV), (V) or (XIII)





(XIII)

wherein:

M is a Group 3 through Group 11 transition metal or a lanthanide metal; and

L^1 is a monodentate monoanionic ligand into which an ethylene molecule may insert between L^1 and M, and L^2 is a monodentate neutral ligand which may be displaced by ethylene or an empty coordination site, or L^1 and L^2 taken together are a monoanionic bidentate ligand into which ethylene may insert between said monoanionic bidentate ligand and said nickel atom, and each L^3 is independently a monoanionic ligand and z is the oxidation state of M minus 2;

and provided that;

any two of R^3 , R^4 , R^5 , R^6 , R^8 , R^9 , R^{11} and R^{12} bonded to the same carbon atom taken together may form a functional group;

any two of R^1 , R^2 , R^3 , R^4 , R^5 , R^6 , R^7 , R^8 , R^9 , R^{11} , R^{12} , R^{31} , R^{32} , R^{33} , R^{34} , R^{35} and R^{36} bonded to the same atom or vicinal to one another taken together may form a ring; and

when said compound is (IV), Y is C(O), Z is O, and R^1 and R^2 are each independently hydrocarbyl, then R^1 and R^2 are each independently an aryl substituted in one position vicinal to the free bond of the aryl group, or R^1 and R^2 each independently have an E_s of -1.0 or less.

6. The complex of claim 5, characterized in that M is Ni, Pd, Pt, Fe, Co, Ti, Zr, V, Hf, Cr or Cu.

7. The complex of claim 6, characterized in that M is
5 Ni, Pd, Ti or Zr.

8. The complex of claim 5, characterized in that the compound is (IV) and:

10 M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

15 M is Ti, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

20 M is Zr, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} is hydrocarbyl or substituted hydrocarbyl, R^{12} is hydrocarbyl, substituted hydrocarbyl or a functional group, and Z is O; or

M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} is hydrogen, R^{12} is hydrocarbyl or substituted hydrocarbyl, and Z is N; or

25 M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is O; or

M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, R^7 is hydrocarbyl or substituted hydrocarbyl, Y is $CR^{11}R^{12}$, R^{11} and R^{12} taken together are oxo, and Z is N; or

30 M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is S(T), T is =O and Z is O; or

M is Ni, m is 0, n is 1, R^3 and R^4 are hydrogen, Y is S(T), T is =N-silyl, Z is N and R^7 is silyl; or

M is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O, Z is N, and R⁷ is hydrocarbyl or substituted hydrocarbyl; or

5 M is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are a ring and Z is O; or

M is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are N-hydrocarbyl- or N-substituted hydrocarbylimino, Z is N and R⁷ is hydrocarbyl or substituted hydrocarbyl; or

10 M is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is S(T), T is =O and Z is O; or

the transition metal is Ni, m is 0, n is 1, R³ and R⁴ are hydrogen, Y is CR¹¹R¹², R¹¹ and R¹² taken together are sulfo, Z is N and R⁷ is hydrocarbyl or substituted hydrocar-
15 byl.

9. A polymerization catalyst component comprising the complex of any one of claims 1-8.

20 10. The component of claim 9, which is on a solid support.

11. The component of claim 9, characterized in that a cocatalyst which is an alkylaluminum compound or a borane or
25 both is also present.


12. A process for the polymerization of olefins, comprising the step of contacting, at a temperature of about -100°C to about +200°C, at least one polymerizable olefin
30 with an active polymerization catalyst, characterized in that the active polymerization catalyst comprises the polymerization catalyst component of claim 9.




13. A process for forming an ethylene/polar monomer copolymer, comprising the step of contacting, under polymerizing conditions, a transition metal catalyst with a monomer component comprising one or more hydrocarbon olefins and one or more polar comonomers, characterized in that the transition metal catalyst comprises a nickel complex of a bidentate neutral ligand or a bidentate monoanionic ligand, and the catalyst and monomer component are contacted at a temperature of about 60°C to about 170°C, provided that when CO is present, at least one other polar monomer is present.

14. The process of claim 13, characterized in that ethylene is present and an ethylene partial pressure of at least about 0.67 MPa is used.

15. The process of claim 13, characterized in that said one or more polar comonomers comprises $\text{H}_2\text{C}=\text{CHR}^{20}\text{C}(\text{O})\text{Y}$, or $\text{H}_2\text{C}=\text{CR}^{25}\text{C}(\text{O})\text{Y}$, wherein R^{20} is alkylene or substituted alkylene, R^{25} is hydrogen, and Y is $-\text{OH}$, $-\text{NR}^{21}\text{R}^{22}$, $-\text{OR}^{23}$, or $-\text{SR}^{24}$, wherein R^{21} and R^{22} are each independently hydrogen, hydrocarbyl or substituted hydrocarbyl, R^{23} and R^{24} are each hydrocarbyl or substituted hydrocarbyl.

16. The process of any one of claims 13-15, characterized in that said bidentate ligand is





wherein:

10 R^{26} and R^{27} are each independently hydrocarbyl or substituted hydrocarbyl, provided that the carbon atom bound to the imino nitrogen atom has at least two carbon atoms bound to it;

15 R^{28} and R^{29} are each independently hydrogen, hydrocarbyl, substituted hydrocarbyl, or R^{28} and R^{29} taken together are hydrocarbylene or substituted hydrocarbylene to form a carbocyclic ring;

20 R^{60} and R^{61} are each independently functional groups bound to the rest of (XV) through heteroatoms (for example O, S or N), or R^{60} and R^{61} (still containing their heteroatoms) taken together form a ring.

each R^{50} is independently hydrocarbyl or substituted hydrocarbyl;

each R^{51} is independently hydrogen, hydrocarbyl or substituted hydrocarbyl; and

5 each R^{52} is hydrocarbyl, substituted hydrocarbyl, hydrocarbyloxy, or substituted hydrocarbyloxy.

17. A polymer, consisting essentially of repeat units derived from ethylene, and one or more polar olefins of the
10 formula $H_2C=CHC(O)R^{32}$, wherein R^{32} is $-OR^{34}$ or any group readily derivable from it, and R^{34} is hydrocarbyl or substituted hydrocarbyl, characterized in that:

said polymer contains "first branches" of the formula $-(CH_2)_nCH_3$ and "second branches" of the formula $-(CH_2)_mC(O)R^{32}$,
15 wherein m and n are independently zero or an integer of 1 or more; and

said polymer has the following structural characteristics:

(a) one or both of:

20 (1) the ratio of first branches wherein n is 0 to first branches wherein n is 1 is about 3.0 or more; and

(2) the ratio of first branches wherein n is 0 to first branches wherein n is 3 is 1.0 or more; and

25 (b) one or both of:

(1) the total number of first branches in which n is 0, 1, 2 and 3 in said polymer is about 10 or more per 1000 CH_2 groups; and

30 (2) the incorporation of repeat units derived from $H_2C=CHC(O)R^{32}$ is 0.3 mole percent or more based on the total repeat units derived from the hydrocarbonolefin and $H_2C=CHC(O)R^{32}$.

18. A polymer, consisting essentially of repeat units derived from:


one or more hydrocarbon olefins, such as ethylene, and
one or more polar olefins of the formula $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$,
5 wherein R^{32} is $-\text{OR}^{34}$, or any group readily derivable from it,
and R^{34} is hydrocarbyl or substituted hydrocarbyl,
characterized in that

in said polymer incorporation of repeat units derived
from $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$ is 0.3 mole percent or more based on the
10 total repeat units; and

said polymer has one or both of the following structural characteristics:

at least 5 mole percent of said repeat units derived
from $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$ are present in said polymer as end groups;
15 and

said end groups are at least 0.001 mole percent of the
total repeat units in said polymer;
and provided that said end groups have the formula




20 wherein ----- is the remainder of the polymer chain of
said end group.

19. A polymer, consisting essentially of:

repeat units derived from ethylene;

25 repeat units derived from one or more monomers of the
formula $\text{H}_2\text{C}=\text{CHC}(\text{O})\text{R}^{32}$, wherein each R^{32} is independently $-\text{OR}^{34}$
or any group readily derivable from it, and each R^{34} is inde-
pendently hydrocarbyl or substituted hydrocarbyl, and

repeat units derived from one or more alpha-olefins of
30 formulas $\text{H}_2\text{C}=\text{CH}-(\text{CH}_2)_t-\text{H}$ and/or $\text{H}_2\text{C}=\text{CH}-\text{R}^{75}-\text{G}$, wherein t is an
integer of 1 to 20, R^{75} is alkylene or substituted alkylene,
and G is an inert functional group.



١٢٤




FIG. 2

3/3

Mole % Calculations

$$MA = \frac{\text{comonomer+tends}}{\text{comonomer+tends+ethylene}}$$

$$\text{Ethylene} = \frac{\text{ethylene}}{\text{comonomer+tends+ethylene}} \quad \text{OR}$$

$$MA \text{ comonomer} = \frac{\text{comonomer+tends}}{\text{comonomer+tends+homopolymer+ethylene}}$$

$$MA \text{ homopolymer} = \frac{\text{homopolymer}}{\text{comonomer+tends+homopolymer+ethylene}}$$

$$\text{Ethylene} = \frac{\text{ethylene}}{\text{comonomer+tends+homopolymer+ethylene}}$$

Methyl Acrylate comonomer = Y peak
 Methyl Acrylate vinyl end = V
 Ethylene = $([10-40 \text{ ppm}] - J)/2$
 Methyl Acrylate homopolymer = J-Y





FIG. 3

(19) World Intellectual Property Organization
International Bureau



(43) International Publication Date
6 December 2001 (06.12.2001)

PCT

(10) International Publication Number
WO 01/092342 A3

(51) International Patent Classification⁷: **C08F 4/70**,
4/80, 4/642, 110/02, 210/02, C07F 15/04, 7/00 // (C08F
210/02, 220:12, 220:18, 220:24, 220:30, 216:02, 216:20,
216:36, 222:14)

Wooded Knoll, West Chester, PA 19382 (US). ITTEL,
Steven, D. [US/US]; 7 Barley Mill Drive, Wilmington, DE
19807 (US).

(21) International Application Number: PCT/US01/17627

(74) Agent: LERMAN, Bart, E.; E.I. Du Pont De Nemours
And Company, Legal Patent Records Center, 1007 Market
Street, Wilmington, DE 19898 (US).

(22) International Filing Date: 31 May 2001 (31.05.2001)

(25) Filing Language: English

(26) Publication Language: English

(30) Priority Data:
60/208,087 31 May 2000 (31.05.2000) US
60/211,601 15 June 2000 (15.06.2000) US
60/214,036 23 June 2000 (23.06.2000) US
60/264,537 25 January 2001 (25.01.2001) US

(81) Designated States (*national*): AE, AG, AL, AM, AT, AU,
AZ, BA, BB, BG, BR, BY, BZ, CA, CH, CN, CO, CR, CU,
CZ, DE, DK, DM, DZ, EE, ES, FI, GB, GD, GE, GH, GM,
HR, HU, ID, IL, IN, IS, JP, KE, KG, KP, KR, KZ, LC, LK,
LR, LS, LT, LU, LV, MA, MD, MG, MK, MN, MW, MX,
MZ, NO, NZ, PL, PT, RO, RU, SD, SE, SG, SI, SK, SL,
TJ, TM, TR, TT, TZ, UA, UG, US, UZ, VN, YU, ZA, ZW.

(71) Applicant (*for all designated States except US*): E.I. DU
PONT DE NEMOURS AND COMPANY [US/US]; 1007
Market Street, Wilmington, DE 19898 (US).

(84) Designated States (*regional*): ARIPO patent (GH, GM,
KE, LS, MW, MZ, SD, SL, SZ, TZ, UG, ZW), Eurasian
patent (AM, AZ, BY, KG, KZ, MD, RU, TJ, TM), European
patent (AT, BE, CH, CY, DE, DK, ES, FI, FR, GB, GR, IE,
IT, LU, MC, NL, PT, SE, TR), OAPI patent (BF, BJ, CF,
CG, CI, CM, GA, GN, GW, ML, MR, NE, SN, TD, TG).

(72) Inventors; and

(75) Inventors/Applicants (*for US only*): WANG, Lin
[US/US]; 112 Brook Run, Hockessin, DE 19707 (US).
HAUPTMAN, Elisabeth [FR/US]; 26 Holly Way, Wilm-
ington, DE 19809 (US). JOHNSON, Lynda, K. [US/US];
707 Burnley Road, Wilmington, DE 19803 (US). MC-
CORD, Elizabeth, F. [US/US]; 514 Hemlock Drive,
Hockessin, DE 19707 (US). WANG, Ying [CN/US]; 1347

Published:

— with international search report

(88) Date of publication of the international search report:
16 January 2003

*For two-letter codes and other abbreviations, refer to the "Guid-
ance Notes on Codes and Abbreviations" appearing at the begin-
ning of each regular issue of the PCT Gazette.*

(54) Title: CATALYSTS FOR OLEFIN POLYMERIZATION

(57) Abstract: Transition metal complexes of selected monoanionic phosphine ligands, which also contain a selected Group 15 or 16 (IUPAC) element and which are coordinated to a Group 3 to 11 (IUPAC) transition metal or a lanthanide metal, are po-lymerization catalysts for the (co)polymerization of olefins such as ethylene and α -olefins, and the copolymerization of such olefins with polar group-containing olefins. These and other nickel complexes of neutral and monoanionic bidentate ligands copolymerize ethylene and polar comonomers, especially acrylates, at relatively high ethylene pressures and surprisingly high temperatures, and give good incorporation of the polar comonomers and good polymer productivity. These copolymers are often unique structures, which are described.

WO 01/092342 A3

INTERNATIONAL SEARCH REPORT

International Application No
PCT/US 01/17627

A. CLASSIFICATION OF SUBJECT MATTER

IPC 7 C08F4/70 C08F4/80 C08F4/642 C08F110/02 C08F210/02
C07F15/04 C07F7/00 //(C08F210/02, 220:12, 220:18, 220:24,
220:30, 216:02, 216:20, 216:36, 222:14)

According to International Patent Classification (IPC) or to both national classification and IPC

B. FIELDS SEARCHED

Minimum documentation searched (classification system followed by classification symbols)

IPC 7 C08F C07F

Documentation searched other than minimum documentation to the extent that such documents are included in the fields searched

Electronic data base consulted during the international search (name of data base and, where practical, search terms used)

CHEM ABS Data, EP0-Internal

C. DOCUMENTS CONSIDERED TO BE RELEVANT

Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	WO 98 30609 A (COUGHLIN EDWARD BRYAN ;ITTEL STEVEN DALE (US); DU PONT (US); FELDM) 16 July 1998 (1998-07-16) page 69; example 46 page 71; example 159; table 7 page 79; examples 219, 220; table 9 claim 1; example XXXVIII claims 2, 36; example XXXII --- -/--	1-19

☒ Further documents are listed in the continuation of box C.

☒ Patent family members are listed in annex.

* Special categories of cited documents:

- "A" document defining the general state of the art which is not considered to be of particular relevance
- "E" earlier document but published on or after the international filing date
- "L" document which may throw doubts on priority claim(s) or which is cited to establish the publication date of another citation or other special reason (as specified)
- "O" document referring to an oral disclosure, use, exhibition or other means
- "P" document published prior to the international filing date but later than the priority date claimed

"T" later document published after the international filing date or priority date and not in conflict with the application but cited to understand the principle or theory underlying the invention

"X" document of particular relevance; the claimed invention cannot be considered novel or cannot be considered to involve an inventive step when the document is taken alone

"Y" document of particular relevance; the claimed invention cannot be considered to involve an inventive step when the document is combined with one or more other such documents, such combination being obvious to a person skilled in the art.

"&" document member of the same patent family

Date of the actual completion of the international search

23 April 2002

Date of mailing of the international search report

14 08. 2002

Name and mailing address of the ISA

European Patent Office, P.B. 5818 Patentlaan 2
NL - 2280 HV Rijswijk
Tel. (+31-70) 340-2040, Tx. 31 651 epo nl,
Fax (+31-70) 340-3016

Authorized officer

Parry, J.

C.(Continuation) DOCUMENTS CONSIDERED TO BE RELEVANT		
Category *	Citation of document, with indication, where appropriate, of the relevant passages	Relevant to claim No.
X	<p>HITCHCOCK, PETER B. ET AL: "Use of a highly hindered phosphino-alkoxide ligand in the formation of monomeric homoleptic lanthanoid metal complexes: x-ray structures of $[Ln(OC(Bu-tert)2CH2PMe2)3]$ (Ln = Y or Nd)"</p> <p>J. CHEM. SOC., CHEM. COMMUN. (1988), (23), 1557-8,</p> <p>XP001073452</p> <p>page 1558; figure 1</p> <p>-----</p>	1

INTERNATIONAL SEARCH REPORT

International application No.
PCT/US 01/17627

Box I Observations where certain claims were found unsearchable (Continuation of item 1 of first sheet)

This International Search Report has not been established in respect of certain claims under Article 17(2)(a) for the following reasons:

1. ☐ Claims Nos.:
because they relate to subject matter not required to be searched by this Authority, namely:
2. ☒ Claims Nos.: 1-16 (in part)
because they relate to parts of the International Application that do not comply with the prescribed requirements to such an extent that no meaningful International Search can be carried out, specifically:
see FURTHER INFORMATION sheet PCT/ISA/210
3. ☐ Claims Nos.:
because they are dependent claims and are not drafted in accordance with the second and third sentences of Rule 6.4(a).

Box II Observations where unity of invention is lacking (Continuation of item 2 of first sheet)

This International Searching Authority found multiple inventions in this International application, as follows:

see additional sheet

1. ☐ As all required additional search fees were timely paid by the applicant, this International Search Report covers all searchable claims.
2. ☐ As all searchable claims could be searched without effort justifying an additional fee, this Authority did not invite payment of any additional fee.
3. ☐ As only some of the required additional search fees were timely paid by the applicant, this International Search Report covers only those claims for which fees were paid, specifically claims Nos.:
4. ☒ No required additional search fees were timely paid by the applicant. Consequently, this International Search Report is restricted to the invention first mentioned in the claims; it is covered by claims Nos.:
1-16 (in part)

Remark on Protest

- ☐ The additional search fees were accompanied by the applicant's protest.
- ☐ No protest accompanied the payment of additional search fees.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

This International Searching Authority found multiple (groups of) inventions in this international application, as follows:

1. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

2. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

3. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

4. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

5. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

6. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

7. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

8. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

9. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

10. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 2$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

11. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

12. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

13. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

14. Claims: 1-16 (in part)

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

15. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

16. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

17. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

18. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

19. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

20. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

21. Claims: 1-16 (in part).

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

22. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

23. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

24. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

25. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

26. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

27. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = O, S$ or NR_3 .

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

28. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = 0$, S or NR_3 .

29. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = 0$, S or NR_3 .

30. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 0$; $Y = CR_3R_4$; $Z = 0$, S or NR_3 .

31. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

32. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

33. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

34. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

35. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

36. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

37. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

38. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

39. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to previous groups 1-27, in which additionally Z is linked to a light metal or boron compound.

40. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to previous groups 1-27, in

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

which additionally Z is linked to a light metal or boron compound.

41. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

42. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

43. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

44. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

45. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

46. Claims: 1-16 (in part)

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

47. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

48. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

49. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the transition metal, is CT, or CS, or ST, or ST2.

50. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula 1, claim 1 wherein $m = 0$; $n = 1$; $Z = 0$ or NR3 only, and Y, not coordinated to the lanthanide metal, is CT, or CS, or ST, or ST2.

51. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula 1, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

52. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

53. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

54. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

55. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

56. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

57. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

~~58.~~ Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

59. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

60. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 0$; $n = 1$ and $Z = 0$, Y is NR3.

61. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR3R4$, and $Z = 0$.

62. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR3R4$, and $Z = 0$.

63. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR3R4$, and $Z = 0$.

64. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR3R4$, and $Z = 0$.

65. Claims: 1-16 (in part)

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

66. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

67. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

68. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

69. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

70. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula I, claim 1, wherein: $m = 1$, $X = 0$, $n = 1$, $Y = CR_3R_4$, and $Z = 0$.

71. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

ligand complexes of group 3 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

72. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 4 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

73. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 5 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

74. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 6 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

75. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 7 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

76. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 8 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

77. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 9 of the Periodic Table of

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

78. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 10 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

79. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of group 11 of the Periodic Table of Elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

80. Claims: 1-16 (in part)

The subject matter of claims 1-16 insofar as they relate to ligand complexes of the lanthanide elements wherein the ligand is defined according to formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.

81. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the ligand is defined according to formula XIX, claim 16, wherein R52 is additionally a functional group.

82. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the ligand is defined according to formula XVII, claim 16.

83. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the ligand is defined according to formula XIV, claim 16.

84. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the ligand is defined according to formula XV, claim 16, wherein the

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

heteroatom is O, S, or N.

85. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the complex is H1, as depicted on p. 165 of the present application.

86. Claims: 13-16 (in part)

The subject matter of claims 13-16 wherein the complex is H2, as depicted on p. 165 of the present application.

87. Claim : 17

The subject matter of claim 17.

88. Claim : 18

The subject matter of claim 18.

89. Claim : 19

The subject matter of claim 19.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

Continuation of Box I.2

Claims Nos.: 1-16 (in part)

Present claims 1-19 relate to an extremely large number of compounds and processes. Support within the meaning of Article 6 PCT and disclosure within the meaning of Article 5 PCT is to be found, however, for only a very small proportion of compounds and processes claimed. In the present case, the claims so lack support, and the application so lacks disclosure, that a meaningful search over the whole of the claimed scope is impossible. In particular, claims 1-8 alone claim complexes of 27 transition metals plus the lanthanide elements with monoanionic ligands comprising phosphorus. With so few limitations available with regards to search criteria, these claims therefore encompass millions of permutations.

Furthermore, there appears to be an unclarity in claim 1, formula I, in which the term "Y=CT" may possibly be missing, as evidenced by the following observations 1-3:

1. Claim 4, p.177, 1.28, 1.32: "Y is CR11R12, R11 and R12 taken together are oxo": this cannot depend on ligand I of claim 1 as therein "Y = CR11R12". Thus, in order for CR11R12 to represent the "oxo" group of C=O, R11 and R12 must be joined together (p.176, 1.23-25), but one of R11 must be a functional group (in this case, oxygen) and the other must be a covalent bond. This covalent bond has not been specified in claim 1. Alternatively speaking, the term "Y=CT" appears to be missing.
2. Claim 5, p.179, 1.22: point 1 applies here also, wherein the term "Y is C(0)" means that this claim cannot depend on claim 1.
3. Claim 8, p.180, 1.25-26: point 1 applies here also, wherein the term "Y is CR11R12, R11 and R12 taken together are oxo" means that this claim cannot refer back to claim 1.

The result of this unclarity is that many of the examples of the present application are not encompassed by the claims. Furthermore, many other examples are also not embraced by the claims but in these cases this discrepancy cannot be correlated to an unclarity in the claims. Consequently, the search has been carried out for those parts of the claims which appear to be supported and disclosed, namely those parts of claims 1-16 insofar as they relate to complexes as depicted in:

1. Formula I, claim 1, in which the following restrictions apply: $m = 0$; $n = 0-2$; $Y = CR3R4$; $Z = O, S$ or $NR3$.
2. Compounds falling under item 1 above in which additionally Z may be linked to a light metal or boron compound.
3. Formula I, claim 1, in which the following restrictions apply: $m = 0$; $n = 1$ and $Z = O$ or $NR3$ only; Y; not coordinated to the transition or lanthanide metal, is CT, or CS, or ST, or ST2.
4. Formula I, claim 1, in which the following restrictions apply: $m = 0$; $n = 1$ and $Z = O$, Y is $NR3$.

FURTHER INFORMATION CONTINUED FROM PCT/ISA/ 210

5. Formula I, claim 1, in which the following restrictions apply: $m = 1$, $X = O$, $n = 1$, $Y = CR_3R_4$, and $Z = O$.
6. Formula II, claim 1, wherein N, coordinated to the transition or lanthanide metal, can also be replaced by O.
7. Formula XIX, claim 16, wherein R52 is additionally a functional group.
8. Formula XVII, claim 16.
9. Formula XIV, claim 16.
10. Formula XV, claim 16, where the heteroatom is O, S or N only.
11. H1, as depicted on p. 165.
12. H2, as depicted on p. 165.

Such constructs were made based on the original claims in order to encompass all examples of the present application.

The applicant's attention is drawn to the fact that claims, or parts of claims, relating to inventions in respect of which no international search report has been established need not be the subject of an international preliminary examination (Rule 66.1(e) PCT). The applicant is advised that the EPO policy when acting as an International Preliminary Examining Authority is normally not to carry out a preliminary examination on matter which has not been searched. This is the case irrespective of whether or not the claims are amended following receipt of the search report or during any Chapter II procedure.

Patent document cited in search report	Publication date	Patent family member(s)	Publication date
WO 9830609	A	16-07-1998	
		AU 734651 B2	21-06-2001
		AU 5915098 A	03-08-1998
		BR 9806894 A	21-03-2000
		EP 0952997 A1	03-11-1999
		HU 0001341 A2	28-07-2000
		JP 2000514132 T	24-10-2000
		NO 993295 A	01-09-1999
		PL 334836 A1	27-03-2000
		TR 9901645 T2	21-04-2000
		WO 9830609 A1	16-07-1998

THIS PAGE BLANK (USPTO)